

# **RULES**

## **FOR THE CLASSIFICATION AND CONSTRUCTION OF SEA-GOING SHIPS**

### **PART III**

#### **EQUIPMENT, ARRANGEMENTS AND OUTFIT**

ND No. 2-020101-152-E



**St. Petersburg**  
**2022**

# **RULES FOR THE CLASSIFICATION AND CONSTRUCTION OF SEA-GOING SHIPS**

---

Rules for the Classification and Construction of Sea-Going Ships of Russian Maritime Register of Shipping have been approved in accordance with the established approval procedure and come into force on 1 January 2022 (except for Part XX which came into force on 15 March 2022).

The present edition of the Rules is based on the 2021 edition taking into account the amendments and additions developed immediately before publication.

The procedural requirements, unified requirements, unified interpretations and recommendations of the International Association of Classification Societies (IACS) and the relevant resolutions of the International Maritime Organization (IMO) have been taken into consideration.

The Rules are published in the following parts:

- Part I "Classification";
- Part II "Hull";
- Part III "Equipment, Arrangements and Outfit";
- Part IV "Stability";
- Part V "Subdivision";
- Part VI "Fire Protection";
- Part VII "Machinery Installations";
- Part VIII "Systems and Piping";
- Part IX "Machinery";
- Part X "Boilers, Heat Exchangers and Pressure Vessels";
- Part XI "Electrical Equipment";
- Part XII "Refrigerating Plants";
- Part XIII "Materials";
- Part XIV "Welding";
- Part XV "Automation";
- Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships";
- Part XVII "Distinguishing Marks and Descriptive Notations in the Class Notation Specifying Structural and Operational Particulars of Ships";
- Part XVIII "Additional Requirements for Structures of Container Ships and Ships, Dedicated Primarily to Carry their Load in Containers". The text of the Part is identical to IACS UR S11A "Longitudinal Strength Standard for Container Ships" (June 2015) and S34 "Functional Requirements on Load Cases for Strength Assessment of Container Ships by Finite Element Analysis" (May 2015);
- Part XIX "Additional Requirements for Cargo Ships of Less Than 500 Gross Tonnage";
- Part XX "Additional Requirements for Yachts";
- Supplement to Rules and Guidelines of Russian Maritime Register of Shipping "IACS Procedural Requirements, Unified Requirements, Unified Interpretations and Recommendations".

## REVISION HISTORY<sup>1</sup>

(purely editorial amendments are not included in the Revision History)

Amended paras/chapters/ sections	Information on amendments	Number and date of the Circular Letter	Entry-into-force date
<a href="#">Annotation</a>	Annotation has been amended in connection with issuing new Part XX. Annotation has been specified due to renaming of Part XX	— 312-09-1747c of 14.04.2022	15.03.2022 14.04.2022
<a href="#">Para 2.1.3</a>	Reference to IACS UR S10 (Rev.6 Sep 2019) has been specified	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 2.9.12</a>	Requirement for arrangement of rudder stops has been specified	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 3.1.1</a>	Editorial amendment of 07.03.2023: terms of application of the requirements have been specified	—	01.11.2022
<a href="#">Table 3.1.3-1</a>	Footnote has been specified	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 3.2.1</a>	Para has been amended considering IACS UR A1 (Rev.7 Corr.1 Sep 2021)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 3.2.3</a>	Para has been amended considering IACS UR A1 (Rev.7 Corr.1 Sep 2021)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Paras 3.2.5 — 3.2.5.3</a>	Reference to IACS recommendation has been replaced by reference to the applicable requirements of these Rules; new paras 3.2.5.1 — 3.2.5.3 have been introduced considering IACS recommendation No. 10 (Rev.4 Sep 2020)	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 3.6.4.3</a>	Para has been amended considering IACS UR L4 (Rev.3 Corr.2 Feb 2022)	314-18-1830c of 30.09.2022	01.11.2022
<a href="#">Para 4.1.1</a>	Editorial amendment of 07.03.2023: terms of application of the requirements have been specified	—	01.11.2022
<a href="#">Paras 4.1.3 — 4.1.3.3</a>	Reference to IACS recommendation has been replaced by reference to the applicable requirements of these Rules; new paras 4.3.1.1 — 4.1.3.3 have been introduced considering IACS recommendation No. 10 (Rev.4 Sep 2020)	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 4.3.1</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 4.3.4.1</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022

<sup>1</sup> Amendments and additions introduced at re-publication or by new versions based on circular letters or editorial amendments.

Amended paras/chapters/sections	Information on amendments	Number and date of the Circular Letter	Entry-into-force date
<a href="#">Para 4.3.4.4</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020). Editorial amendment: Figure and references thereto have been renumbered in accordance with the Russian version	314-18-1672c of 30.11.2021 —	01.01.2022 01.01.2022
<a href="#">Para 4.3.5</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020). Editorial amendment: text has been aligned with the corresponding text in IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021 —	01.01.2022 01.01.2022
<a href="#">Para 4.3.6</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 4.5.2</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 5.1.4</a>	Editorial amendment of 07.03.2023: terms of application of the requirements have been specified	—	01.11.2022
<a href="#">Para 5.3.4</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 5.3.7</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020). Editorial amendment: reference to the applicable requirements has been specified	314-18-1672c of 30.11.2021 —	01.01.2022 01.01.2022
<a href="#">Para 5.3.8.1</a>	Para has been amended considering IACS UR A2 (Rev.5 Sep 2020)	314-18-1672c of 30.11.2021	01.01.2022
<a href="#">Para 7.2.1.1</a>	Requirement for thickness of side scuttle glasses has been specified	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 7.2.1.10</a>	Requirements for ships having a distinguishing mark for a ship carrying equipment for fire fighting aboard other ships in the class notation have been specified due to introduction of distinguishing mark <b>FF3</b>	313-14-1728c of 29.03.2022	01.07.2022
<a href="#">Para 7.2.2.4</a>	Requirements for type of side scuttle glasses has been specified	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 7.2.2.6</a>	Requirement for thickness of side scuttle glasses has been specified	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 7.10.2.1</a>	Requirement for fishing vessels has been rearranged as a separate paragraph	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 7.10.2.2</a>	Requirement regarding submission of technical background for reduction of the coamings height has been specified	314-18-1761c of 18.05.2022	15.06.2022

Amended paras/chapters/sections	Information on amendments	Number and date of the Circular Letter	Entry-into-force date
<a href="#">Para 7.10.6.34</a>	Reference to the applicable requirements of these Rules has been specified	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 7.12.4.2</a>	Requirement for doors has been specified in accordance with SOLAS regulation II-1/13-1	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 7.14.2</a>	Reference to IACS UI SC191 (Rev.8 Apr 2019) has been specified	314-18-1738c of 11.04.2022	01.05.2022
<a href="#">Para 8.5.4.3</a>	Requirement for the angle of slope of fishing vessels has been specified. Requirement for number of stairway handrails has been specified	314-18-1677c of 06.12.2021 314-18-1761c of 18.05.2022	01.01.2022 15.06.2022
<a href="#">Para 9.1.1</a>	Application of requirements for emergency outfit has been specified	314-18-1761c of 18.05.2022	15.06.2022
<a href="#">Para 9.2.12</a>	Requirements for ships having a distinguishing mark for a ship carrying equipment for fire fighting aboard other ships in the class notation have been specified due to introduction of distinguishing mark <b>FF3</b>	313-14-1728c of 29.03.2022	01.07.2022

## **1 GENERAL**

### **1.1 APPLICATION**

**1.1.1** The requirements of this Part apply to equipment, arrangements and outfit of sea-going ships navigating in a displacement condition. To hydrofoil boats, air cushion vehicles, hydrogliders and other similar ships, unless expressly provided otherwise below, the requirements of this Part are applicable to the extent that is practicable and reasonable.

**1.1.2** Ship's equipment, arrangements and outfit designed for special purposes (such as special anchor arrangements of dredgers, a deep-sea anchor arrangement for special purpose ships and similar arrangements) are not subject to the Register supervision.

**1.1.3** The requirements of this Part apply, as far as practicable and reasonable, to floating metallic wing-walled docks, unless expressly provided otherwise. These Rules do not specify conditions for mooring of floating docks in a particular place of operation and selection of types and characteristics of the equipment, arrangements and outfit (anchor, mooring, etc.) used for this purpose.

## 1.2 DEFINITIONS AND EXPLANATIONS

The definitions and explanations relating to the general terminology of these Rules are given in Part I "Classification".

For the purpose of this Part the following definitions have been adopted:

### 1.2.1 Waterlines.

Damage waterlines are the waterlines of a damaged ship after flooding of corresponding separate compartments or their combinations as provided in Part V "Subdivision".

Summer load waterline is the waterline indicated by the upper edge of the line which passes through the centre of the ring of the load line mark for a ship in upright position.

Summer timber load waterline is the waterline indicated by the upper edge of the assigned summer timber load line.

Deepest load waterline is the waterline indicated by the upper edge of the assigned uppermost regional or seasonal load line, including fresh water load lines.

Deepest subdivision load waterline is the uppermost waterline at which the requirements of Part V "Subdivision" are still fulfilled.

Margin line at docking is the envelope of the waterlines corresponding to the maximum permitted trims of the floating docks and docklift ships when carrying out the docking operations.

### 1.2.2 Dimensions and draught of the ship.

Length of ship  $L$  is taken as 96 % of the total length on a waterline at 85 % of the least moulded depth or as the length from the fore side of the stem to the axis of the rudder stock on that waterline, if that be greater.

Where the stem contour is concave above that waterline, the length of the ship shall be measured from the vertical projection to that waterline of the aftermost point of the stem contour (above that waterline).

In ships designed with a rake of keel the waterline on which this length is measured shall be parallel to the design waterline.

Length of floating dock  $L$  is the distance measured along the pontoon deck and parallel to the base line, between the inner sides of the pontoon end bulkheads.

Moulded draught  $d$  is the vertical distance measured amidships from the top of the plate keel or from the point where the inner surface of the shell (outer surface in a ship with a non-metal shell) abuts upon the bar keel, to the summer load waterline.

Moulded depth  $D$  is the vertical distance measured amidships from the top of the plate keel, or from the point where the inner surface of the shell abuts upon the bar keel, to the top of the freeboard deck beam at side.

In ships having rounded gunwales, the moulded depth shall be measured to the point of intersection of the moulded lines of the freeboard deck and side, the lines extending as though the gunwale were of angular design.

Where the freeboard deck is stepped in the longitudinal direction and the raised part of the deck extends over the point at which the moulded depth shall be determined, the moulded depth shall be measured to a line of reference extending from the lower part of the deck along a line parallel with the raised part.

Moulded breadth  $B$  is the maximum breadth measured amidships from outside of frame to outside of frame in a ship with a metal shell and to the outer surface of the hull in a ship with a shell of any other material.

### 1.2.3 Superstructures, deckhouses.

**Superstructure** is a decked structure on the freeboard deck, extending from side to side of the ship or with the side plating not being inboard of the shell plating more than 4 % of the breadth  $B$ .

The superstructure may be either complete, i.e. extending over the entire ship's length  $L$ , or detached, i.e. extending only over a definite part of this length. Both complete and detached superstructures may be arranged either in a single or several tiers.

**Deckhouse** is a decked structure on the freeboard or superstructure deck which is set in from the sides of the ship for more than 4 % of the breadth  $B$  and has doors, windows or other similar openings in the outer bulkheads. The deckhouses may be arranged in a single or several tiers.

**Trunk** is a decked structure on the freeboard deck which is set in from the sides of the ship for more than 4 % of the breadth  $B$  and has no doors, windows or other similar openings in the outer bulkheads.

### 1.2.4 Tightness.

**Tight under pressure head up to...** is the term pertaining to closing appliances of openings, which means that under specified pressure the liquid will not penetrate through the openings inside the ship.

**Weathertight** is the term pertaining to closing appliances of openings in the above-water hull, which means that in any sea conditions water will not penetrate through the openings inside the ship. The above closing appliances shall undergo tests according to the requirements of 4.4.3, Appendix 1 to Part II "Hull".

It is allowed that the specialized organizations recognized by the Register carry out tests by means of the ultrasonic equipment as well as other test methods approved by the Register.

### 1.2.5 Decks.

**Upper deck** is the uppermost continuous deck extending for the full length of the ship.

The upper deck may be stepped.

**Raised quarter deck** is the after upper part of a stepped deck, the forward lower part of which is taken as a portion of the freeboard deck.

**Freeboard deck** is the deck from which the freeboard is measured.

In a ship having a discontinuous deck the lowest line of this deck and the continuation of that line parallel to upper part of the deck is taken as a freeboard deck.

**Superstructure deck, deckhouse top or trunk deck** is the deck forming the top of a superstructure, deckhouse or trunk, respectively.

**Superstructure deck or deckhouse top of the first, second, etc. tiers** is the deck forming the top of the superstructure or deckhouse of the first, second, etc. tiers, counting from the freeboard deck.

**Bulkhead deck** is the deck up to which the main transverse watertight subdivision bulkheads are carried.

The bulkhead deck may be discontinuous, i.e. with a step or steps formed both by main transverse watertight bulkheads reaching the keel and transverse watertight bulkheads not reaching the keel.

**Weather deck** is the deck which is completely exposed to the weather from above and from at least two sides.

**Lower decks** are the decks below the upper deck.

**Pontoon deck of the dock** is the deck on which the ship to be docked is fitted.

**Top deck of the dock** is the uppermost deck of the dock (the uppermost deck of the wing walls).



#### **1.2.6 Perpendiculars and amidships.**

Amidships is at the middle of the ship's length  $L$ .

Forward and after perpendiculars are the vertical lines passing in the centreline at the fore and after ends of the ship's length  $L$ , respectively.

#### **1.2.7 Ships.**

Type "A" ship is a ship designed to carry only liquid cargoes in bulk, and in which cargo tanks have only small access openings closed by gasketed covers tight under an appropriate inner pressure of liquid which is carried in the tanks. Furthermore, a type "A" ship shall have some other features, as defined in the Load Line Rules for Sea-Going Ships which permit this ship to be assigned a freeboard based on Tables 4.1.2.3, 6.4.2.2 or 6.4.3.2 of the above Rules.

Type "B" ship is a ship which does not comply with the requirements regarding type "A" ships and which is assigned a freeboard based on Table 4.1.3.2, 6.4.2.3 or 6.4.3.3 of the Load Line Rules for Sea-Going Ships.

A type "B" ship may not be classified as a type "A" ship even though, as a result of her features detailed in the Load Line Rules, a reduction in tabular freeboard is permitted up to the total difference between the values given in Tables 4.1.2.3, 6.4.2.2, 6.4.3.2 and those in Tables 4.1.3.2, 6.4.2.3, 6.4.3.3, respectively, of the above Rules.

Docklift ship is a dry cargo ship adapted to carry out cargo handling operations using the docking principle in ports and protected water areas.

#### **1.2.8 Active means of the ship's steering.**

Active means of the ship's steering (AMSS) are special propulsion and steering units and any combination of them or with the main propulsion devices, capable of producing thrust or traction force both at a fixed angle to the centreline of the ship and at a variable angle, either under all running conditions or part thereof including small and zero speed.

The active means of the ship's steering comprise steerable propellers including retractable units of all types, active rudders, vertical-axis propellers, waterjets, propellers in transverse tunnel (athwartship thrusters), separate steering nozzles and other devices of similar purpose.

#### **1.2.9 Steering gear.**

Main steering gear is the machinery, rudder actuators, steering gear power units, if any, ancillary equipment and the means of applying torque to the rudder stock (e.g. tiller or quadrant) necessary for effecting movement of the rudder for the purpose of steering the ship under normal service conditions.

Auxiliary steering gear is the equipment other than any part of the main steering gear necessary to steer the ship in the event of failure of the main steering gear, but not including the tiller, quadrant or components serving the same purpose.

Steering gear power unit is:

in the case of electric steering gear an electric motor and its associated electrical equipment;

in the case of electrohydraulic steering gear an electric motor and its associated equipment and connected pump;

in the case of other hydraulic steering gear a driving engine and connected pump.

Power actuating system is the hydraulic equipment provided for supplying power to turn the rudder stock, comprising a steering gear power unit or units, together with the associated pipes and fittings, and a rudder actuator. The power actuating systems may share common mechanical components, i.e. tiller, quadrant and rudder stock, or components serving the same purpose.

Steering gear control system is the equipment by which orders are transmitted from the navigation bridge to the steering gear power units. Steering gear control systems comprise transmitters, receivers, hydraulic control pumps and their associated motors, motor controllers, piping and cables.

### 1.3 SCOPE OF SURVEY

**1.3.1** General provisions on survey of ship's equipment, arrangements and outfit are given in General Regulations for the Classification and Other Activity and in Part I "Classification".

**1.3.2** The following items included into ship's equipment, arrangements and outfit are subject to the survey by the Register during their manufacture.

**1.3.2.1** Rudder and steering gear:

- .1 rudder stocks;
- .2 rudder blade;
- .3 steering nozzles;
- .4 rudder axles;
- .5 pintles of rudders and steering nozzles;
- .6 bushes of pintles;
- .7 fastenings of rudder stocks, rudder stock with rudder blade or steering nozzle, and also of rudder axle with sternframe (muff couplings, keys, bolts, nuts, etc.);
- .8 parts of the system of rudder stops;
- .9 rudder stock bearings;
- .10 active means of the ship's steering (only in the case specified in [2.1.4.2](#)).

**1.3.2.2** Anchor arrangement:

- .1 anchors;
- .2 chain cables or ropes;
- .3 anchor stoppers;
- .4 devices for securing and releasing the inboard end of chain cable or rope;
- .5 anchor hawse pipes.

**1.3.2.3** Mooring arrangement:

- .1 mooring lines;
- .2 mooring bollards, belaying cleats, fairleaders, chocks and rollers.

**1.3.2.4** Towing arrangement:

- .1 tow lines;
- .2 towing bollards, bitts, fairleaders, chocks and stoppers;
- .3 tow hooks and towing rails with fastenings for their securing to ship's hull;
- .4 towing snatch-blocks.

**1.3.2.5** Masts and rigging:

- .1 metal, wooden and fiber-reinforced plastic spars;
- .2 standing ropes;
- .3 permanent attachments to masts and decks (eyeplates, hoops, etc.);
- .4 loose gear of masts and rigging (shackles, turnbuckles, etc.).

**1.3.2.6** Closing appliances of openings in hull, superstructures and deckhouses:

- .1 side and deck scuttles;
- .2 doors of bow, side and stern openings in the shell plating;
- .3 doors in superstructures and deckhouses;
- .4 companion hatches, skylights and ventilating trunks;
- .5 ventilators;
- .6 manholes to deep and other tanks;
- .7 hatchway covers in dry cargo ships and tankers;
- .8 cargo tank hatchway covers in tankers;
- .9 doors in subdivision bulkheads.

**1.3.2.7** Equipment of ship's spaces:

- .1 ceiling and battens in cargo holds;
- .2 exit doors from ship's spaces in escape routes;

- .3 stairways and vertical ladders;
- .4 guard rails, bulwark and gangways;
- .5 cellular guide members in the holds of container ships.

**1.3.2.8** Emergency outfit:

- .1 collision mats;
- .2 tools;
- .3 materials.

**1.3.3** The Register survey of the manufacture of items specified in [1.3.2.1.7](#), [1.3.2.1.8](#), [1.3.2.5](#), [1.3.2.7.1](#), [1.3.2.7.5](#), [1.3.2.8.2](#) and [1.3.2.8.3](#) is confined to consideration of the relevant technical documentation.

**1.3.4** For items specified in [1.3.2](#) the following documents shall be submitted to the Register:

- .1 assembly drawing;
- .2 detail drawings if parts or assemblies are not manufactured in accordance with standards and specifications approved by the Register.

**1.3.5** Materials used for items specified in [1.3.2.1.1 — 1.3.2.1.5](#), [1.3.2.2.1](#), [1.3.2.2.2](#), [1.3.2.4.3](#), [1.3.2.6.2](#) and [1.3.2.6.7 — 1.3.2.6.9](#) are subject to the Register survey during manufacture.

**1.3.6** The following equipment, arrangements and outfit are subject to the Register survey when the ship is under construction:

- .1 rudder and steering gear;
- .2 anchor arrangement;
- .3 mooring arrangement;
- .4 towing arrangement;
- .5 masts and rigging;
- .6 openings in hull, superstructures and deckhouses and their closing appliances;
- .7 arrangement and equipment of ship's spaces;
- .8 emergency outfit;
- .9 cellular guide members in the holds of container ships;
- .10 active means of the ship's steering ([refer to 2.1.4](#)).

## **1.4 GENERAL**

**1.4.1** In ships intended to carry in bulk flammable liquids with the flash point 60 °C and below no deck machinery shall be fitted directly on the decks being the top of cargo and fuel tanks. In this case, the deck machinery shall be fitted on special foundations, the construction of which provides for free circulation of air underneath the machinery.

**1.4.2** Towing and mooring arrangements plan containing the relevant information shall be available on board for the guidance of the master. The information provided on the plan in respect of shipboard equipment shall include:

- type and location on the ship;

- safe working load (*SWL*);

- purpose (mooring/harbour towing/escort service);

- manner of applying tow line or mooring line load including limiting fleet angles.

Also the number of mooring lines together with the breaking strength of each mooring line shall be indicated on the plan.

This information shall be incorporated into the pilot card in order to provide the pilot with the proper information on harbour operations/escort service.

## **1.5 WORKING AND ALLOWABLE STRESSES**

**1.5.1** Wherever the working stresses are mentioned in the text of the present Part of the Rules, they mean equivalent stress(es)  $\sigma_{eq}$ , in MPa, determined by the formula

$$\sigma_{eq} = \sqrt{\sigma^2 + 3\tau^2} \quad (1.5.1)$$

where  $\sigma$  = normal stresses in the section under consideration, in MPa;  
 $\tau$  = shear stresses in the section under consideration, in MPa.

The strength conditions shall be checked against these stresses.

**1.5.2** Allowable stresses with which the combined stresses shall be compared when verifying the strength conditions are specified in the present Part in fractions of the upper yield stress of the material used; the upper yield stress shall not be taken as more than 0,7 times the tensile strength of this material, unless expressly provided otherwise.

## **1.6 MATERIALS AND WELDING**

**1.6.1** Steel forgings and castings, steel plates, sections and bars and also chain steel used for items specified in [1.3.2.1.1 — 1.3.2.1.5](#), [1.3.2.1.7](#), [1.3.2.2.1](#), [1.3.2.2.2](#), [1.3.2.4.3](#), [1.3.2.6.2](#), [1.3.2.6.7](#) and [1.3.2.6.9](#) shall meet the relevant requirements of Part XIII "Materials". Materials for other items of equipment, arrangements and outfit shall meet the requirements specified in the design documentation approved by the Register, unless expressly provided otherwise in these Rules.

**1.6.2** The grades of steel plates and sections (refer to Tables 3.2.2-1 and 3.2.2-2 of Part XIII "Materials") for items specified in [1.3.2.1.2](#) and [1.3.2.1.3](#) shall be selected according to 1.2.3.1 of Part II "Hull" in the same manner as for hull structural members of category II; in this case, for ships of ice class **Arc4** and higher and for icebreakers steel not lower than Grade B shall be adopted, and for rudder blades of icebreakers, not lower than Grade D. For items specified in [1.3.2.6.2](#) the grades of steel plates and sections of the main carrying framing members and plating of cover structures ensuring fixing of items when stowed for sea, as well as essential parts of drivers intended for opening at sea shall be selected according to 1.2.3.1 of Part II "Hull" as for hull structural members of category II.

**1.6.3** Welding of structural elements of ship's equipment, arrangements and outfit shall be performed in accordance with the requirements of Part XIV "Welding"; besides, welded structures and joints of items specified in [1.3.2.6.2](#), [1.3.2.6.7](#) and [1.3.2.6.9](#) shall comply with the applicable requirements of 1.7 of Part II "Hull".

## 1.7 DESIGN ACCELERATIONS DUE TO HEAVE OF THE SEA

**1.7.1** The dimensionless, gravity related, design accelerations due to heave of the sea as described in this Chapter shall be applied when determining the loads upon equipment, arrangements and batches of cargo items carried by ships of unrestricted service and those of restricted area of navigation **R1**.

With regard to ships of other areas of navigation, accelerations may be applied different from those required herein which shall be substantiated by calculations approved by the Register.

**1.7.2** The dimensionless acceleration  $a_z$  due to heave, pitch and roll normal to the water planes of the ship shall be determined by the formula

$$a_z = \pm a_0 \sqrt{1 + \left(5,3 - \frac{45}{L}\right)^2 \left(\frac{x}{L} - 0,45\right)^2 \left(\frac{0,6}{C_B}\right)^{3/2}} \quad (1.7.2-1)$$

$$\text{where } a_0 = 0,2 \frac{v}{\sqrt{L}} + \frac{34 - 600/L}{L}; \quad (1.7.2-2)$$

$v$  = maximum ahead speed, in knots, with the ship on summer load waterline on still water;

$L$  = ship's length, in m;

$x$  = longitudinal distance from the centre of gravity of equipment, arrangement or batch of cargo items in question to the aft perpendicular;

$C_B$  = block coefficient.

$a_z$  does not include the component of the static weight.

**1.7.3** The dimensionless acceleration  $a_y$  due to transverse displacement, yaw and roll normal to the centreline of the ship shall be determined by the formula

$$a_y = \pm a_0 \sqrt{0,6 + 2,5 \left(\frac{x}{L} - 0,45\right)^2 + k_1 \left(1 + 0,6 k_1 \frac{z}{B}\right)^2} \quad (1.7.3-1)$$

where  $k_1$  = coefficient of stability to be determined by the formula

$$k_1 = \frac{13 \overline{GM}}{B}. \quad (1.7.3-2)$$

If  $k_1$  as determined by [Formula \(1.7.3-2\)](#), is below 1,0,  $k_1=1,0$  shall be assumed for calculating  $a_y$ ;

$\overline{GM}$  = transverse metacentric height of loaded ship when the volume and distribution of stores are such as to yield maximum  $\overline{GM}$ , in m;

$B$  = ship's breadth, in m;

$z$  = vertical distance, in m, from the summer load waterline to the centre of gravity of equipment, arrangement or batch of cargo items in question;  $z$  is positive above and negative below the summer load waterline.

$a_y$  includes the component of the static weight in the transverse direction due to rolling.

**1.7.4** The dimensionless acceleration  $a_x$  due to longitudinal displacement and pitch normal to the midship section plane shall be determined by the formula

$$a_x = +a_0 \sqrt{0,06 + k_2^2 - 0,25 k_2} \quad (1.7.4-1)$$

where  $k_2$  = factor determined from the formula

$$k_2 = \left(0,7 - \frac{L}{1200} + 5 \frac{z}{L}\right) \frac{0,6}{C_B}. \quad (1.7.4-2)$$

$a_x$  includes the component of the static weight in the longitudinal direction due to pitching.

**1.7.5** When determining loads it shall be considered that the accelerations calculated using  $a_x$ ,  $a_y$  and  $a_z$  act independently of each other.

## 2 RUDDER AND STEERING GEAR

### 2.1 GENERAL

**2.1.1** Every ship, except for shipborne barges, shall be provided with a reliable device ensuring her steering and course-keeping facilities ([refer to 2.10](#)). Such devices may be rudder, steering nozzle, etc., approved by the Register.

For non-propelled vessels of the dredging fleet with regard to the area of navigation and service conditions it may be allowed to omit such device or provide only stabilizers.

**2.1.2** The requirements of this Section apply only to ordinary streamlined rudders or steering nozzles with streamlined profiles and rigidly fixed stabilizers.

**2.1.3** Steering gears may be designed compliant to IACS unified requirement (UR) S10 (Rev.6 Sept 2019) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)).

**2.1.4 Active means of the ship's steering.**

**2.1.4.1** The active means of the ship's steering may be both the means supplementary to the regulated minimum ([refer to 2.1.1](#)) and the main means of the ship's steering.

**2.1.4.2** Taking into account the ship's purpose, design features and intended service conditions it may be permitted that the regulated steerability of the ship shall be provided at the low speed by simultaneous operation of the devices specified in [2.1.1](#) and the active means of the ship's steering.

In case where the AMSS are the main means of the ship's steering the regulated steerability shall be ensured under those running conditions of the ship for which the means are intended.

In any case, it shall be demonstrated by the method recognized by the Register that the steerability will not then be at least worse than that ensured in case of fulfilment of the requirements of [2.10](#).

**2.1.4.3** Requirements for AMSS construction and design, exclusive of the separate steering nozzles and rudder section of the active rudders are outlined in Part VII "Machinery Installations". Requirements for AMSS used in the dynamic positioning systems of mobile offshore drilling units shall be fulfilled with consideration for Rules for the Classification and Construction of Mobile Offshore Drilling Units.

**2.1.5** The number of rudder pintles supporting the rudder is not regulated by the Register. For icebreakers and ships of ice class **Arc4** and higher, the recommended number of rudder pintles is given in [Table 2.1.5](#).

Table 2.1.5

Ice class	Number of rudder pintles
<b>Icebreaker9</b> and <b>Icebreaker8</b>	4
<b>Icebreaker7</b> , <b>Icebreaker6</b> , <b>Arc9</b> , <b>Arc8</b> and <b>Arc7</b>	3
<b>Arc6</b> and <b>Arc5</b>	2
<b>Arc4</b>	1

In any case, the strength of the rudder structure in ice class ships shall be verified by the appropriate calculations for a ship operating in the specified ice conditions.

In icebreakers and **Arc7**, **Arc8** and **Arc9** ice class ships the steering nozzles shall not be fitted.

In ships of ice classes **Arc4**, **Arc5** and **Arc6** the arrangement of the steering nozzles without the lower pintle in the solepiece is not permitted.

**2.1.6** Wherever the upper yield stress  $R_{eH}$  of the material used enters into the formulae of this Section, the provisions of [1.5.2](#) shall be taken into account, but in all cases the upper yield stress  $R_{eH}$  of the material shall not be taken more than 390 MPa.



**2.1.7** When checking the rudder or steering nozzle pintles and rudder stock bearings for surface pressure, the latter shall not exceed the values indicated in [Table 2.1.7](#).

Table 2.1.7

Materials	Surface pressure $p$ , in MPa	
	Water lubrication	Oil lubrication
Stainless steel or bronze against lignum vitae	2,4	—
Stainless steel or bronze against textolite or synthetic materials	On agreed manufacture's specification	—
Stainless steel against bronze or vice versa	6,9	—
Steel against white metal	—	4,4

**2.1.8** In ships of ice classes **Arc5** and **Arc6** the arrangement of two steering nozzles (in case of twin-screw ships) shall be verified by strength calculation as well as by taking measures to ensure protection against ice impact.

**2.1.9** In ships of ice class **Arc4** and higher the measures to ensure protection of steering nozzles against ice impact shall be submitted by the designer.

**2.1.10** For passenger ships and special purpose ships carrying more than 60 persons having length of 120 m or more or having three or more main vertical zones, the steering gear shall comply with the requirements of 2.2.6.8 of Part VI "Fire Protection" (refer also to 2.2.6.7.2 of the above Part).

## 2.2 INITIAL DESIGN DATA

**2.2.1** The initial design data specified in this Chapter are valid only for the choice of scantlings of ordinary rudders and steering nozzles with rigidly fixed stabilizers and cannot be used for determination of steering gear output characteristics. Methods of determination of these characteristics are not regulated by the Register, and the relevant calculations are not subject to approval by the Register. The steering gear is checked by the Register during sea trials of the ship to make sure that the steering gear output characteristics comply with the requirements of [2.9.2](#), [2.9.3](#) and [2.9.8](#).

### 2.2.2 Rudder force and rudder torque.

**2.2.2.1** The rudder blade force  $F$ , in kN, for the ahead condition shall be determined by the formula

$$F = F_1 + F_2 \quad (2.2.2.1-1)$$

$$\text{where } F_1 = 5,59 \cdot 10^{-3} k_1 k_2 (6,5 + \lambda) (b_1 - C_B)^2 A v^2; \quad (2.2.2.1-2)$$

$$F_2 = 0,177 k_1 (6,5 + \lambda) \frac{T}{D_p^2} A_p \quad (2.2.2.1-3)$$

where  $k_1$  = factor equal to:

1,0 for rectangular and trapezoidal rudders, except for rudders behind the rudder post;

0,95 for semispade rudders (rudders of types I, II, VII and VIII in [Fig. 2.2.4.1](#));

0,89 for rudders behind the rudder post (rudders of types IV, X and XIII in [Fig. 2.2.4.1](#));

$k_2$  = factor equal to:

1,0 for rudders operating directly behind the propeller;

1,25 for rudders not operating directly behind the propeller;

$\lambda$  = value determined by the formula

$$\lambda = h_r^2 / A_t \quad (2.2.2.1-4)$$

where  $h_r$  = mean height of the rudder blade part abaft the centreline of the rudder stock, in m;

$A_t$  = sum of the rudder area and lateral area of the rudder horn or rudder post, if any, within the height  $h_r$ , in m<sup>2</sup>. In case of no rudder horn or rudder post, the value of  $A_t$  is taken as  $A$  in the calculations;

$A$  = rudder area, in m<sup>2</sup>;

$A_p$  = portion of the rudder area in the wake of the propeller when the rudder is in the non-reversed position, in m<sup>2</sup>;

$b_1$  = value equal to:

2,2 for rudders situated at the centreline of the ship;

2,32 for side rudders;

$C_B$  = block coefficient with the ship on the summer load waterline;

$v$  = maximum ahead speed with the ship on the summer load waterline, in knots;

$T$  = propeller thrust at the speed  $v$ , in kN, ([refer to 2.2.2.6](#));

$D_p$  = propeller diameter, in m.

**2.2.2.2** The value of the force  $F$  specified in [2.2.2.1](#) shall not be taken less than  $F_3$ , in kN, determined by the formula

$$F_3 = k_3 A \quad (2.2.2.2)$$

where  $k_3$  = factor equal to:

171 — for icebreakers of ice class **Icebreaker9**;

150 — for icebreakers of ice class **Icebreaker8**;

130 — for icebreakers of ice class **Icebreaker7**;

110 — for icebreakers of ice class **Icebreaker6** and for ships of ice class **Arc9**;  
 95 — for ships of ice class **Arc8**;  
 81 — for ships of ice class **Arc7**;  
 75 — for ships of ice class **Arc6**;  
 66 — for ships of ice class **Arc5**;  
 53 — for ships of ice class **Arc4**;  
 18 — for other ships.

When the value of the force  $F_3$  is greater than that of the force  $F$  specified in [2.2.2.1](#), in subsequent calculations the value of  $F_3$  is taken instead of  $F$ , and the value  $F_2$  is taken equal to zero.

**2.2.2.3** For the ahead condition the rudder torque  $M_t$ , in kN·m, shall not be taken less than determined by the formula

$$M_t = F \frac{A}{h_r} (0,35 - \frac{A_1}{A}) \quad (2.2.2.3-1)$$

where  $A_1$  = part of the rudder blade area forward of its centreline, in m<sup>2</sup>.

For single-plate solid-cast rudders with the leading edge aft of the rudder stock centre line,  $A_1$  is taken as the negative value of the area formed by the leading edge of the rudder blade and the rudder stock centre line.

For icebreakers and **Arc4**, **Arc5**, **Arc6**, **Arc7**, **Arc8** and **Arc9** ice class ships the rudder torque  $M_t$ , in kN·m, due to the force  $F_3$  specified in [2.2.2.2](#), shall not be taken less than determined by the formula

$$M_t = 0,35F_3b_r \quad (2.2.2.3-2)$$

where  $b_r$  = distance from the centre line to the rear edge of the rudder blade at the level of the midheight of the rudder blade, in m.

**2.2.2.4** For the astern condition the rudder torque  $M_{as}$ , in kN·m, shall not be taken less than determined by the formula

$$M_{as} = k_4 \frac{A^2}{h_r} (0,7 - \frac{A_1}{A}) v_{as}^2 \quad (2.2.2.4)$$

where  $k_4$  = factor equal to:

0,185 — for rudders operating directly behind the propeller;

0,139 — for rudders not operating directly behind the propeller;

$v_{as}$  = maximum specification speed of the ship for the astern condition, but not less than  $0,5v$ , in knots.

**2.2.2.5** For the astern condition the rudder blade force  $F_{as}$ , in kN, shall be determined by the formula

$$F_{as} = M_{as} \frac{h_r}{A(0,7 - \frac{A_1}{A})} \quad (2.2.2.5)$$

When determining the bending moments and reactions of the supports according to the provisions of [2.2.4 — 2.2.7](#) for the astern condition, the force  $F_{as}$  shall be considered as the force  $F_1$ , and the value of  $F_2$  is then taken equal to zero.

**2.2.2.6** In case reliable data are not available on the value of the propeller thrust mentioned in [2.2.2.1](#), the value of  $T$ , in kN, may be determined by the formulae:

for fixed-pitch propellers

$$T = 0,0441 \left( \frac{30,6N_e}{nH_1 \sqrt[3]{z\theta}} - n^2 D_p^4 \right); \quad (2.2.2.6-1)$$

for controllable-pitch propellers

$$T = 0,0441 \left( \frac{110N_e}{v(b_1 - C_B) \sqrt[3]{z}} - n^2 D_p^4 \right) \quad (2.2.2.6-2)$$

where  $N_e$  = nominal total output of the propulsion plant of the ship divided by the number of the propellers, in kW;

$n$  = number of propeller revolutions per second, in  $s^{-1}$ ;

$H_1$  = propeller pitch at the zero thrust, in m, determined by the formula

$$H_1 = H + \frac{0,055D_p}{\theta + 0,3} \quad (2.2.2.6-3)$$

where  $H$  = design propeller pitch, in m;

$\theta$  = blade area ratio;

$z$  = number of propeller blades.

### 2.2.3 Steering nozzle rudder force and torque.

**2.2.3.1** The total force  $F$ , in kN, acting on the steering nozzle and stabilizer shall not be taken less than determined by the formula

$$F = F_n + F_{st} \quad (2.2.3.1-1)$$

where  $F_n$  = force acting on the steering nozzle, in kN;

$F_{st}$  = force acting on the stabilizer, in kN;

$F_n$  and  $F_{st}$  are determined by the formulae:

$$F_n = 9,81 \cdot 10^{-3} p D_n l_n v_1^2; \quad (2.2.3.1-2)$$

$$F_{st} = 9,81 \cdot 10^{-3} q m A_{st} v_1^2 \quad (2.2.3.1-3)$$

where  $D_n$  = inner minimum steering nozzle bore, in m;

$l_n$  = steering nozzle length, in m;

$A_{st}$  = area of steering nozzle stabilizer, in  $m^2$ ;

$v_1$  = speed, in knots, determined by the formula

$$v_1 = v(1 - W) \quad (2.2.3.1-4)$$

where  $W$  = average wake factor. In case reliable experimental data are not available, the wake factor may be determined by the formula

$$W = 0,165 C_B^n \sqrt[3]{\Delta / D_p} \quad (2.2.3.1-5)$$

where  $C_B$  = block coefficient of the ship;

$\Delta$  = volume displacement, in  $m^3$ , with the ship on summer load waterline;

$n$  = number of propellers;

$D_p$  = propeller diameter, in m;

$v$  = maximum ahead speed, in knots, with the ship on summer load waterline;  
 this speed shall not be taken less than:  
 17 knots for ships of ice classes **Arc5** and **Arc6**;  
 14 knots for ships of ice class **Arc4**;  
 11 knots for other ships;

$p, q$  = coefficients determined by the formulae:

$$p = 78,4 - 55,6\sqrt{\lambda_n} + (44,0 - 33,4\sqrt{\lambda_n})C_{HB}; \quad (2.2.3.1-6)$$

$$q = 7,43 - 5,72\lambda_n + (2,82 - 2,2\lambda_n)C_{HB}; \quad (2.2.3.1-7)$$

$C_{HB}$  being determined by the formula

$$C_{HB} = 9,38T / (D_p^2 v_1^2) \quad (2.2.3.1-8)$$

where  $T$  = propeller thrust at speed  $v$ , in kN;

$D_p$  = propeller diameter, in m;

$\lambda_n$  is determined by the formula

$$\lambda_n = l_n / D_n; \quad (2.2.3.1-9)$$

$m$  = coefficient determined by the formula

$$m = 4,5 - 0,12(\lambda_{st} - 5,43)^2; \quad (2.2.3.1-10)$$

$\lambda_{st}$  is determined by the formula

$$\lambda_{st} = h_{st} / l_{st} \quad (2.2.3.1-11)$$

where  $h_{st}$  = height of steering nozzle stabilizer, in m;

$l_{st}$  = length of steering nozzle stabilizer, in m.

**2.2.3.2** A point situated at the level of the longitudinal axis of the steering nozzle at the distance  $r_n$  from the steering nozzle leading edge shall be considered as a point of application of force  $F_n$ . The distance  $r_n$ , in m, shall not be less than determined by the formula

$$r_n = l_n(bk + c) \quad (2.2.3.2-1)$$

where  $k$  = coefficient determined by the formula

$$k = l_{r.s} / l_n \quad (2.2.3.2-2)$$

where  $l_{r.s}$  = distance between the centre line of the rudder stock and the leading edge of the steering nozzle, in m;

$b, c$  = coefficients determined by the formulae

$$b = 0,796 - 0,011(C_{HB} - 7,18)^2; \quad (2.2.3.2-3)$$

$$c = 0,1585 - 0,0916\sqrt{C_{HB}}. \quad (2.2.3.2-4)$$

A point situated at the level of the steering nozzle longitudinal axis at the distance  $r_{st}$  from the stabilizer leading edge shall be considered as a point of application of force  $F_{st}$ . The distance  $r_{st}$ , in m, shall not be less than determined by the formula

$$r_{st} = 0,25l_{st}. \quad (2.2.3.2-5)$$

**2.2.3.3** The total torque  $M_t$ , in kN·m, for the steering nozzle shall be determined by the formula

$$M_t = M_n - M_{st} \quad (2.2.3.3-1)$$

where  $M_n$  = torque of force  $F_n$ , in kN·m;

$M_{st}$  = torque of force  $F_{st}$ , in kN·m;

$M_n$  and  $M_{st}$  are determined by the formulae:

$$M_n = F_n(l_{r.s} - r_n); \quad (2.2.3.3-2)$$

$$M_{st} = F_{st}(a + r_{st}) \quad (2.2.3.3-3)$$

where  $a$  = distance between the centre line of the rudder stock and the leading edge of the stabilizer, in m.

In any case, the total torque  $M_t$  for the steering nozzle shall not be taken less than the minimum value of torque  $M_{\min}$ , in kN·m, determined by the formula

$$M_{\min} = \frac{28,1F_n}{p} (0,72l_n - l_{r.s}) + \frac{7,8F_{st}}{qm} (l_n - l_{r.s} + 0,5l_{st}). \quad (2.2.3.3-4)$$


## 2.2.4 Bending moments and reactions of supports for rudders of types I — IV, VI — XII and steering nozzles of type V ([refer to Fig. 2.2.4.1](#)).

2.2.4.1 The design values of the bending moments and reactions of supports shall be determined from the formulae of this Chapter depending on the types of the rudders shown in [Fig. 2.2.4.1](#) having regard to the provisions of [Table 2.2.4.1](#) as well as the type and location of the steering gear as specified in [2.2.4.2](#).

Table 2.2.4.1

Type of rudder ( <a href="#">refer to Fig. 2.2.4.1</a> )	Design value of load $Q_2$	Design value of load $Q_1$
I, II, VII, VIII	$Q_2 = \left( \frac{F_1}{A} + \frac{F_2}{A_p} \right) A_l$	$Q_1 = F - Q_2$
III — VI and IX — XII	$Q_2 = 0$	

Notes: 1. The value of  $A_l$  is the portion the semispade rudder area below the lower pintle (below section 4 in [Fig. 2.2.4.1](#)), in m<sup>2</sup>.  
2. For steering nozzles of type V the design value of the ratio  $l_{r.s}/l_r$  is taken equal to zero.  
3. The force  $F$  is taken in accordance with the provisions of [2.2.2](#) for rudders and of [2.2.3](#) for steering nozzles.



**2.2.4.2** The transverse force  $P$ , in kN, created on the rudder stock by steering gear (quadrant steering gears, steering gears with single-arm tillers and similar steering gears) is determined by the formula

$$P = M_t / r_1 \quad (2.2.4.2)$$

where  $M_t$  = rudder torque, in kN·m, specified in [2.2.2.3](#) and [2.2.3.3](#). When considering the astern running of the ship, the rudder torque  $M_t$  is taken as the value  $M_{as}$  specified in [2.2.2.4](#);

$r_1$  = radius of the steering gear quadrant or tiller resultant force arm measured from the centre line of the rudder stock, in m.

Depending on the location of the steering gear quadrant or tiller indicated in [Fig. 2.2.4.2](#) the value  $P$  for Case I is taken as  $P_I$  and the value  $P_{II}$  is taken equal to zero. For Case II the value of  $P$  is taken as  $P_{II}$  and the value of  $P_I$  is taken equal to zero. The values of  $P_I$  or  $P_{II}$  are assumed to be positive when the quadrant or tiller are located forward of the rudder stock centre line and they are assumed to be negative when the quadrant or tiller are located aft of the rudder stock centre line.

For steering gears the rudder torque of which is transmitted to the rudder stock by a pair (or pairs) of forces (four-piston, rotary vane steering gears or similar) the values of  $P_I$  and  $P_{II}$  are taken equal to zero.




Fig. 2.2.4.2

**2.2.4.3** In the formulae of this Chapter the numerical indices of symbols of the bending moments ( $M_1$ ,  $M_2$ ,  $M_3$ ,  $M_4$ ) and reactions of supports ( $R_1$ ,  $R_2$ ,  $R_4$ ) correspond to the number of the support or section given in [Figs. 2.2.4.1](#) and [2.2.4.2](#) for the relevant type of the rudder.

**2.2.4.4** Unless expressly provided otherwise, in the formulae of this Chapter the linear dimensions shown in [Figs. 2.2.4.1](#) and [2.2.4.2](#) shall be taken in metres, and the forces, in kN.

**2.2.4.5** The design values of the bending moments and reactions of supports may be taken less than those specified in [2.2.4.1](#) on condition that the detailed calculation is submitted where due consideration is given to the flexibility of the rudder supports and to the non-uniformity of the force distribution over the rudder blade area.



**2.2.4.6** For Case I of the quadrant steering gear or tiller location ([refer to Fig. 2.2.4.2](#)) the design value of bending moment  $M_1$ , in kN·m, in section 1 of the rudder stock (at the upper bearing) shall be determined by the formula

$$M_1 = P_I l_7 \quad (2.2.4.6)$$

where for  $P_I$  and  $l_7$ , refer to [2.2.4.2](#) and [2.2.4.4](#).

For Case II of the steering gear quadrant or tiller location  $M_1$  is taken equal to zero.

**2.2.4.7** The design value of the bending moment  $M_2$ , in kN·m, acting in section 2 of the rudder stock (at the lower bearing for rudders of types I — VI; in the rudder stock and rudder blade coupling for rudders of types VII — XII) shall be determined by the formula

$$M_2 = \frac{1}{8} Q_1 h \frac{k_5}{k_7} - \frac{1}{2} Q_2 c \frac{k_6}{k_7} - \frac{1}{2} P_I l_7 \frac{k_8}{k_7} + \frac{1}{2} P_{II} l_8 \frac{k_9}{k_7} \quad (2.2.4.7-1)$$

where  $Q_1, Q_2$  = loads determined in accordance with [Table 2.2.4.1](#);  
 $P_I, P_{II}$  = forces determined in accordance with [2.2.4.2](#);  
 $h, c, l_7, l_8$  = linear dimensions ([refer to 2.2.4.4](#));  
 $k_5, k_6, k_7, k_8, k_9$  = factors determined by the formulae:

$$k_5 = 2 \left( \frac{e}{h} \right)^2 \left( 3 + \frac{e}{h} \right) + \left( 1 + 5 \frac{e}{h} \right) \frac{I_{r.s}}{I_r} + 12 \left( 1 + 2 \frac{e}{h} \right) \frac{I_{r.s} \alpha_4}{h^3}, \quad (2.2.4.7-2)$$

$$k_6 = \left( \frac{e}{h} \right)^2 \left( 3 + \frac{e}{h} \right) + \left( 1 + 3 \frac{e}{h} \right) \frac{I_{r.s}}{I_r} - 6 \left( 1 + \frac{l_2}{c} \right) \frac{I_{r.s} \alpha_4}{h^3}, \quad (2.2.4.7-3)$$

$$k_7 = \left( 1 + \frac{e}{h} \right)^2 \left( 1 + \frac{e}{h} + \frac{l_1}{h} \right) - 1 + \frac{I_{r.s}}{I_r} + 3 \frac{I_{r.s} \alpha_4}{h^3}, \quad (2.2.4.7-4)$$

$$k_8 = l_1 l_2^2 / h^3; \quad (2.2.4.7-5)$$

$$k_9 = \frac{l_1 l_2^2}{h^3} \left( 1 - \frac{l_2^2}{l_1^2} \right) \quad (2.2.4.7-6)$$

where  $e, l_1$  and  $l_2$  = linear dimensions ([refer to 2.2.4.4](#));

$I_{r.s}$  = mean moment of inertia of the rudder stock cross-section, in cm<sup>4</sup>;

$I_r$  = mean moment of inertia of the rudder cross-section at the portion between sections 3 — 4 (rudder types I — VI) or between sections 2 — 4 (rudder types VII — XII), in cm<sup>4</sup>;

$\alpha_4$  = coefficient determined in accordance with the provisions of [2.2.4.17 — 2.2.4.21](#) depending on the type of the rudder, in m<sup>3</sup>/cm<sup>4</sup>.

**2.2.4.8** The design value of the bending moment  $M_3$ , in kN·m, acting in section 3 of the rudder stock (in the rudder stock and rudder blade coupling for rudders of types I to VI) shall be determined by the formula

$$M_3 = M_2 \frac{h}{l_2} + Q_2 c \frac{e}{l_2} - \frac{1}{2} Q_1 h \frac{e}{l_2} \quad (2.2.4.8)$$

**2.2.4.9** The design value of the bending moment  $M_4$ , in kN·m, acting in section 4 of the rudder blade for rudders of types I, II, VII and VIII shall be determined by the formula

$$M_4 = Q_2 c. \quad (2.2.4.9)$$

For rudders of these types the value of  $M_4$  is taken as the bending moment acting in any rudder cross-section above support 4 of the rudder.

For other rudders the value of the bending moment  $M_4$  is taken equal to zero.

**2.2.4.10** The design value of the reaction  $R_1$ , in kN, of support 1 of the rudder (of the upper bearing) shall be determined by the formula

$$R_1 = \frac{M_2}{l_1} - P_I \left(1 + \frac{l_7}{l_1}\right) - P_{II} \left(1 + \frac{l_8}{l_1}\right). \quad (2.2.4.10)$$

**2.2.4.11** The design value of the reaction  $R_2$ , in kN, of support 2 of the rudder (of the lower bearing for rudder types I — VI, of the upper bearing of the rudder axle for rudder type XI, of the upper pintle of rudders for types VII — X and XII) shall be determined by the formula

$$R_2 = M_2 \left(\frac{1}{l_1} + \frac{1}{l_2}\right) + Q_2 \frac{c}{l_2} - \frac{1}{2} Q_1 \frac{h}{l_2} + P_I \frac{l_7}{l_1} - P_{II} \frac{l_8}{l_1}. \quad (2.2.4.11)$$

**2.2.4.12** The design value of the reaction  $R_4$ , in kN, of support 4 of the rudder (of the lower pintle) shall be determined by the formula

$$R_4 = \frac{M_2}{l_1} - \frac{1}{2} Q_1 \left(1 + \frac{e}{l_2}\right) - Q_2 \left(1 + \frac{c}{l_2}\right). \quad (2.2.4.12)$$

**2.2.4.13** The design value of the bending moment  $M_r$ , in kN·m, acting in the considered section of the lower part of the semispade rudder body (below section 4 shown in [Fig. 2.2.4.1](#) for rudder types I, II, VII and VIII) shall be determined by the formula

$$M_r = \frac{1}{2} Q_2 \frac{y^2}{l_6} \quad (2.2.4.13)$$

where  $y, l_6$  = linear dimensions ([refer to 2.2.4.4](#)).

**2.2.4.14** The design value of the bending moment  $M_r$ , in kN·m, acting in any cross-section of the rudder blade for rudders of types III, IV, VI and IX — XII shall be determined by the formula

$$M_r = \frac{1}{2} M_2 \frac{h}{l_2} \left(2 - \frac{h}{l_2} - \frac{M_2}{Q_1 l_2}\right) - \frac{1}{8} Q_1 h \left(2 - \frac{h}{l_2}\right)^2. \quad (2.2.4.14)$$

**2.2.4.15** The design value of the bending moment  $M_{r,a}$ , in kN·m, acting in the section of the rudder axle near its flange shall be determined by the formula

$$M_{r,a} = R_4 l_4 \left[ 0,42 \frac{(l_4 - l_2)}{l_4} + 0,24 \frac{l_3}{l_4} \frac{l_{r,p}}{l_s} + 0,15 \left(\frac{l_3}{l_4}\right)^2 \right] \quad (2.2.4.15)$$

where  $l_3, l_4$  = linear dimensions ([refer to 2.2.4.4](#));  
 $l_{r,p}$  = mean moment of inertia of the rudder axle or rudder post cross-section, in cm<sup>4</sup>;  
 $l_s$  = mean moment of inertia of the solepiece cross-section, in cm<sup>4</sup>.

**2.2.4.16** For Case II of the steering gear quadrant or tiller location ([refer to Fig. 2.2.4.2](#)) the design value of the bending moment  $M_s$ , in kN·m, acting in the section of the rudder stock in way of the quadrant or tiller location shall be determined by the formula

$$M_s = R_1 l_8. \quad (2.2.4.16)$$

For Case I of the steering gear quadrant or tiller location  $M_s$  is taken equal to zero.

**2.2.4.17** The coefficient  $\alpha_4$ , in  $\text{m}^3/\text{cm}^4$ , for rudders of types I and VII (for the horn of the semispade rudder) shall be determined by the formula

$$\alpha_4 = \frac{1,07l_3^3}{3I_1} \left(4 - 3 \frac{b_{h0}}{b_{h1}}\right) + \frac{1,3l_5^2 l_3}{I_2} \left(1 + \frac{b_{h1}}{b_{h0}}\right) \frac{b_{h1}}{b_{h0}} \quad (2.2.4.17-1)$$

where  $l_5$  = linear dimension (refer to 2.2.4.4);  
 $I_1$  = moment of inertia of the rudder horn cross-section at its root about the axis parallel to the centreline of the ship, in  $\text{cm}^4$ ;  
 $b_{h0}$  = maximum width of the horizontal section of the rudder horn at the lower pintle (section 4 in Fig. 2.2.4.1), in m;  
 $b_{h1}$  = maximum width of the horizontal section of the rudder horn at its root, in m;  
 $I_2$  = polar moment of inertia of the rudder horn cross-section at its root, in  $\text{cm}^4$ , determined by the formula

$$I_2 = \frac{4A_{r,h}^2}{\sum_{i=1}^n l_{oi}/S_{oi}} \quad (2.2.4.17-2)$$

where  $A_{r,h}$  = area enclosed by the centre line of the rudder horn plating (with the cross-section at the horn root), in  $\text{cm}^2$ ;  
 $l_{oi}$  = length of the centre line of the rudder horn plating (in the cross-section at the horn root) of the given thickness, in cm;  
 $S_{oi}$  = thickness of the considered portion of the rudder horn plating with the length  $l_{oi}$ , in cm;  
 $n$  = number of portions of the rudder horn plating with the length  $l_{oi}$  and thickness  $S_{oi}$ .

**2.2.4.18** The coefficient  $\alpha_4$ , in  $\text{m}^3/\text{cm}^4$ , for rudders of types III, V and IX (for the solepiece) shall be determined by the formula

$$\alpha_4 = \frac{l_3^3}{3I_{s1}} \left(4 - 3 \frac{b_{s0}}{b_{s1}}\right) \quad (2.2.4.18)$$

where  $I_{s1}$  = moment of inertia of the solepiece cross-section at its root about the vertical axis, in  $\text{cm}^4$ ;  
 $b_{s0}$  = width of the solepiece cross-section at the rudder stock or steering nozzle pintle, in cm;  
 $b_{s1}$  = width of the solepiece cross-section at its root, in cm.

**2.2.4.19** The coefficient  $\alpha_4$ , in  $\text{m}^3/\text{cm}^4$ , for rudders of types IV and X (for the rudder post with the solepiece) shall be determined by the formula

$$\alpha_4 = \frac{l_3^3}{3I_s} \left(0,075 \frac{I_s}{I_{r-p}} - 0,334 \frac{l_4}{l_3}\right). \quad (2.2.4.19)$$

**2.2.4.20** The coefficient  $\alpha_4$ , in  $\text{m}^3/\text{cm}^4$ , for rudders of type XI (for rudder axle with the solepiece) shall be determined by the formula

$$\alpha_4 = \frac{l_3^3}{3I_s} \left\{ \left(0,075 \frac{I_s}{I_{r-p}} + 0,334 \frac{l_4}{l_3}\right) - 0,282 \frac{(l_4 - l_2)}{l_4} \times \left[1,55 \frac{l_4}{l_3} + 0,053 \left(\frac{l_4}{l_3}\right)^2 + \frac{(l_4 - l_2)}{l_4} \frac{I_s}{I_{r-p}}\right] \right\}. \quad (2.2.4.20)$$

**2.2.4.21** The coefficient  $\alpha_4$  for rudders of types II, VI, VIII and XII is taken equal to zero.

**2.2.5 Bending moments and reactions of supports for rudder of type XIII (refer to Fig. 2.2.4.1).**

**2.2.5.1** The requirements of 2.2.4.2 — 2.2.4.6 and 2.2.4.16 are also applicable to the rudders of type XIII.

**2.2.5.2** The design value of the bending moment acting in way of the rudder stock and rudder blade coupling shall be taken equal to zero.

**2.2.5.3** The design value of the bending moment  $M_r$ , in kN·m, acting in any cross-section of the rudder blade shall be determined by the formula

$$M_r = 0,1 F h_i^2 / h_r \quad (2.2.5.3)$$

where  $F$  = force determined according to the provisions of [2.2.2.1](#), [2.2.2.2](#) and [2.2.2.5](#), in kN;  
 $h_i, h_r$  = linear dimensions ([refer to 2.2.4.4](#)); in this case, the greater of the value  $h_i$  shall be taken as the design value.

**2.2.5.4** The design value of the reaction  $R_1$  of support 1 of the rudder (of the upper bearing) shall be taken equal to zero.

**2.2.5.5** The design value of the reaction  $R_2$ , in kN, of support 2 of the rudder (of any pintle) shall be determined by the formula

$$R_2 = F h_i / h_r. \quad (2.2.5.5)$$

**2.2.6 Bending moments and reactions of supports for rudder of type XIV (refer to [Fig. 2.2.4.1](#)).**

**2.2.6.1** The requirements of [2.2.4.2 — 2.2.4.6](#) and [2.2.4.16](#) are also applicable to the rudders of type XIV.

**2.2.6.2** The design value of the bending moment  $M_2$ , in kN·m, acting in section 2 of the rudder stock (at the lower bearing) shall be determined by the formula

$$M_2 = F_1 c_1 + F_2 c_2 \quad (2.2.6.2)$$

where  $F_1, F_2$  = forces determined according to the provisions of [2.2.2.1](#), [2.2.2.2](#) and [2.2.2.5](#), in kN;  
 $c_1, c_2$  = linear dimensions ([refer to 2.2.4.4](#)), in m.

**2.2.6.3** The design value of the bending moment  $M_3$ , in kN·m, acting in section 3 of the rudder stock (in the rudder stock and rudder blade coupling) shall be determined by the formula

$$M_3 = F_1 (c_1 - e) + F_2 (c_2 - e) \quad (2.2.6.3)$$

where  $e$  = linear dimension ([refer to 2.2.4.4](#)), in m.

**2.2.6.4** The design value of the bending moment  $M_r$ , in kN·m, acting in the considered section of the rudder blade shall be determined by the formulae:

for sections with  $y < h_1$

$$M_r = \frac{1}{2} \left( \frac{F_1}{h_r} + \frac{F_2}{h_1} \right) y^2; \quad (2.2.6.4-1)$$

for sections with  $y \geq h_1$

$$M_r = \frac{1}{2} \frac{F_1}{h_r} y^2 + F_2 \left( y - \frac{1}{2} h_1 \right) \quad (2.2.6.4-2)$$

where  $h_r, h_1$  and  $y$  = linear dimensions ([refer to 2.2.4.4](#)), in m.

**2.2.6.5** The design value of the reaction  $R_1$ , in kN, of support 1 of the rudder (of the upper bearing) shall be determined by the formula

$$R_1 = F_1 \frac{c_1}{l_1} + F_2 \frac{c_2}{l_1} - P_I \left(1 + \frac{l_7}{l_1}\right) - P_{II} \left(1 - \frac{l_8}{l_1}\right) \quad (2.2.6.5)$$

where  $l_1$  = linear dimension ([refer to 2.2.4.4](#)), in m.

**2.2.6.6** The design value of the reaction  $R_2$ , in kN, of support 2 of the rudder (of the lower bearing) shall be determined by the formula

$$R_2 = F_1 \left(1 + \frac{c_1}{l_1}\right) + F_2 \left(1 + \frac{c_2}{l_1}\right) - P_I \frac{l_7}{l_1} + P_{II} \frac{l_8}{l_1}. \quad (2.2.6.6)$$

**2.2.7 Bending moments and reactions of supports for steering nozzles of type XV ([refer to Fig. 2.2.4.1](#)).**

**2.2.7.1** The requirements of [2.2.4.2 — 2.2.4.4](#), [2.2.4.6](#) and [2.2.4.16](#) are also applicable to the steering nozzle of type XV.

**2.2.7.2** The design value of the bending moment  $M_2$ , in kN·m, acting in [section 2](#) of the rudder stock (at the lower bearing) shall be determined by the formula

$$M_2 = Fc_1 \quad (2.2.7.2)$$

where  $F$  = force determined according to the provisions of [2.2.3.1](#), in kN;  
 $c_1$  = linear dimension ([refer to 2.2.4.4](#)), in m.

**2.2.7.3** The design value of the bending moment  $M_3$ , in kN·m, acting in section 3 of the rudder stock (at the rudder stock and steering nozzle coupling) shall be determined by the formula

$$M_3 = F(c_1 - e) \quad (2.2.7.3)$$

where  $e$  = linear dimension ([refer to 2.2.4.4](#)), in m.

**2.2.7.4** The design value of the reaction  $R_1$ , in kN, of support 1 (of the upper bearing) shall be determined by the formula

$$R_1 = F \frac{c_1}{l_1} - P_I \left(1 + \frac{l_7}{l_1}\right) - P_{II} \left(1 + \frac{l_8}{l_1}\right) \quad (2.2.7.4)$$

where  $l_1$  = linear dimension ([refer to 2.2.4.4](#)), in m.

**2.2.7.5** The design value of the reaction  $R_2$ , in kN, of support 2 (of the lower bearing) shall be determined by the formula

$$R_2 = F \left(1 + \frac{c_1}{l_1}\right) - P_I \frac{l_7}{l_1} + P_{II} \frac{l_8}{l_1}. \quad (2.2.7.5)$$

**2.2.8** The design values of bending moments and reactions of supports for the steering gears which differ from those indicated in [Fig. 2.2.4.1](#) shall be submitted by the designer.

## 2.3 RUDDER STOCK

**2.3.1** The diameter of the rudder stock head  $d_0$ , in cm, shall be not less than the greater value determined by the formula

$$d_0 = k_{10} \sqrt[3]{M_t / R_{eH}} \quad (2.3.1)$$

where  $k_{10}$  = factor equal to:

26,1 for the ahead condition;

23,3 for the astern condition;

$M_t$  = torque according to [2.2.2.3](#), [2.2.2.4](#) or [2.2.3.3](#), in kN·m;

$R_{eH}$  = upper yield stress of the rudder stock material, in MPa.

**2.3.2** Under combined action of the torque and bending moment the working stresses ([refer to 1.5.1](#)) acting in rudder stock sections 1, 2 or 3 shown in [Fig. 2.2.4.1](#) for the appropriate type of the rudder shall not exceed 0,5 times the upper yield stress for the ahead condition and 0,7 times the upper yield stress of the material for the astern condition ([refer to 1.5.2](#) and [2.1.6](#)). In this case, the normal stress  $\sigma$  and the shear stress  $\tau$ , in MPa, shall be determined by the formulae:

$$\sigma = 10,2 \cdot 10^3 M_b / d_i^3; \quad (2.3.2-1)$$

$$\tau = 5,1 \cdot 10^3 M_t / d_i^3 \quad (2.3.2-2)$$

where  $M_b$  = bending moment acting in the considered section of the rudder stock ( $M_1$ ,  $M_2$  or  $M_3$ ) determined according to the provisions of [2.2.4 — 2.2.7](#) for the appropriate type of the rudder, in kN·m;

$d_1$  = diameter of the rudder stock in the considered section, in cm.

**2.3.3** The change in the rudder stock diameter between the adjacent sections specified in [2.3.1](#) and [2.3.2](#) shall not be more sudden than that permitted by the linear law.

Where the change of the rudder stock diameter is stepped, the steps shall be provided with fillets having as large radius as practicable. The transition of the rudder stock into the flange shall be carried out with a radius of fillet of not less than 0,12 times the diameter of the rudder stock in way of the flange.

## 2.4 RUDDER BLADE AND STEERING NOZZLE

### 2.4.1 Rudder blade.

**2.4.1.1** The thickness of the streamlined rudder blade side plating  $s$ , in mm, shall be not less than determined by the formula

$$s = ak_{11} \sqrt{\frac{98d + k_{12} \left( \frac{F_1}{A} + k_{13} \frac{F_2}{A_p} \right)}{R_{eH}}} + 1,5 \quad (2.4.1.1-1)$$

where  $d$  = draught of the ship, in m;

$F_1, F_2$  = forces according to 2.2.2.1 and 2.2.2.2, in kN;

for  $A$  and  $A_p$ , refer to 2.2.2.1;

$a$  = distance between horizontal or vertical web plates, whichever is the less, in m;

$k_{11}$  = factor determined by the formula

$$k_{11} = 10,85 - 2,516 \left( \frac{a}{b} \right)^2; \quad (2.4.1.1-2)$$

$R_{eH}$  = upper yield stress of the rudder blade plating material, in MPa;

$b$  = distance between horizontal or vertical web plates whichever is the greater, in m;

$k_{12}$  = factor equal to:

18,6 for the rudder blade plating within 0,35 of the rudder blade length from its leading edge;

8,0 for the rudder blade plating within 0,65 of the rudder length from its rear edge;

$k_{13}$  = factor equal to:

1 for the rudder blade plating in the wake of the propeller (when rudder is in the non-reversed position);

0 for the rudder blade plating beyond the wake of the propeller (when rudder is in the non-reversed position).

**2.4.1.2** In any case, the thickness of the streamlined rudder blade side plating  $s_{\min}$ , in mm, shall be not less than determined by the formulae:

for ships of less than 80 m in length

$$s_{\min} = 21,5 \frac{L+51}{L+240}; \quad (2.4.1.2-1)$$

for ships of 80 m in length and over

$$s_{\min} = 24 \frac{L+37}{L+240} \quad (2.4.1.2-2)$$

where  $L$  = length of the ship, in m.

**2.4.1.3** For ice class ships the thickness of the rudder blade side plating in way of the ice belt shall be not less than that of the ice belt of the shell plating in the after part of the ship, specified in 3.10.4.1 of Part II "Hull", with the frame spacing being equal to the distance between the vertical web plates of the rudder blade.

The thickness  $s$ , in mm, of the rudder blade side plating for the icebreakers shall be not less than determined by the formula

$$s = 9,2k_{16}a \sqrt{\frac{p_a}{R_{eH}}} + 6 \quad (2.4.1.3-1)$$

where  $a$  = distance between horizontal or vertical web plates, whichever is the less, for streamlined welded rudders; distance between rudder arms for single-plate steel solid-cast rudders, m. In any case, in the calculations the value  $a$  shall not be taken less than 0,6 m;

$p_a$  = intensity of ice pressure in the CI region determined according to 3.10.3.5.2 of Part II "Hull", in kPa;

$R_{eH}$  = upper yield stress of the material of the rudder blade plating, in MPa;

$k_{16}$  = factor determined for streamlined welded rudders by the formula

$$k_{16} = 1 - 0,38(a/b)^2 \quad (2.4.1.3-2)$$

where  $b$  = distance between horizontal or vertical web plates, whichever is the greater, in m.

For single-plate steel solid-cast rudders the value of  $k_{16}$  shall be taken in the calculations equal to 1.

**2.4.1.4** The streamlined rudder blade side plating shall be stiffened from the inside by horizontal and vertical web plates. The thickness of the web plates shall be not less than that of the rudder blade side plating.

The side plating and web plates shall be welded together by fillet or plug welds with slots of linear form. Dimensions of elements of plug welds are selected according to 1.7.5.13 of Part II "Hull".

The horizontal and vertical web plates shall be provided with sufficient number of openings for free drainage of water which may penetrate inside the rudder blade.

The rear edge of the rudder blade shall be rigidly fixed in the proper way.

**2.4.1.5** The streamlined rudder blade shall be provided with top and bottom plates, the thickness of which shall be not less than 1,2 times the greater value of the side plating thickness according to [2.4.1.1](#). The top and bottom plates shall be fitted with drain plugs of corrosion-resistant metal.

**2.4.1.6** The corners of the openings (in way of the pintles) in the side plating of the semispade rudder blade shall be rounded off. The radius of curvature shall be not less than 2 times the side plating thickness in this area, and the free edge of the rudder side plating shall be thoroughly stripped.

**2.4.1.7** Near the rotation axis of the streamlined rudder one or several vertical web plates shall be provided ensuring the general strength of the rudder blade. The section modulus of these web plates, including the effective flanges, shall be such that the normal stresses in the considered section are not more than 0,5 times the upper yield stress of the material of the rudder blade side plating ([refer to 1.5.2](#)).

The normal stresses  $\sigma$ , in MPa, shall be calculated by the formula

$$\sigma = 1000M_b/W \quad (2.4.1.7)$$

where  $M_b$  = bending moment in the considered section of the rudder blade ( $M_A$  or  $M_I$ ) determined according to the provisions of [2.2.4 — 2.2.6](#) for the appropriate type of the rudder, in kN·m;

$W$  = section modulus of the considered section of the web plates, including the effective flanges, about the axis of symmetry of the rudder blade profile, in cm<sup>3</sup>.

The dimensions of the effective flanges of the web plates shall be as follows:

the thickness equal to that of the rudder blade side plating;

the width equal to 1/6 of the rudder blade height or 1/2 of the distance between the nearest web plates located on both sides of the considered web plate, whichever is the less.

**2.4.1.8** Special care shall be given to the reliable securing to the rudder blade of the flange for coupling the rudder blade and the rudder stock and of the gudgeons for pintles.

**2.4.1.9** At the leading edge of the single-plate steel solid-case rudders of the icebreakers the rudder piece shall be provided over the entire height of the rudder blade.



The equivalent stress  $\sigma_{eq}$ , in MPa, developed in any horizontal section of the rudder piece and determined by the formula given below shall not exceed 0,5 times the upper yield stress of the rudder blade material

$$\sigma_{eq} = 1000 \sqrt{\left(\frac{M_r}{W}\right)^2 + 3 \left(\frac{M_t y}{h_r \rho S}\right)^2} \quad (2.4.1.9)$$

where  $M_r$  = bending moment determined according to the provisions of 2.2.5.3, in kN·m;  
 $M_t$  = torque according to 2.2.2.3, in kN·m;  
 $h_r$  = height of the rudder measured on the rudder stock centre line, in m;  
 $y$  = distance between the considered section and the lower edge of the rudder (refer to Fig. 2.4.1.9), in m;  
 $W$  = section modulus of the considered cross-section of the rudder piece about the axis  $O_1 - O_1$ , ignoring the rudder blade plating (the rudder piece section taken into account in the calculation of  $W$  is hatched in section I—I of Fig. 2.4.1.9), in cm<sup>3</sup>;  
 $S$  = area of the considered cross-section of the rudder piece (refer to hatched area in section I—I of Fig. 2.4.1.9), in cm<sup>2</sup>;  
 $\rho$  = distance between the centroid of the area  $S$  and the rudder blade centre line, in cm.




Fig. 2.4.1.9

**2.4.1.10** The single-plate steel solid-case rudder shall be stiffened by the rudder arms founded on both sides of the rudder blade at the level of each gudgeon (refer to Fig. 2.4.1.9).

The section modulus of the considered cross-section of the rudder arms  $W$ , in cm<sup>3</sup>, (including the body of the rudder blade within the dimension  $h_i$ , refer to section II—II in Fig. 2.4.1.9) about the axis  $O_2 - O_2$  shall be not less than determined by the formula

$$W = \frac{1000 h_i x^2 F}{A R_{eH}} \quad (2.4.1.10)$$

where  $F$  = force determined according to the provisions of 2.2.2.2, kN;  
 $A$  = rudder area, in m<sup>2</sup>;  
 $h_i$  = linear dimension, in m (refer to Fig. 2.4.1.9);  
 $x$  = distance between the considered section and the rear edge of the rudder, in m (refer to Fig. 2.4.1.9);  
 $R_{eH}$  = upper yield stress of the rudder material, in MPa.

**2.4.2 Steering nozzle rudder.**

**2.4.2.1** The thickness  $s_o$ , in mm, of the steering nozzle outside plating shall be not less than determined by the formula

$$s_o = k_{14} l_1 \sqrt{\frac{98 D_n l_n d + 20 F_n}{D_n l_n R_{eH}}} + 2 \quad (2.4.2.1-1)$$

where  $D_n$  = inner minimum nozzle bore, in m;  
 $l_n$  = length of the steering nozzle, in m;  
 $d$  = draught of the ship, in m;  
 $F_n$  = force acting on the steering nozzle according to [2.2.3.1](#), in kN;  
 $R_{eH}$  = upper yield stress of the material of the steering nozzle outside plating, in MPa;  
 $k_{14}$  = factor determined by the formula

$$k_{14} = 7,885 - 2,221(l_1/u_1)^2 \quad (2.4.2.1-2)$$

where  $l_1$  = distance between transverse web plates or between the transverse web plate and the nearest edge of the steering nozzle, in m. This distance shall not exceed 600 mm;  
 $u_1$  = distance between the longitudinal web plates measured along the length of the steering nozzle outside plating, in m. This distance shall not exceed 1000 mm.

**2.4.2.2** The thickness  $s_{in}$ , in mm, of the steering nozzle inside plating, except for its middle belt, shall be not less than

$$s_{in} = 6,39 \frac{l_1}{D_n} \sqrt{T} \quad (2.4.2.2-1)$$

where  $T$  = propeller thrust at speed  $v$ , in kN.

The thickness  $s_m$ , in mm, of the middle belt of the steering nozzle inside plating shall be not less than

$$s_m = 7,34 \frac{l_2}{D_n} \sqrt{T} + 0,51 \frac{T}{D_n^2} \quad (2.4.2.2-2)$$

where  $l_2$  = distance between transverse web plates situated in way of the middle belt of the inside plating, in m.

**2.4.2.3** In any case, the thickness of the outside and inside plating of the steering nozzle shall be not less than that given in [2.4.1.2](#).

**2.4.2.4** The middle belt of the steering nozzle inside plating shall extend not less than  $0,05D_n$  forward and not less than  $0,1D_n$  aft of the propeller blade tips. Its breadth shall be at least equal to the maximum breadth of the side projection of the propeller blade.

**2.4.2.5** The outside and inside plating of the steering nozzle shall be stiffened from the inside by transverse and longitudinal web plates. The spacing of the web plates shall comply with the requirements of [2.4.2.1](#). At least four longitudinal web plates shall be provided which are equally spaced around the circumference of the steering nozzle.

The thickness of web plates, except those situated in way of the middle belt of the steering nozzle inside plating, shall be not less than the thickness of the outside plating according to [2.4.2.1](#) and [2.4.2.3](#).

The transverse and longitudinal web plates shall be welded to the steering nozzle inside plating by double side continuous welds with full penetration on the inside of the steering nozzle. When the thickness of the web plates is 10 mm and more, edge preparation shall be carried out.

The outside plating and web plates shall be connected by plug welding with slots of linear form or by backing welding. The dimensions of elements of plug welds with slots of linear form are selected according to 1.7.5.13 of Part II "Hull".

The transverse and longitudinal web plates shall be provided with sufficient number of openings for free drainage of water which might penetrate inside the steering nozzle, and in the lower and upper parts of the outside plating the drain plugs of stainless metal shall be fitted. The distance from the opening edge to the inside and outside plating of the steering nozzle shall be not less than 0,25 times the web plate height.

It is not allowed to weld on doubling plates to the inside plating of the steering nozzle.

**2.4.2.6** In way of the middle belt of the steering nozzle inside plating at least two continuous transverse web plates shall be fitted. The thickness of these web plates shall be not less than the thickness of the inside plating off its middle belt as per [Formula \(2.4.2.2-1\)](#).

**2.4.2.7** Special care shall be given to the reliable securing of the nozzle flange, welded-in bush and other steering nozzle welded-in parts for connecting the steering nozzle welded-in parts for connecting the steering nozzle with its stock and pintle.

**2.4.2.8** The thickness  $s_{st}$  of the stabilizer plating, in mm, shall be not less than determined by the formula

$$s_{st} = k_{14} l_1 \sqrt{\frac{98A_{st}d + 20F_{st}}{A_{st}R_{eH}}} + 2 \quad (2.4.2.8)$$

where  $A_{st}$  = area of the steering nozzle stabilizer, in m<sup>2</sup>;

$F_{st}$  = force acting on the stabilizer according to [Formula \(2.2.3.1-3\)](#), in kN;

$k_{14}$  = factor according to [2.4.2.1](#) when the distance between horizontal web plates equals to  $u_1$ , in m;

$l_1$  = distance between vertical web plates or between the web plate and fore or aft edge of the stabilizer, in m;

$R_{eH}$  = upper yield stress of material of the stabilizer plating, in MPa.

**2.4.2.9** The steering nozzle stabilizer plating shall be stiffened from the inside by horizontal and vertical web plates having the thickness not less than that of the plating in accordance with [2.4.2.8](#).

The stabilizer body shall terminate in top and bottom plates. The thickness of top and bottom plates shall not be less than 1,5 times the thickness of the plating according to [2.4.2.8](#). Vertical web plates shall be securely connected to top and bottom plates.

The plating and horizontal and vertical web plates shall be welded together by fillet or plug welds. The types of plug welds with slots of linear form are selected according to 1.7.5.13 of Part II "Hull".

The horizontal and vertical web plates shall be provided with sufficient number of openings, and top and bottom plates shall be fitted with drain plugs of corrosion-resistant material.

**2.4.2.10** In way of attachment of the stabilizer to the steering nozzle one or several vertical web plates shall be provided ensuring general strength of the stabilizer. The section modulus  $W_{st}$ , in cm<sup>3</sup>, of these web plates, the effective flange included, shall be not less than determined by the formula

$$W_{st} = 1390 F_{st} h_{st} / R_{eH} \quad (2.4.2.10)$$

where  $F_{st}$  = force acting on the stabilizer according to [Formula \(2.2.3.1-3\)](#), in kN;

$h_{st}$  = stabilizer height, in m;

$R_{eH}$  = upper yield stress of the material used, in MPa.

The effective flange dimensions shall be as follows: thickness equal to the stabilizer plating thickness; width equal to 1/5 of the stabilizer height.

**2.4.2.11** The steering nozzle and stabilizer shall be so connected that rigid fixation of the latter is ensured.

The force  $F_{st}$  determined from [Formula \(2.2.3.1-3\)](#) and uniformly distributed with the height of the stabilizer shall be taken in strength calculations as a force acting on the stabilizer. Depending on the type of connection a torque of force  $F_{st}$  acting on this connection shall be considered with regard to the point of application of this force (refer to [Formula \(2.2.3.2-3\)](#)). In this case, stresses developed in the connection ([refer to 1.5.1](#)) shall not exceed 0,4 times the upper yield stress of the material.

## 2.5 COUPLINGS

### 2.5.1 Horizontal flange coupling.

**2.5.1.1** The diameter of the coupling bolts  $d_1$ , in cm, shall be not less than

$$d_1 = 0,62 \sqrt{\frac{d_2^3 2R_{eH_1}}{z_1 r_2 R_{eH_2}}} \quad (2.5.1.1-1)$$

where  $d_2$  = diameter of the rudder stock at the coupling flange, in cm;

$z_1$  = number of coupling bolts;

$r_2$  = mean distance from the centre of the bolts to the centre of the system of the flange bolt holes, in cm;

$R_{eH_1}$  = upper yield stress of the rudder stock material, in MPa;

$R_{eH_2}$  = upper yield stress of the bolt material, in MPa.

The coupling bolt diameter at the bottom of threads  $d_3$ , in cm, shall be not less than determined by the formula

$$d_3 = 76,84 \sqrt{\frac{M_b}{z_1 r_3 R_{eH_2}}} \quad (2.5.1.1-2)$$

where  $M_b$  = bending moment acting in the rudder stock section at the flange ( $M_2$  or  $M_3$ ) determined according to the provisions of [2.2.4 — 2.2.7](#) for the appropriate type of the rudder, in kN·m;

$r_3$  = mean distance from the centre of the bolts to the longitudinal axis of symmetry of the flange, in cm.

The number of bolts  $z_1$  shall be not less than 6.

The mean distance from the centre of the bolts to the centre of the system of the flange bolt holes shall be not less than 0,9 times the rudder stock diameter according to [2.3.1](#). When the coupling is under the action of the bending moment, the mean distance from the centre of the bolts to the longitudinal axis of symmetry of the flange shall be not less than 0,6 times the rudder stock diameter at the flange.

**2.5.1.2** Only fitted bolts shall be employed, except the cases of a key setting when it is sufficient to have only two fitted bolts. The nuts shall have standard sizes. The bolts and nuts shall be efficiently secured.

**2.5.1.3** The thickness of the coupling flanges shall not be less than the diameter of the bolts. The centres of the holes for bolts shall be distant from the outside edges of the flange by not less than 1,15 times the diameter of the bolts.

**2.5.1.4** When coupling flanges of steering nozzles are not built into the steering nozzle body but connected to it by the structure formed of sheets, the strength of this structure shall be equivalent to that of the rudder stock in accordance with [2.3.2](#). In this case, the calculated equivalent stress shall not exceed 0,4 times the upper yield stress of the material used.

### 2.5.2 Keyed cone coupling.

**2.5.2.1** The cone length of the rudder stock fitted to the rudder blade or steering nozzle shall not be less than 1,5 times the diameter of the rudder stock according to [2.3.2](#); the cone on the diameter shall be 1:10. The cone shall change into cylindrical portion without any step in the diameter.

**2.5.2.2** A key shall be set on the cone generatrix. The ends of the key shall be fairly rounded. The working sectional area of the key  $A_k$  (product of the key length by its width), in  $\text{cm}^2$ , shall be not less than the greater value determined by the formula

$$A_k = \frac{k_{15} M_t}{d_m R_{eH}} \quad (2.5.2.2)$$

where  $k_{15}$  = factor equal to:

6920 for rudders for the ahead condition and for steering nozzles;

4950 for rudders for the astern condition;

$M_t$  = torque according to [2.2.2.3](#), [2.2.2.4](#) or [2.2.3.3](#), in  $\text{kN}\cdot\text{m}$ ;

$d_m$  = diameter of the cone section at the middle of the key length, in  $\text{cm}$ ;

$R_{eH}$  = upper yield stress of the key material, in  $\text{MPa}$ .

The height of the key shall be not less than half its width.

The keyway of the rudder stock shall be confined to the cone coupling.

**2.5.2.3** The external diameter of the rudder stock threaded portion shall not be less than 0,9 times the minimum diameter of the cone. The thread shall be fine. The outer diameter and height of the nut shall not be less than 1,5 and 0,8 times the external diameter of the rudder stock threaded portion, respectively. To prevent self-unscrewing, the nut shall be securely fastened at least by two welded-on strips or one welded-on strip and a split pin.

### **2.5.3 Keyless cone coupling.**

**2.5.3.1** The requirements of [2.5.3](#) are applicable to a keyless fitting of the rudder stock to the rudder blade or steering nozzle which is made by oil injection method.

**2.5.3.2** The cone length of the rudder stock fitted to the rudder blade or steering nozzle shall not be less than 1,5 times the diameter of the rudder stock according to [2.3.2](#); the cone on the diameter shall be 1:15.

**2.5.3.3** The rudder blade or steering nozzle boss shall be a good fit on the rudder stock cone. During the fit up, and before the push-up load is applied, an area of contact of at least 70 % of the theoretical area of contact shall be achieved, and this shall be distributed evenly.

The relationship of the rudder stock and boss cones at which this occurs shall be marked, and push-up length then measured from that point.

In well-founded cases another method of determining the original position of the rudder stock and boss cones relationship can be used.

**2.5.3.4** To ensure the required interference in the cone coupling the push-up length of the rudder stock ([refer to 2.5.3.3](#)) during its fitting shall be not less than determined by the formula

$$s_1 = \frac{1,1q}{EK} \left[ \frac{2d_m}{1 - \left(\frac{d_m}{d_c}\right)^2} + 35,7 \right] \quad (2.5.3.4-1)$$

where  $s_1$  = push-up length of the rudder stock, in  $\text{mm}$ ;

$d_m$  = mean diameter of the rudder stock cone, in  $\text{mm}$ ;

$d_c$  = outer diameter (or minimum outer dimension) of rudder blade boss or steering nozzle (in the mean section), in  $\text{mm}$ ;

$E$  = modulus of elasticity of rudder stock material, in  $\text{MPa}$ ;

$K$  = taper of conical coupling, on the diameter;

$q$  = required contact pressure applied to mating surfaces during the push-up, in  $\text{MPa}$ , determined by the formula

$$q = \frac{4,25 \cdot 10^6 n M_t}{d_m^2 L_a} \sqrt{1 + \left( \frac{5 \cdot 10^{-6} Q d_m}{M_t} \right)^2} \times \left( 1 + 0,257 \frac{L_a}{d_m} \frac{M_t}{M_b} \right) \quad (2.5.3.4-2)$$

where  $n$  = safety factor against friction slip under the action of rated torque;

$M_t$  = maximum value of design torque according to [2.2.2.3](#), [2.2.2.4](#) or [2.2.3.3](#), in  $\text{kN}\cdot\text{m}$ ;

- $L_a$  = actual length of the contact part of cone, excluding the oil distribution grooves and similar devices, in mm;  
 $Q$  = mass of rudder blade or steering nozzle, in kg;  
 $M_b$  = maximum bending moment in way of cone coupling determined according to 2.2.4.8, 2.2.6.3 or 2.2.7.3, in kN·m.

The spade rudders and steering nozzles of types XIV and XV (refer to Fig. 2.2.4.1) the value  $n$  shall be taken not less than 2,5; for other types of rudders and steering nozzles this value shall be not less than 2,0.

If the contact pressure  $q$  determined by Formula (2.5.3.4-2) is less than 40 MPa, then  $q = 40$  MPa shall be taken in the calculations.

**2.5.3.5** The strength of the maximum loaded part of the coupling shall be checked: the combined stress on the inside of the rudder blade or steering nozzle boss shall not exceed 0,85 of the yield stress of the boss material. The combined stress  $\sigma_{com}$  on the inside of the boss shall be determined by the formula

$$\sigma_{com} = \sqrt{0,5(\sigma_1 - \sigma_2)^2 + 0,5(\sigma_2 - \sigma_3)^2 + 0,5(\sigma_3 - \sigma_1)^2} \quad (2.5.3.5-1)$$

$$\text{where } \sigma_1 = q_1 \frac{d_c^2 + d_3^2}{d_c^2 - d_3^2}; \quad (2.5.3.5-2)$$

$$q_1 = q + 5,73 \frac{M_b \cdot 10^6}{d_3 L_{s,t}^2}; \quad (2.5.3.5-3)$$

$$\sigma_2 = -q_1; \quad (2.5.3.5-4)$$

$$\sigma_3 = \frac{40Q}{\pi(d_c^2 - d_3^2)} + \frac{M_b \cdot 10^7}{d_3^3}; \quad (2.5.3.5-5)$$

$q_1$  = contact pressure between mating cone surfaces in way of maximum diameter of the rudder stock cone under combined action of torque and bending moments, in MPa;

$d_3$  = maximum diameter of rudder stock cone, in mm;

$L_{s,t}$  = length of rudder stock cone, in mm.

**2.5.3.6** The value of oil pressure applied to the mating cone surfaces of the rudder stock and rudder blade boss during mounting and dismounting of the coupling shall not exceed  $p_{max}$  pmax, in MPa, determined by the formula

$$p_{max} = 0,55R_{eH} \left[ 1 - \left( \frac{d_m}{d_c} \right)^2 \right] \quad (2.5.3.6)$$

where  $R_{eH}$  = yield stress of material of the rudder blade or steering nozzle boss, in MPa.

**2.5.4** Where the rudder stock is not made of a solid piece, its parts shall be joined by means of a muff coupling or by other method which shall ensure a strength equivalent to that of the rudder stock.

## 2.6 RUDDER PINTLES

**2.6.1** The diameter  $d_4$  in cm, of pintles without liners, as well as of pintles with liners, but before their setting, shall be not less than determined by the formula

$$d_4 = 18\sqrt{R_i/R_{eH}} \quad (2.6.1)$$

where  $R_i$  = design value of the reaction of the considered pindle ( $R_2$  or  $R_4$ ) determined according to the provisions of [2.2.4](#) and [2.2.5](#) for the appropriate type of the rudder, in kN;  
 $R_{eH}$  = upper yield stress of the pindle material, in MPa.

**2.6.2** The length of the cone part of the pindle in rudder gudgeon, in welded-in bush of the steering nozzle or in the solepiece shall not be less than the diameter of the pindle according to [2.6.1](#); the cone on the diameter shall not exceed 1:10. The cone shall change into cylindrical portion without any step in the diameter.

The external diameter of the pindle threaded portion shall not be less than 0,8 times the minimum diameter of the cone. The outer diameter and height of the nut shall not be less than 1,5 and 0,6 times the external diameter of the pindle threaded portion, respectively.

**2.6.3** The ratio of bearing height to diameter measured outside the pindle liners, where fitted, shall not be less than 1, nor more than 1,3.

**2.6.4** The width of material in the rudder gudgeons and welded-in bushes of the steering nozzle measured outside the hole for the pindle bush shall not be less than 0,5 times the diameter of the pindle without liner.

For rudder pintles of 200 mm and over in diameter it is allowed to reduce the specified width of the gudgeon from 0,5 times the diameter of the gudgeon down to 0,35 times the diameter of the pindle without liner in case the requirements of [2.6.2](#) and [2.6.3](#) are met, the following relation is obtained:

$$\frac{l_7}{d'_4} \geq \frac{R_{eH(p)}}{R_{eH(g)}} \quad (2.6.4)$$

where  $l_7$  = height of the pindle bush, in cm;  
 $d'_4$  = diameter of the pindle, in cm, including its liner, where fitted;  
 $R_{eH(p)}$  = upper yield stress of the pindle material, in MPa;  
 $R_{eH(g)}$  = upper yield stress of the gudgeon material, in MPa.

**2.6.5** To prevent self-unscrewing, the nut shall be securely fastened by means of at least two welded-on strips or one welded-on strip and a split pin, and the pintles shall be securely fastened in gudgeons of the rudder or sternframe.

**2.6.6** The chosen dimensions of the pintles shall be checked by the surface loading  $p$ , in MPa, this being taken as

$$p = 10R_i/(d'_4 l_7) \quad (2.6.6)$$

where for  $R_i$ , refer to [2.6.1](#);  
 $d'_4$  = diameter of the pindle, in cm, including its liner, where fitted;  
 $l_7$  = height of the pindle bush, in cm.

This surface loading shall not exceed the values specified in [Table 2.1.7](#).



## 2.7 RUDDER AXLE

**2.7.1** The diameter of the rudder axle directly at the flange  $d_5$  shall be such that the normal stresses  $\sigma$  developed in its sections do not exceed 0,5 times the upper yield stress of the rudder axle material. The normal stress  $\sigma$ , in MPa, shall be determined by the formula

$$\sigma = 10^4 M_{r.a} / d_5^3 \quad (2.7.1)$$

where  $M_{r.a}$  = design value of the bending moment determined according to the provisions of [2.2.4.15](#), in kN·m;  
 $d_5$  = diameter of the rudder axle at the flange, in cm.

The diameter of the rudder axle in way of the rudder bearings shall be not less than the diameter  $d_5$ . The diameter of the rudder axle between the rudder blade bearings may be reduced by 10 %.

**2.7.2** As regards the cone and threaded portions of the rudder axle and also its nut, the requirements are as stipulated in [2.6.2](#) for the pintles.

**2.7.3** The diameter of bolts of the rudder axle flange coupling  $d_6$ , in cm, shall be not less than determined by the formula

$$d_6 = 6,77 \sqrt{\frac{R_2 + \frac{M_{r.a}}{r_4} \sqrt{1 + \left(0,17 + 0,6 \frac{R_2 r_5}{M_{r.a}}\right)^2}}{z_2 R_{eH}}} \quad (2.7.3)$$

where  $R_2$  = design value of the reaction of the rudder axle upper bearing determined according to [2.2.4.11](#), in kN;  
 $M_{r.a}$  = design value of the bending moment acting in the rudder axle section near its flange determined according to [2.2.4.15](#), in kN·m;  
 $r_4$  = mean distance from the centre of the bolts to the centre of the system of the flange bolt holes, in m;  
 $r_5$  = distance from the centre line of the rudder stock to the contact plane of the rudder axle flanges and the sternframe, in m;  
 $z_2$  = number of the bolts of the flange coupling;  
 $R_{eH}$  = upper yield stress of the bolt material, in MPa.

The number of the bolts  $z_2$  shall be not less than 6.

The distance from the centre of any bolt to the centre of the system of the flange bolt holes shall be not less than 0,7, and to the vertical axis of symmetry of the flange plane, not less than 0,6 times the diameter  $d_5$  of the rudder axle given in [2.7.1](#).

**2.7.4** Only fitted bolts shall be employed, except the cases of a key setting when it is sufficient to have only two fitted bolts. The nuts shall have standard sizes, and they shall be securely fastened by split pins or weld-on strips.

**2.7.5** The thickness of the coupling flange shall not be less than the diameter of the bolts. The centres of the holes for bolts shall be distant from the outside edges of the flange by not less than 1,15 times the diameter of the bolts.

**2.7.6** Where the diameter of the rudder axle changes, sufficient fillets shall be provided. At transition from the rudder axle to the flange a fillet shall be provided with a radius of not less than 0,12 times the rudder axle diameter.

**2.7.7** To prevent self-unscrewing, the nut of the rudder axle shall be securely fastened at least by two weld-on strips or one weld-on strip and a split pin.

**2.7.8** The requirements of [2.6.6](#) for pintles are applicable to the rudder blade bearings on the rudder axle.

## **2.8 RUDDER STOCK BEARINGS**

**2.8.1** The requirements of [2.6.6](#) for pintles are applicable to the rudder stock bearings taking lateral load.

**2.8.2** A rudder carrier shall be installed to take the mass of the rudder blade or steering nozzle and rudder stock. The deck shall be efficiently strengthened in way of the rudder carrier.

Measures shall be taken against axial displacement of the rudder blade or steering nozzle and rudder stock upwards by a value exceeding that permitted by the construction of the steering gear; furthermore, for steering nozzle measures shall be taken to provide for guaranteed clearance between propeller blades and nozzle under service conditions.

**2.8.3** A stuffing box shall be fitted in way of passage of the rudder stock through the top of a rudder trunk which is open to sea to prevent water from entering the ship's space. The stuffing box shall be fitted in a place accessible for inspection and maintenance at all times.

## 2.9 STEERING GEAR

**2.9.1** Ships shall be provided with a main steering gear and an auxiliary steering gear, unless expressly provided otherwise.

**2.9.2** The main steering gear and rudder stock shall be capable of putting the rudder or steering nozzle over from 35° on one side to 35° on the other side with the ship at its deepest seagoing draught and running ahead at maximum ahead service speed and under the same conditions, from 35° on either side to 30° on the other side in not more than 28 s.

**2.9.3** The auxiliary steering shall be capable of putting the rudder or steering nozzle over from 15° on one side to 15° on the other side in not more than 60 s with the ship at its deepest sea going draught and running ahead at one half of the maximum ahead service speed or 7 knots, whichever is the greater.

**2.9.4** In oil tankers, oil tankers (> 60 °C), combination carriers, gas carriers and chemical tankers of 10000 gross tonnage and upwards, in all nuclear ships and in other ships of 70000 gross tonnage and upwards the main steering gear shall comprise two or more identical power units satisfying the requirements of [2.9.5](#) (refer also to 6.2.1.8 and 6.2.1.9 of Part IX "Machinery").

**2.9.5** Where the main steering gear comprises two or more power units, an auxiliary steering gear need not be fitted if:

**.1** in passenger and nuclear ships as well as in special purpose ships having more than 240 persons on board the main steering gear is capable of operating as required in [2.9.2](#) while any one of the power units is out of operation;

**.2** in cargo ships as well as in special purpose ships having 240 or less persons on board the main steering gear is capable of operating as required in [2.9.2](#) while all power units are in operation;

**.3** the main steering gear is so arranged that after a single failure in its piping system or in any one of the power units the defect can be isolated so that steering capability can be maintained or speedily regained.

**2.9.6** Where according to [2.3.1](#) the diameter of the rudder head is required to be over 230 mm, excluding strengthening for navigation in ice, provision shall be made for an additional source of electrical power as prescribed in 5.5.6 of Part XI "Electrical Equipment" sufficient to ensure operation of the steering gear power unit in compliance with the requirements of [2.9.3](#).

**2.9.7** The main steering gear may be hand-operated provided it meets the requirements of 6.2.3.2 of Part IX "Machinery" and the rudder stock and steering nozzle diameter specified in [2.3.1](#) does not exceed 120 mm (excluding strengthening for navigation in ice).

In all other cases, the main steering gear shall be operated by power.

**2.9.8** The auxiliary steering gear may be handoperated provided it meets the requirements of 6.2.3.3 of Part IX "Machinery" and the rudder stock or steering nozzle diameter specified in [2.3.1](#) does not exceed 230 mm (excluding strengthening for navigation in ice).

In all other cases, the auxiliary steering gear shall be operated by power.

**2.9.9** Diameters mentioned in [2.9.6 — 2.9.8](#) shall be taken as having been calculated for rudder stock of mild steel with a yield strength stress of 235 N/mm<sup>2</sup> (i.e. with a material factor  $\eta = 1$ ).

**2.9.10** The main and auxiliary steering gears shall act on the rudder stock independently of one another, but it is allowed that the main and auxiliary steering gears have some common parts (such as tiller, quadrant, gear box, cylinder block, etc.) provided the respective scantlings of these parts are increased in accordance with 6.2.8.2 of Part IX "Machinery".

**2.9.11** The rudder tackle may be considered as an auxiliary steering gear only in the following cases:

- .1 in self-propelled ships of less than 500 gross tonnage;
- .2 in non-propelled ships.

In other cases, the rudder tackle is not considered as a steering gear and shall not necessarily be fitted in ships.

**2.9.12** The rudder shall be provided with a system of rudder stops permitting to put the rudder over either side only to an angle  $\beta^\circ$ :

$$(\alpha^\circ + 1^\circ) \leq \beta \leq (\alpha^\circ + 1,5^\circ) \quad (2.9.12-1)$$

where  $\alpha^\circ$  = maximum hard-over angle to which the steering gear control system is adjusted but not over  $35^\circ$ ; technical background for the greater hard-over angle, based on the constructional features of the steering gear, shall be submitted by the designer.

All the parts of the system of rudder stops, including those which are at the same time the parts of the steering actuator, shall be calculated to take forces corresponding to an ultimate reverse torque  $M_{ult}$ , in kN·m, from the rudder of not less than

$$M_{ult} = 1,135 R_{eH} d^3 \cdot 10^{-4} \quad (2.9.12-2)$$

where  $d$  = actual diameter of the rudder stock head, in cm;  
 $R_{eH}$  = upper yield stress of the rudder stock material, in MPa.

The stresses in these parts shall not exceed 0,95 times the upper yield stress of their material. The rudder stops of the system may be fitted on the sternframe, deck platform, bulkhead or other structural members of the ship's hull. These stops may be built in with the actuator design.

Where an active rudder is installed and putting the rudder over to an angle exceeding the maximum one is required, arrangement of stops at an angle provided by the rudder design may be allowed.

**2.9.13** Control of the main steering gear shall be provided both on the navigation bridge and in the steering gear compartment.

**2.9.14** When the main steering gear is arranged according to [2.9.4](#) or [2.9.5](#), two independent steering gear control systems shall be provided, each of which shall be operable separately from the navigation bridge. These systems may have a common steering wheel or level. If the control system comprises a hydraulic telemotor, the Register may waive the requirement for a second independent control system of the steering gear for the ship (with the exception of oil tankers, oil tankers ( $> 60^\circ\text{C}$ ), combination carriers, gas carriers and chemical tankers of 10000 gross tonnage and upwards, of other ships of 70000 gross tonnage and upwards and of nuclear ships).

**2.9.15** The auxiliary steering gear control shall be provided in the steering gear compartment.

For the auxiliary steering gear which is power operated, control shall also be provided from the navigation bridge and shall be independent of the control system for the main steering gear.

For ships of less than 500 gross tonnage and fishing vessels, the auxiliary steering gear control may not be provided from the steering gear compartment.

**2.9.16** A rudder or steering nozzle angle indicator shall be fitted in the vicinity of each control station of the main and auxiliary steering gears and in the steering gear compartment. The difference between the indicated and actual positions of the rudder or steering nozzle shall be not more than:

- 1° when the rudder or steering nozzle is in the centre line or parallel to it;
- 1,5° for rudder or steering nozzle angles from  $0^\circ$  —  $5^\circ$ ;

2,5° for rudder or steering nozzle angles from 5° — 35°.

The rudder or steering nozzle angle indication shall be independent of the steering gear control system.

**2.9.17** In all other respects the steering gear shall meet the requirements of Part IX "Machinery" and Part XI "Electrical Equipment".

## 2.10 EFFICIENCY OF RUDDERS AND STEERING NOZZLES

### 2.10.1 General.

**2.10.1.1** The choice of the ship's main characteristics affecting the steerability and the characteristics of the rudder and steering nozzle is made at the discretion of the designer and shipowner considering the necessity to ensure the proper steerability of the ship according to its purpose and service conditions and to ensure the correspondence between relative areas of rudders and steering nozzles of the ship under design and the prototype ship provided the total efficiency of the chosen rudders and/or steering nozzles is not less than that required in this Chapter.

**2.10.1.2** The requirements of this Chapter apply to stern rudders and steering nozzles (refer to 2.1.2) provided according to 2.1.1 in self-propelled ships (other than icebreakers) of 20 m and over in length of unrestricted service and restricted area of navigation **R1** sailing in the displacement condition. For ships of restricted areas of navigation **R2** and **R3** the standards set forth in 2.10.3 shall be considered as recommendations.

For ships of river-sea navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** the standards set forth in 2.10.3 shall also be considered as recommendations, and the fulfilment of these standards does not give the grounds for exemption from the fulfilment of the current standards of steerability for ships of inland navigation.

**2.10.1.3** The requirements of this Chapter apply to ships having the geometric characteristics of the hull within the following limits:

$$\begin{aligned} L_1/B &= 3,2 - 8,0; \dots\dots\dots C_B = 0,45 - 0,85; \\ L_1/d &= 8,3 - 28,6; \dots\dots\dots C_p = 0,55 - 0,85; \\ B/d &= 1,5 - 3,5; \dots\dots\dots \sigma_a = 0,80 - 0,99 \end{aligned}$$

where  $B$  = breadth of the ship, in m;

for  $C_B$ ,  $d$ ,  $L_1$ ,  $C_p$  and  $\sigma_a$ , refer to 2.2.2.1, 2.4.1.1 and 2.10.3.3, respectively.

**2.10.1.4** The requirements of this Chapter apply to catamarans with two identical hulls (symmetric about the centreline of the hulls), each having geometric characteristics according to the provisions of 2.10.1.3, and with two identical rudders and/or steering nozzles arranged in the centre plane of each hull.

**2.10.1.5** The active means of the ship's steering which are not the main means of the ship's steering (thrusters, active rudders, etc.) are considered as means supplementing the required minimum and are not taken into account when meeting the requirements of this Chapter (refer also to 2.1.4.2).

### 2.10.2 Estimation of efficiency of rudders and steering nozzles.

**2.10.2.1** The efficiency of the chosen rudder  $E_r$ , other than rudders of types IV, X and XIII (refer to Fig. 2.2.4.1), shall be determined by the formula

$$E_r = \mu_1 \frac{A_1}{A_2} \left( 1 + C_{HB} \frac{A_p}{A} \right) (1 - W)^2 \quad (2.10.2.1-1)$$

$$\text{where } \mu_1 = \frac{6,28}{1 + \frac{2A_1}{h^2}} \quad (2.10.2.1-2)$$

$W$  = coefficient:

for rudder arranged in the centreline behind the propeller

$$W = 0,3C_B; \quad (2.10.2.1-3)$$

for rudder arranged in the centreline with no propeller fitted forward of it

$$W = 0; \quad (2.10.2.1-4)$$

for side rudders

$$W = 0,4C_B - 0,13;$$

(2.10.2.1-5)

$A_2$  = lateral underwater area at the summer load waterline draught, in  $m^2$ ;

for  $A$ ,  $A_p$ ,  $h_r$ ,  $C_B$ , refer to 2.2.2.1;

$C_{HB}$  = value determined by Formula (2.2.3.1-8) with regard to Formula (2.2.3.1-4) at  $W$  as specified in this para with regard to 2.2.2.6; for rudders not operating directly behind the propeller the thrust is taken as  $T = 0$ .

**2.10.2.2** The efficiency of the chosen rudder  $E_{rr}$  of types IV, X or XIII (refer to Fig. 2.2.4.1) shall be determined by the formula

$$E_{rr} = 1,3\mu_2 \frac{A_t}{A_2} (1 - W)^2 \quad (2.10.2.2-1)$$

$$\text{where } \mu_2 = \frac{6,28\sqrt{b_r/b_t}}{1 + \frac{2b_t^2}{A_t}} + \frac{1,4C_{HB}}{1 + 0,5\left(\frac{b_t^2}{A_t}\right)^2} \quad (2.10.2.2-2)$$

where  $b_r$  = breadth of the rudder, in m;

$b_t$  = total breadth of the rudder and rudder post, in m;

for  $A_t$ , refer to 2.2.2.1;

for  $A_2$ ,  $C_{HB}$ ,  $W$ , refer to 2.10.2.1.

**2.10.2.3** The efficiency of the chosen steering nozzle  $E_n$  with or without a stabilizer shall be determined by the formula

$$E_n = 2,86\mu_3 \frac{D_o l_n}{A_2} (1 - W)^2 \quad (2.10.2.3-1)$$

$$\text{where } \mu_3 = \left(0,175 + 0,275 \frac{D_n}{l_n}\right) \left[1 + 0,25(1 + \sqrt{1 + C_{HB}})^2\right] + 0,25C_{HB} \frac{D_n}{l_n} \quad (2.10.2.3-2)$$

$W$  = coefficient:

for steering nozzle arranged in the centreline of the ship

$$W = 0,2C_B;$$

(2.10.2.3-3)

for side steering nozzle

$$W = 0,1C_B;$$

(2.10.2.3-4)

$D_o$  = outside diameter of the steering nozzle in the plane of the propeller disk, in m;

for  $C_B$ ,  $D_n$ ,  $l_n$  and  $A_2$ , refer to 2.2.2.1, 2.2.3.1 and 2.10.2.1, respectively;

$C_{HB}$  = value determined by Formula (2.2.3.1-8) with regard to Formula (2.2.3.1-4) at  $W$  as specified in this para with regard to 2.2.2.6.

### 2.10.3 Standards for efficiency of rudders and steering nozzles.

**2.10.3.1** The total efficiency of all rudders and steering nozzles (refer to 2.10.2) fitted in the ship (other than catamaran) shall not be less than the greater of the values  $E$ ,  $E_1$  or  $E_2$  given below.

**2.10.3.2** The efficiency of the single rudder or steering nozzle fitted in the catamaran which is determined according to 2.10.2 shall not be less than the greater of the values  $E_1$ ,  $E_2$  or  $E_3$  estimated according to the provisions specified below considering each hull of the catamaran as an independent single-screw ship. When determining the side-projected area (windage area), all the above-water structures of the catamaran and the deck cargo (if intended to be carried) are considered as belonging to one hull.

**2.10.3.3** For all ships, other than tugs, rescue and fishing vessels, the value of  $E_1$  is determined depending on the values of  $C_p$  and  $\sigma_a$ :

for single-screw ships — according to Fig. 2.10.3.3-1;

for twin-screw and triple-screw ships — according to Fig. 2.10.3.3-2.

For intermediate values of  $C_p$  the value of  $E_1$  is determined by linear interpolation between the curves for two nearest values of  $C_p$  given in [Figs. 2.10.3.3-1](#) and [2.10.3.3-2](#) where  $C_p$  is prismatic coefficient of the underwater part of the hull at the summer load waterline draught as determined by the formula

$$C_p = C_B / C_m \quad (2.10.3.3-1)$$

where  $C_m$  = coefficient of fineness of midship section at the summer load waterline draught;

$\sigma_a$  = afterbody lateral area coefficient at the summer load waterline draught as determined by the formula

$$\sigma_a = 1 - \frac{2(f-f_0)}{L_1 d} \quad (2.10.3.3-2)$$

where  $L_1$  = length of the ship measured on the summer load waterline from the fore side of the stem to the after side of the after end of the ship, in m;

$f$  = area of side projection of the stern counter, in  $m^2$ , calculated as the area of the figure bounded by the extension line of the keel lower edge, by the perpendicular to this line from the point of intersection of the summer load waterline and the outline of the centreline section of the ship's after end and by the sternframe after edge line drawn ignoring the rudder post, solepiece or rudder horn, if any;

$f_0$  = for twin-screw ships — area of the side projection of the propeller cone (or its part) superimposed on the area of the figure  $f$ , in  $m^2$ . In all other cases  $f_0$  shall be taken as zero;

for  $d$ , refer to [2.4.1.1](#).




Fig. 2.10.3.3-1






Fig. 2.10.3.3-2

**2.10.3.4** For tugs, rescue ships and fishing vessels the value  $E_1$  is determined according to [Fig. 2.10.3.4](#) depending on the value  $\sigma_a$ .




Fig. 2.10.3.4

**2.10.3.5** The value  $E_2$  is determined by the formula

$$E_2 = \frac{3.8A_3}{v^2A_4} \left( 1 - 0.0667 \frac{A_3}{A_4} \right) \left\{ 1 + (\lambda_r - 1) [0.33 + 0.015 \times (v - 7.5)] - 5 \frac{x_0}{L_1} \right\} \quad (2.10.3.5-1)$$

where  $A_3$  = side-projected area at such a minimum draught at which the rudder blade or steering nozzle is fully immersed (at the upright position of the ship), in  $m^2$ , to be determined according to 1.4.6 of Part IV "Stability";

$A_4$  = lateral underwater area at such a minimum draught at which the rudder blade or steering nozzle is fully immersed (at the upright position of the ship), in  $m^2$ ;

$x_0$  = horizontal distance from the midship frame (middle of the length  $L_1$ ) to the centroid of the area  $A_3$ , in m. The value of  $x_0$  is taken to be positive in case the centroid is forward of the midship frame, and negative in case of aft position;

$\lambda_r$  = coefficient determined by the formulae:

for all rudders, other than rudders of types IV, X and XIII ([refer to Fig. 2.2.4.1](#))

$$\lambda_r = h_r^2 / A;$$

$$(2.10.3.5-2)$$

for rudders of types IV, X, XIII ([refer to Fig. 2.2.4.1](#))

$$\lambda_r = h_r^2 / A_t;$$

$$(2.10.3.5-3)$$

for steering nozzles

$$\lambda_r = D_n / l_n \quad (2.10.3.5-4)$$

where for  $v, h_r, A, A_t$ , [refer to 2.2.2.1](#);  
for  $D_n, l_n$ , [refer to 2.2.3.1](#).

**2.10.3.6** For ships of 70 m in length and more, the value  $E_3$  is determined by the formula

$$E_3 = 0,03 + 0,01(\lambda_r - 1) + 0,01 \frac{A_5}{A_2} (1 - 3 \frac{x}{L_1}) \quad (2.10.3.6)$$

where  $A_5$  = side-projected area of the ship at the summer load waterline draught, in  $m^2$ , to be determined according to 1.4.6 of Part IV "Stability";  
 $x$  = horizontal distance from the midship frame (middle of the length  $L_1$ ) to the centroid of the area  $A_5$ , in m. The value of  $x$  is taken to be positive in case the centroid is forward of the midship frame and negative in case of aft position.

For ships of less than 70 m in length  $E_3 = 0$  is taken in the calculations.

**2.10.3.7** For all ships (other than rescue and fishing vessels and tugs, with  $\sigma_a > 0,865$ ) it is permitted in the calculations to take  $E_1$  as zero (if the value of  $E_1$  is greater than any of the values of  $E_2$  or  $E_3$ ) provided it is proved by the test of a self-propelled model not less than 2 m in length (at the speed of the model conforming to the ship's speed  $v$ , [refer to 2.2.2.1](#)) that:

**.1** the steady turning diameter of the ship with the rudder (rudders) or steering nozzle (rudders) put over to  $35^\circ$  on either side is not more than four lengths of the ship;

**.2** the steady spontaneous turning diameter of the ship with non-reversed rudder (rudders) or steering nozzle (rudders)  $D_s$  determined by the formula

$$D_s = (D_{ss} + D_{sp})/2 \quad (2.10.3.7.2)$$

is not less than  $3,35 (D_{ts} + D_{tp})$

where  $D_{ts}$  and  $D_{tp}$  = steady turning diameter of the ship with the rudder or steering nozzle put over to  $35^\circ$  on starboard or port side, respectively;  
 $D_{ss}$  and  $D_{sp}$  = diameter of steady spontaneous turning starboard or port, respectively, with the non-reversed rudder or steering nozzle.

**2.10.3.8** For ships with the displacement exceeding 60000 t and block coefficient exceeding 0,75 at the summer load waterline draught, the compliance with the requirements of [2.10.3.7.1](#) and [2.10.3.7.2](#) shall be proved by testing a self-propelled model of not less than 2 m in length (at the speed of the model conforming to the ship's speed  $v$ , [refer to 2.2.2.1](#)), notwithstanding the fulfilment of the requirements of [2.10.3.1](#).

### 3 ANCHOR ARRANGEMENT

#### 3.1 GENERAL

**3.1.1** Each ship shall be provided with anchoring equipment and also with chain stoppers for securing the bower anchors in hawse pipes, devices for securing and releasing the inboard ends of the chain cables and machinery for dropping and hoisting the bower anchors as well as for holding the ship at the bower anchors dropped.

Besides, in cases specified in [3.6.1.1](#) each bower anchor chain cable shall be provided with a stopper for riding the ship at anchor.

The requirements of this Section for selection of anchoring equipment do not apply to oil tankers of 150 m in length and above as well as bulk carriers of 90 m in length and above, contracted for construction on or after 1 July 2015, but before 1 January 2022. The requirements for anchoring equipment of the said ships are regulated by the IACS Common Structural Rules for Bulk Carriers and Oil Tankers<sup>1</sup>.

**3.1.2** If a ship in addition to the anchor arrangement or anchoring equipment specified in [3.1.1](#) is provided with some other anchor arrangement or anchoring equipment (for example, special anchors and winches on dredgers, mooring anchors on lightships, etc.), such anchor arrangement or anchoring equipment is regarded as special one and is not subject to the Register survey. The use of anchor arrangement specified in [3.1.1](#) as a working special arrangement for moving the dredgers and also for holding the dredgers in place in the course of dredging carried out by grabs may be allowed; in so doing the required data characterizing the conditions of work of anchor arrangement elements (the value and degree of dynamics of acting forces, the degree of intensity of work and wear rate of the anchor arrangement elements, etc.) shall be submitted.

**3.1.3** For all ships other than fishing vessels, the anchoring equipment shall be selected from [Table 3.1.3-1](#), for fishing vessels — from [Table 3.1.3-2](#). For fishing vessels, when Equipment Number exceeds 720, the anchoring equipment shall be selected from [Table 3.1.3-1](#).

The Equipment Number is determined in compliance with [3.2](#) for ships of unrestricted service and of restricted area of navigation **R1**, and is reduced:

by 15 % for ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN**;

by 25 % for ships of restricted area navigation **R3**, taking into account of the provisions specified in [3.1.4](#), [3.3.1](#), [3.3.2](#), [3.4.1](#), [3.4.2](#) and [3.4.3](#).

Table 3.1.3-1

Equipment Number EN		Bower anchors		Mass of stream anchor, in kg	Chain cables for bower anchors			Stream wire or chain		Tow line		Mooring lines				
Exceeding	Not exceeding	Number	Mass of anchor, in kg		Total length of both chain cables, in m	Diameter			Length, in m	Chain cable breaking load or breaking strength of wire rope, in kN	Length, in m	Minimum breaking strength, in kN	Number	Length of each line, in m	Minimum breaking strength, in kN	
						Ordinary (grade 1), in mm	Special quality (grade 2), in mm	Extra special quality (grade 3), in mm								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	
10	15	2	35	—	110	1)	—	—	—	—	—	—	2	30	29	
15	20	2	50	—	137,5		—	—	—	—	—	—	—	2	30	29
20	25	2	65	—	165		—	—	—	—	—	—	—	2	40	29
25	30	2	80	—	165	11,0	—	—	—	—	—	—	2	50	29	
30	40	2	105	35	192,5	11,0	—	—	55	55	120	65	2	50	29	

<sup>1</sup> Hereinafter referred to as "the IACS Common Structural Rules".

Equipment Number EN		Bower anchors		Mass of stream anchor, in kg	Chain cables for bower anchors				Stream wire or chain		Tow line		Mooring lines			
Exceeding	Not exceeding	Number	Mass of anchor, in kg		Total length of both chain cables, in m	Diameter			Length, in m	Chain cable breaking load or breaking strength of wire rope, in kN	Length, in m	Minimum breaking strength, in kN	Number	Length of each line, in m	Minimum breaking strength, in kN	
						Ordinary (grade 1), in mm	Special quality (grade 2), in mm	Extra special quality (grade 3), in mm								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	
40	50	2	135	45	192,5	12,5	–	–	70	60	150	81	2	60	29	
50	70	2	180	60	220	14	12,5	–	80	64,7	180	98	3	80	37	
70	90	2	240	80	220	16	14	–	85	73,5	180	98	3	100	40	
90	110	2	300	100	247,5	17,5	16	–	85	80	180	98	3	110	42	
110	130	2	360	120	247,5	19	17,5	–	90	89,2	180	98	3	110	48	
130	150	2	420	140	275	20,5	17,5	–	90	98,1	180	98	3	120	53	
150	175	2	480	165	275	22	19	–	90	107,9	180	98	3	120	59	
175	205	2	570	190	302,5	24	20,5	–	90	117,7	180	112	3	120	64	
205	240	2	660	–	302,5	26	22	20,5	–	–	180	129	4	120	69	
240	280	2	780	–	330	28	24	22	–	–	180	150	4	120	75	
280	320	2	900	–	357,5	30	26	24	–	–	180	174	4	140	80	
320	360	2	1020	–	357,5	32	28	24	–	–	180	207	4	140	85	
360	400	2	1140	–	385	34	30	26	–	–	180	224	4	140	96	
400	450	2	1290	–	385	36	32	28	–	–	180	250	4	140	107	
450	500	2	1440	–	412,5	38	34	30	–	–	180	276	4	140	117	
500	550	2	1590	–	412,5	40	34	30	–	–	190	306	4	160	134	
550	600	2	1740	–	440	42	36	32	–	–	190	338	4	160	143	
600	660	2	1920	–	440	44	38	34	–	–	190	371	4	160	160	
660	720	2	2100	–	440	46	40	36	–	–	190	406	4	160	171	
720	780	2	2280	–	467,5	48	42	36	–	–	190	441	4	170	187	
780	840	2	2460	–	467,5	50	44	38	–	–	190	480	4	170	202	
840	910	2	2640	–	467,5	52	46	40	–	–	190	518	4	170	218	
910	980	2	2850	–	495	54	48	42	–	–	190	559	4	170	235	
980	1060	2	3060	–	495	56	50	44	–	–	200	603	4	180	250	
1060	1140	2	3300	–	495	58	50	46	–	–	200	647	4	180	272	
1140	1220	2	3540	–	522,5	60	52	46	–	–	200	691	4	180	293	
1220	1300	2	3780	–	522,5	62	54	48	–	–	200	738	4	180	309	
1300	1390	2	4050	–	522,5	64	56	50	–	–	200	786	4	180	336	
1390	1480	2	4320	–	550	66	58	50	–	–	200	836	4	180	352	
1480	1570	2	4590	–	550	68	60	52	–	–	220	888	5	190	352	
1570	1670	2	4890	–	550	70	62	54	–	–	220	941	5	190	362	
1670	1790	2	5250	–	577,5	73	64	56	–	–	220	1024	5	190	384	
1790	1930	2	5610	–	577,5	76	66	58	–	–	220	1109	5	190	411	
1930	2080	2	6000	–	577,5	78	68	60	–	–	220	1168	5)	190	437	
2080	2230	2	6450	–	605	81	70	62	–	–	240	1259			200	2)
2230	2380	2	6900	–	605	84	73	64	–	–	240	1356			200	
2380	2530	2	7350	–	605	87	76	66	–	–	240	1453			200	
2530	2700	2	7800	–	632,5	90	78	68	–	–	260	1471			200	
2700	2870	2	8300	–	632,5	92	81	70	–	–	260	1471			200	
2870	3040	2	8700	–	632,5	95	84	73	–	–	260	1471			200	
3040	3210	2	9300	–	660	97	84	76	–	–	280	1471			200	
3210	3400	2	9900	–	660	100	87	78	–	–	280	1471			200	
3400	3600	2	10500	–	660	102	90	78	–	–	280	1471			200	
3600	3800	2	11100	–	687,5	105	92	81	–	–	300	1471			200	
3800	4000	2	11700	–	687,5	107	95	84	–	–	300	1471			200	
4000	4200	2	12300	–	687,5	111	97	87	–	–	300	1471		200		

Equipment Number EN		Bower anchors		Mass of stream anchor, in kg	Chain cables for bower anchors				Stream wire or chain		Tow line		Mooring lines		
Exceeding	Not exceeding	Number	Mass of anchor, in kg		Total length of both chain cables, in m	Diameter			Length, in m	Chain cable breaking load or breaking strength of wire rope, in kN	Length, in m	Minimum breaking strength, in kN	Number	Length of each line, in m	Minimum breaking strength, in kN
						Ordinary (grade 1), in mm	Special quality (grade 2), in mm	Extra special quality (grade 3), in mm							
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
4200	4400	2	12900	–	715	114	100	87	–	–	300	1471	2)	200	2)
4400	4600	2	13500	–	715	117	102	90	–	–	300	1471		200	
4600	4800	2	14100	–	715	120	105	92	–	–	300	1471		200	
4800	5000	2	14700	–	742,5	122	107	95	–	–	300	1471		200	
5000	5200	2	15400	–	742,5	124	111	97	–	–	300	1471		200	
5200	5500	2	16000	–	742,5	127	111	97	–	–	300	1471		200	
5500	5800	2	16900	–	742,5	130	114	100	–	–	300	1471		200	
5800	6100	2	17800	–	742,5	132	117	102	–	–	300	1471		200	
6100	6500	2	18800	–	742,5	–	120	107	–	–				200	
6500	6900	2	20000	–	770	–	124	111	–	–	Tow lines are not required when ship's length exceeds 180 m	200			
6900	7400	2	21500	–	770	–	127	114	–	–		200			
7400	7900	2	23000	–	770	–	132	117	–	–		200			
7900	8400	2	24500	–	770	–	137	122	–	–		200			
8400	8900	2	26000	–	770	–	142	127	–	–		200			
8900	9400	2	27500	–	770	–	147	132	–	–		200			
9400	10000	2	29000	–	770	–	152	132	–	–		200			
10000	10700	2	31000	–	770	–	–	137	–	–		200			
10700	11500	2	33000	–	770	–	–	142	–	–		200			
11500	12400	2	35500	–	770	–	–	147	–	–		200			
12400	13400	2	38500	–	770	–	–	152	–	–		200			
13400	14600	2	42000	–	770	–	–	157	–	–		200			
14600	16000	2	46000	–	770	–	–	162	–	–		200			

<sup>1)</sup> Chain cables or wire ropes may be used, chain cable breaking load or breaking strength of wire rope being not less than 44 kN.

<sup>2)</sup> Refer to 3.2.5.

Table 3.1.3-2

Equipment Number EN		Bower anchors		Chain cables for bower anchors			Mooring lines		
Exceeding	Not exceeding	Number	Mass per. anchor, in kg	Total length, in m	Diameter		Number	Length of each line, in m	Minimum breaking strength, in kN
					grade 1, in mm	grade 2, in mm			
1	2	3	4	5	6	7	8	9	10
10	15	1	30	55	1)	–	2	30	29
15	20	1	40	55		–	2	30	29
20	25	1	50	82,5		–	2	40	29
25	30	1	60	82,5	1)	–	2	50	29
30	40	2	80	165	11,0	–	2	50	29
40	50	2	100	192,5	11,0	–	2	60	29
50	60	2	120	192,5	12,5	–	2	60	29
60	70	2	140	192,5	12,5	–	2	80	29
70	80	2	160	220	14	12,5	2	100	34
80	90	2	180	220	14	12,5	2	100	37
90	100	2	210	220	16	14	2	110	37
100	110	2	240	220	16	14	2	110	39
110	120	2	270	247,5	17,5	16	2	110	39

Equipment Number EN		Bower anchors		Chain cables for bower anchors			Mooring lines		
Exceeding	Not exceeding	Number	Mass per. anchor, in kg	Total length, in m	Diameter		Number	Length of each line, in m	Minimum breaking strength, in kN
					grade 1, in mm	grade 2, in mm			
1	2	3	4	5	6	7	8	9	10
120	130	2	300	247,5	17,5	16	2	110	44
130	140	2	340	275	19	17,5	2	120	44
140	150	2	390	275	19	17,5	2	120	49
150	175	2	480	275	22	19	2	120	54
175	205	2	570	302,5	24	20,5	2	120	59
205	240	2	660	302,5	26	22	2	120	64
240	280	2	780	330	28	24	3	120	71
280	320	2	900	357,5	30	26	3	140	78
320	360	2	1020	357,5	32	28	3	140	86
360	400	2	1140	385	34	30	3	140	93
400	450	2	1290	385	36	32	3	140	100
450	500	2	1440	412,5	38	34	3	140	108
500	550	2	1590	412,5	40	34	4	160	113
550	600	2	1740	440	42	36	4	160	118
600	660	2	1920	440	44	38	4	160	123
660	720	2	2100	440	46	40	4	160	128

<sup>1)</sup> Chain cables or wire ropes may be used, chain cable breaking load or breaking strength of wire rope being not less than 44 kN.

**3.1.4** For non-propelled ships the anchoring equipment shall be selected based on Equipment Number increased by 25 % as against that calculated in compliance with provisions specified in [3.1.3](#) of this Part of the Rules. For self-propelled ships having the maximum ahead speed not more than 6 knots at the draught to the summer load waterline, the anchoring equipment shall be selected as in the case of non-propelled ships.

The anchor arrangement of shipborne barges and berth-connected ships shall comply with the requirements of Section 3 of Part III "Equipment, Arrangements and Outfit" of the Rules for the Classification and Construction of Inland Navigation Ships (for European Inland Waterways). For the case of sea passage of berth-connected ships having no permanent anchor arrangement, provision shall be made for anchors and anchor chains to be arranged on board.

For non-propelled ships, the anchor arrangement may not be provided. In this case, for temporary holding of the non-propelled ships, the towing ship anchor arrangement may be considered. At that, technical background for ensuring holding anchorage under stormy conditions including Equipment Numbers for supply vessels, safety factors, environmental effects and loads, shall be submitted to the Register.

For non-propelled ships, the position mooring system may be used as anchor arrangement.

**3.1.5** For remote control systems of the anchor arrangements, if any, the type, extent of automated control and scope of remote control operations are determined by the shipowner.

The additional requirements for the remote-controlled anchor arrangements are given in [3.6.5](#) of this Part, 6.3.6 of Part IX "Machinery", and also in 5.1.3 of Part XI "Electrical Equipment".

### 3.2 EQUIPMENT NUMBER

**3.2.1** The Equipment Number  $EN$  for all ships other than floating cranes and tugs, is determined by the formula

$$EN = \Delta^{\frac{2}{3}} + 2(hB + S_{fun}) + \frac{A}{10} \quad (3.2.1-1)$$

where  $\Delta$  – moulded displacement, in t, to the summer load waterline;  
 $B$  – breadth of the ship, in m;  
 $h$  – effective height, in m, from the summer load waterline to the top of the uppermost deckhouse, in m, which is determined by the formula

$$h = a + \sum h_i \quad (3.2.1-2)$$

where  $a$  – vertical distance at hull side, in m, from the summer load waterline amidships to the upper deck;

$h_i$  – height, in m, at the centreline of each tier of superstructures or deckhouses having a breadth greater than  $B/4$ , for the lowest tier  $h_1$  shall be measured at the centreline from the upper deck or from a notional deck line where there is local discontinuity in the upper deck, refer to [Fig. 3.2.1-1](#);

$S_{fun}$  – effective front projected area of the funnel, in m<sup>2</sup>, determined by the formula:

$$S_{fun} = A_{FS} - S_{shield} \quad (3.2.1-3)$$

$A_{FS}$  – front projected area of the funnel, in m<sup>2</sup>, calculated between the upper deck at centreline, or notional deck line where there is local discontinuity in the upper deck, and the effective height  $h_F$ .

$A_{FS}$  is taken equal to zero if the funnel breadth is less than or equal to  $B/4$  at all elevations along the funnel height;

$h_F$  – effective height of the funnel, in m, measured from the upper deck at centreline, or notional deck line where there is local discontinuity in the upper deck, and the top of the funnel.  
The top of the funnel may be taken at the level where the funnel breadth reaches  $B/4$ .

$S_{shield}$  – the section of front projected area  $A_{FS}$ , in m<sup>2</sup>, which is shielded by all deckhouses having breadth greater than  $B/4$ . If there are more than one shielded section, the individual shielded sections, i.e.  $S_{shield1}$ ,  $S_{shield2}$  etc. as shown in [Fig. 3.2.1-2](#) shall be added together. To determine  $S_{shield}$ , the deckhouse breadth is assumed  $B$  for all deckhouses having breadth greater than  $B/4$  as shown for  $S_{shield1}$ ,  $S_{shield2}$  in [Fig. 3.2.1-2](#);

$A$  – side projected area, in m<sup>2</sup>, of the hull, superstructures, deckhouses and funnels above the summer load waterline which are within the equipment length of the ship  $L$  and also have a breadth greater than  $B/4$ . The side projected area of the funnel is considered in  $A$  when  $A_{FS}$  is greater than zero. In this case, the side projected area of the funnel shall be calculated between the upper deck, or notional deck line where there is local discontinuity in the upper deck, and the effective height  $h_F$ .




Fig. 3.2.1-1




Fig. 3.2.1-2

## Notes:

1. When calculating  $h$ , sheer and trim shall be ignored, i.e.  $h$  is the sum of freeboard amidships plus the height (at centreline) of each tier of houses having a breadth greater than  $B/4$ .
2. If a house having a breadth greater than  $B/4$  is above a house with a breadth of  $B/4$  or less, then the wide house shall be included but the narrow house ignored.
3. Screens or bulwarks 1,5 m or more in height shall be regarded as parts of houses when determining  $h$  and  $A$ . The height of the hatch coamings and that of any deck cargo, such as containers, may be disregarded when determining  $h$  and  $A$ .  
With regard to determining  $A$ , when a bulwark is more than 1,5 m high, the area shown as  $A_2$  (refer to [Fig. 3.2.1-3](#)) shall be included in  $A$ .






Fig. 3.2.1-3

4. The equipment length of the ship is the length between perpendiculars but shall not be less than 96 % nor greater than 97 % of the extreme length on the summer load waterline (measured from the forward end of the waterline).
5. When several funnels are fitted on the ship, the above parameters are taken as follows:
  - $h_F$  — effective height of the funnel, in m, measured from the upper deck, or notional deck line where there is local discontinuity in the upper deck, and the top of the highest funnel. The top of the highest funnel may be taken at the level where the sum of each funnel breadth reaches  $B/4$ ;
  - $A_{FS}$  — sum of the front projected area of each funnel, in  $m^2$ , calculated between the upper deck, or notional deck line where there is local discontinuity in the upper deck, and the effective height  $h_F$ .  
 $A_{FS}$  shall be taken equal to zero if the sum of each funnel breadth is less than or equal to  $B/4$  at all elevations along the funnels height;
  - $A$  — side projected area, in  $m^2$ , of the hull, superstructures, deckhouses and funnels above the summer load waterline which are within the equipment length of the ship. The total side projected area of the funnels shall be considered in the side projected area of the ship  $A$ , when  $A_{FS}$  is greater than zero. The shielding effect of funnels in transverse direction may be considered in the total side projected area, i.e., when the side projected areas of two or more funnels fully or partially overlap, the overlapped area needs only to be counted once.

### 3.2.2 The Equipment Number $EN$ for tugs is determined by the formula

$$EN = \Delta^{2/3} + 2(Ba + \sum h_i b_i) + 0,1A \quad (3.2.2)$$

where  $\Delta, B, a, h_i$  and  $A$  are taken according to 3.2.1;

$b_i$  = breadth of the appropriate tier of superstructure or deckhouse, in m. In case of ships with two or more superstructures or deckhouses along the length, the relevant provisions of 3.2.1 shall be followed.

**3.2.3** Main gallows, ladders and pile drivers for lifting the ladders of dredgers may be ignored when determining  $h$ ; when determining the value  $A$ , the side-projected area of these structures shall be calculated as the area limited by the contour of the structure.

### 3.2.4 The Equipment Number $EN$ for floating cranes is determined by the formula

$$EN = 1,5\Delta^{2/3} + 2Bh + 2S + 0,1A \quad (3.2.4)$$

where  $\Delta, B, h$  and  $A$  are taken according to 3.2.1; when determining the value of  $A$ , account shall be taken of the side-projected area of the upper structure of floating crane (stowed for sea) which is calculated as the area limited by the outer contour of the structure;

$S$  = projection on the mid-section of the front area, in  $m^2$ , of the upper structure of the floating crane (stowed for sea) situated above the deck of the uppermost deckhouse taken into account in determination of  $h$ , the front area being determined, in this case, as the area limited by the outer contour of the structure.

**3.2.5** For ships with an equipment length of not less than 135 m, intended to anchor in deep and unsheltered water, as well as to anchor in water with depth up to 120 m, current with up to 1,54 m/s, wind with up to 14 m/s and waves with significant height of up to 3 m, the anchoring equipment shall be selected according to [3.2.5.1 — 3.2.5.3](#).

**3.2.5.1** The scope of chain cable is defined as the ratio between the length of chain paid out and water depth, and is assumed to be not less than 3 to 4.

**3.2.5.2** Anchors and chain cables shall be in accordance with [Table 3.2.5.2](#) and based on the Equipment Number  $EN_1$  obtained from the following formula:

$$EN_1 = 0,628 \left[ a \left( \frac{EN}{0,628} \right)^{\frac{1}{2,3}} + b(1 - a) \right]^{2,3} \quad (3.2.5.2)$$

where  $a = 1,83 \cdot 10^{-9} \cdot L^3 + 2,09 \cdot 10^{-6} \cdot L^2 - 6,21 \cdot 10^{-4} \cdot L + 0,0866$ ;

$b = 0,156 \cdot L + 8,372$ ;

$L$  = the equipment length of the ship between perpendiculars which shall not be less than 96 % nor greater than 97 % of the extreme length on the summer load waterline (measured from forward end of the waterline);

$EN$  = Equipment Number calculated in compliance with [3.2.1](#).

Anchors shall be of the stockless high holding power (HHP) type. The mass of the head of a stockless anchor, including pins and fittings, shall not be less than 60 % of the total mass of the anchor. HHP anchors shall comply with the requirements of 8.1.3.2 of Part XIII "Materials".

The mass, per anchor, of bower anchors given in [Table 3.2.5.2](#) is for anchors of equal mass. The mass of individual anchors may vary to 7 % of the tabular mass, but the total mass of anchors shall not be less than that recommended for anchors of equal mass.

Suitable arrangements shall be provided for securing the anchors in accordance with [3.6.1.2](#).

Table 3.2.5.2

**Anchoring equipment for ships in unsheltered water with depth up to 120 m**

Equipment Number $EN_1$		High holding power stockless bower anchors		Chain cable for bower anchors		
Equal to or greater than	Less than	Number	Mass per anchor ( $m_A$ ), in kg	Length, in m	Min. diameter ( $d$ )	
					Grade 2, in mm	Grade 3, in mm
	1790	2	14150	1017,5	105	84
1790	1930	2	14400	990	105	84
1930	2080	2	14800	990	105	84
2080	2230	2	15200	990	105	84
2230	2380	2	15600	990	105	84
2380	2530	2	16000	990	105	84
2530	2700	2	16300	990	105	84
2700	2870	2	16700	990	105	84
2870	3040	2	17000	990	105	84
3040	3210	2	17600	990	105	84
3210	3400	2	18000	990	105	84
3400	3600	2	18300	990	106	84
3600	3800	2	19000	990	107	85
3800	4000	2	19700	962,5	108	87
4000	4200	2	20300	962,5	111	90
4200	4400	2	21100	962,5	114	92
4400	4600	2	22000	962,5	117	95
4600	4800	2	22900	962,5	119	97
4800	5000	2	23500	962,5	122	99
5000	5200	2	24000	935	125	102

Equipment Number $EN_1$		High holding power stockless bower anchors		Chain cable for bower anchors		
Equal to or greater than	Less than	Number	Mass per anchor ( $m_A$ ), in kg	Length, in m	Min. diameter ( $d$ )	
					Grade 2, in mm	Grade 3, in mm
5200	5500	2	24500	907,5	130	105
5500	5800	2	25000	907,5	133	107
5800	6100	2	25500	880	137	111
6100	6500	2	25700	880	140	113
6500	6900	2	26000	852,5	143	115
6900	7400	2	26500	852,5	147	119
7400	7900	2	27000	825	152	121
7900	8400	2	27500	825	154	123
8400	8900	2	28000	797,5	158	127
8900	9400	2	28900	770	162	132
9400	10000	2	29400	770	—	135
10000	10700	2	29900	770	—	139
10700	11500	2	30600	770	—	143
11500	12400	2	31500	770	—	147
12400	13400	2	33200	770	—	152
13400	14600	2	35000	770	—	157
14600		2	38000	770	—	162

### 3.2.5.3 Chain cables for bower anchors.

Bower anchors shall be associated with chain cables of Grade 2 or Grade 3. The total length of chain cable, as given in [Table 3.2.5.2](#) shall be divided between the two bower anchors.

The application of the requirements of 6.3 of Part IX "Machinery" is recommended for the anchor windlass design and testing.

Notwithstanding the requirements according to 6.3 of Part IX "Machinery", the windlass unit prime mover shall be able to supply for at least 30 min a continuous duty pull  $Z_{cont}$ , in N, determined by the formula:

$$Z_{cont} = 35 d^2 + 13,4 m_A \quad (3.2.5.3)$$

where  $d$  = chain diameter as per [Table 3.2.5.2](#), in mm;  
 $m_A$  = HHP anchor mass as per [Table 3.2.5.2](#), in kg.

In addition to the requirements of 6.3 of Part IX "Machinery", as far as practicable, for testing purpose the speed of the chain cable during hoisting of the anchor and cable shall be measured over 37,5 m of chain cable and initially with at least 120 m of chain and the anchor submerged and hanging free. The mean speed of the chain cable during hoisting of the anchor from the depth of 120 m to the depth of 82,5 m shall be at least 4,5 m/min.

### 3.3 BOWER AND STREAM ANCHORS

**3.3.1** The mass and number of anchors shall be selected in accordance with [3.1.3](#).

Anchors of the following types are permitted to be used in ships:

- .1 ordinary stockless anchors and stock anchors (Hall's, Gruson's, admiralty anchors);
- .2 high holding power (HHP) anchors;
- .3 super high holding power (SHHP) anchors in accordance with [3.3.4](#).

Ships with Equipment Number of 205 and less may have the second bower anchor as a spare one on condition that provision is made for its quick getting ready for use.

Ships of restricted area of navigation **R3** with Equipment Number of 35 and less, if they are not passenger ships, may have only one bower anchor.

**3.3.2** Ships of restricted areas of navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** with Equipment Number in excess of 205 except the values stated in [Table 3.1.3-1](#), shall be equipped with a stream anchor whose mass is at least 75 % of that required for a bower anchor.

For ships of restricted area of navigation **R3**, a stream anchor may be omitted.

In case the installation of stream anchors on board will affect the proper operation of the ship according to its intended purpose, a stream anchor may be omitted.

**3.3.3** When HHP anchors of proven superior holding power are used as bower anchors, the mass of each anchor shall be 75 % of the mass required for ordinary stockless bower anchors in [Table 3.1.3-1](#) or [3.1.3-2](#). When SHHP anchor of proven holding power are used as bower anchors, the mass of each anchor shall be reduced to not less than 50 % of the mass required for ordinary stockless bower anchors in [Table 3.1.3-1](#) or [3.1.3-2](#). For fishing vessels with Equipment Number up to 980, where anchor chain cable is replaced with ropes, the mass of the anchor shall be increased by 25 % of the mass of the chosen anchor type.

For approval and/or acceptance as a HHP anchor satisfactory full scale tests in accordance with A1.4.2 of IACS UR A1 (Rev.7 Sep 2020 Corr.1 Sep 2021) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)) shall be done confirming that the anchor has a holding power at least twice that of an ordinary stockless anchor of the same mass.

For approval and/or acceptance as a SHHP anchor satisfactory full scale tests in accordance with A1.4.2 of IACS UR A1 (Rev.7 Sep 2020 Corr.1 Sep 2021) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)) shall be done confirming that the anchor has a holding power at least four times that of an ordinary stockless anchor of the same mass. Similar full scale tests shall be done for HHP anchor confirming that the SHHP anchor has a holding power at least twice that of a previously approved HHP anchor of the same mass. The scope and procedure for such tests are specified in A1.4.2 of IACS UR A1 (Rev.7 Sep 2020 Corr.1 Sep 2021) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)).

**3.3.4** SHHP anchors are suitable for use in ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)**, **R3-RSN** and **R3**. The SHHP anchor mass shall not generally exceed 1500 kg.

### 3.4 CHAIN CABLES AND ROPES FOR BOWER ANCHORS

**3.4.1** Ship's with Equipment Number 205 and less, in which the second bower anchor is permitted to be a spare one, and also ships with Equipment Number 35 and less and provided according to [3.3.1](#) with only one bower anchor may be equipped with only one chain cable the length of which is two times less than that required in the relevant Equipment Table for two chain cables. For ships of restricted area of navigation **R3** chain cables or wire ropes for a stream anchor may be omitted.

**3.4.2** For ships having a descriptive notation **Supply vessel** in their class notation, the total length of both chain cables for bower anchors shall be taken 165 m greater than the value specified in [Table 3.1.3-1](#), and the diameter of these chain cables shall be taken not less than that given in [Table 3.1.3-1](#) two lines below the Equipment Number for the considered ship (having regard to the provisions of [3.1.3](#) and [3.1.4](#)). For supply vessels having a distinguishing mark for ships fitted with a dynamic positioning system in their class notation, this requirement may be waived.

For supply vessels having Equipment Number over 720 at the specification depth of the anchorage over 250 m and for those having Equipment Number 720 and less at the specification depth of the anchorage over 200 m, the length and diameter of chain cables for bower anchors shall be increased taking account of the specification depths and conditions of the anchorage.

**3.4.3** For hopper barges and dredgers not having hoppers to transport spoil, the diameter of chain cables for bower anchors shall be taken not less than that specified in [Table 3.1.3-1](#) two lines below the Equipment Number of the considered ship, and for dredgers having hoppers to transport spoil, one line below (taking account of the provisions of [3.1.3](#) and [3.1.4](#)).

**3.4.4** Chain cables of bower anchors shall be graded dependent on their strength as specified in 7.1 of Part XIII "Materials".

**3.4.5** [Tables 3.1.3-1](#) and [3.1.3-2](#) specify the diameters of chain cables on the assumption that the links of these chain cables are provided with studs, with the exception of the chain cables less than 15 mm in diameter which are assumed to have no studs.

**3.4.6** The chain cables shall be composed of separate chain lengths, except for the chains less than 15 mm in diameter which need not be divided into chain lengths. The lengths of chains shall be not less than 25 m and not over 27,5 m and shall be interconnected with joining links.

The chain cables shall also meet the requirements of 7.1 of Part XIII "Materials".

**3.4.7** For ships under 40 m in length the chain cables may be replaced with wire ropes. For fishing vessels with Equipment Number up to 980, independently of their length, chain cables may be replaced with ropes, taking account of the requirements of [3.3.3](#). Minimum breaking strength of such ropes shall be not less than the breaking load of the corresponding chain cables, and the length shall be at least 1,5 times the length of chain cables.

Wire ropes of trawl winches complying with this requirement may be used as anchor cables.

Ships having Equipment Number 130 and less may be equipped with synthetic fibre ropes instead of chain cables or wire ropes.

**3.4.8** The wire rope shall be connected to the anchor by means of a chain cable section having a length equal to the distance between the anchor (in stowed for sea position) and the anchor machinery or 12,5 m, whichever is the less; a breaking load of the above chain section shall be not less than the breaking strength of the wire rope.

The length of the chain cable sections may be included into 1,5 times the length of wire ropes specified in [3.4.7](#).

**3.4.9** The wire ropes for anchors shall have at least 114 wires and one natural fibre core. The wires of the ropes shall have a zinc coating according to recognized standards.

In all other respects, the wire ropes for anchors shall meet the requirements of 3.15 of Part XIII "Materials".

### **3.5 CHAIN CABLE OR WIRE ROPE FOR STREAM ANCHOR**

**3.5.1** Stream anchor chain cables shall meet the applicable requirements of [3.4](#).

Ships of restricted areas of navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** with Equipment Number in excess of 205 shall be equipped with a stream anchor chain cable whose length is at least 60 % of that required for a bower anchor chain cable. The chain cable diameter shall be taken not less than that mentioned in [Table 3.1.3-1](#) two lines above the Equipment Number of the ship in question (taking into account [3.1.3](#) and [3.1.4](#)).

Ships having Equipment Number below 205 may be equipped with studless chain cables.

**3.5.2** The requirements of [3.4.8](#) and [3.4.9](#) are applicable to the wire rope for the stream anchor.

### 3.6 ANCHOR APPLIANCES

#### 3.6.1 Stoppers.

**3.6.1.1** Each bower anchor chain cable or rope and each stream anchor chain cable having a mass of 200 kg and above shall be provided with a stopper holding the anchor in the hawse pipe when stowed for sea or, in addition, intended for riding the ship at anchor.

In ships having no anchor machinery or having the anchor machinery, which is not in compliance with the requirements of 6.3.2.3.2 of Part IX "Machinery" provision of stoppers for riding the ship at anchor is obligatory.

**3.6.1.2** Where the stoppers is intended only for securing the anchor in the hawse pipe when stowed for sea, its parts shall be calculated to withstand the chain cable strain equal to twice the weight of the anchor, the stresses in the stopper parts not exceeding 0,4 times the upper yield stress of their material. Where the stopper comprises a chain cable or rope, this shall have safety factor 5 in relation to the breaking load of the chain cable or minimum breaking strength of the rope under the action of a force equal to twice the weight of the anchor.

**3.6.1.3** Where the stopper is intended for riding the ship at anchor, its parts shall be calculated on assumption that the stopper will be subjected to a force in the chain cable equal to 0,8 times its breaking load. The stresses in the stopper parts shall not exceed 0,95 times the upper yield stress of their material. Where the stopper comprises a chain cable or rope, they shall have strength equal to that of the chain cable for which they are intended.

**3.6.1.4** In fiber-reinforced plastic ships the stoppers shall be fastened by bolts with the use of steel gaskets or wooden pads on the deck and under deck flooring between the framing. Bolt connections shall comply with the requirements of 1.7.4 of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".

#### 3.6.2 Device for securing and releasing the inboard end of the chain cable.

**3.6.2.1** The parts of the device for securing and releasing the inboard end of the chain cable shall be able to withstand a force not less than 15 % *BL* nor more than 30 % *BL* (where *BL* = breaking load of the chain cable).

**3.6.2.2** The fastening shall be provided with a mean suitable to permit, in case of emergency, an easy slipping of the chain cables to sea, operable from an accessible position outside the chain locker.

**3.6.2.3** In fiber-reinforced plastic ships, the device for securing and releasing the inboard end of the chain cable shall be fastened by bolts with the use of steel gaskets on both sides of the bulkhead. Bolt connections shall comply with the requirements of 1.7.4 of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".

#### 3.6.3 Laying of chain cables.

**3.6.3.1** Laying of chain cables shall provide for their free run when dropping or hoisting the anchors.

In ships with a bulbous bow laying of chain cables shall comply with the requirements of 2.8.2.4 of Part II "Hull".

**3.6.3.2** The anchor shank shall easily enter the hawse pipe under the mere action of the chain cable tension and shall readily take off the hawse pipe when the chain cable is released.

**3.6.3.3** The thickness of the hawse pipe shall not be less than 0,4 times the diameter of the chain cable passing through the hawse pipe.

**3.6.3.4** In fiber-reinforced plastic ships galvanized or stainless steel plates shall be fitted on the outside plating under the hawse pipes; the plates shall be fastened by countersunk bolts.

Bolt connections shall comply with the requirements of 1.7.4 of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".



**3.6.4 Chain lockers.**

**3.6.4.1** For stowage of each bower anchor chain lockers shall be provided.

When one chain locker is designed for two chains, it shall be provided with an internal permeable or watertight division so that separate stowage of each chain is ensured.

**3.6.4.2** The chain locker shall be of shape, capacity and depth adequate to provide an easy direct lead of the cables through the chain pipes, an easy self-stowing of the cables and their free veering away when dropping the anchors.

**3.6.4.3** The chain locker design, as well as chain and hawse pipes shall be watertight up to the weather deck. Upper openings of such pipes shall be fitted with the permanent buckler plates. These may be made both of steel with the relevant cutouts for a chain cable diameter and of canvas with the relevant fastenings to keep the plate closed down.

The openings for access to the chain locker shall be fitted with covers secured with closely spaced bolts.

Where a means of access to chain lockers or chain or hawse pipes is located below the weather deck, the watertight cover shall be in accordance with international, national or other equivalent standards (for example, ISO 5894:2018, GOST 2021-90, etc.). Butterfly nuts and/or hinged bolts are prohibited as the securing mechanism for the cover.

**3.6.4.4** Drainage of chain lockers shall comply with the requirements in 7.12.1 of Part VIII "Systems and Piping", and lighting — with the requirements of 6.7 of Part XI "Electrical Equipment".

**3.6.5 Additional requirements for remote-controlled anchor appliances.**

**3.6.5.1** Stoppers and other anchor appliances for which remote control is provided ([refer to 3.1.5](#)) shall also be fitted with means of local manual control.

**3.6.5.2** The anchor appliances and the associated means of local manual control shall be so designed that normal operation is ensured in case of failure of separate elements or the whole of the remote control system (refer also to 5.1.3 of Part XI "Electrical Equipment").

### **3.7 ANCHOR MACHINERY**

**3.7.1** Anchor machinery shall be fitted on the deck in the fore part of the ship for dropping and hoisting the anchors, as well as for holding the ship with the bower anchors dropped if the mass of the anchor exceeds 35 kg.

Ships of restricted area of navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** shall be fitted with the anchor machinery for dropping and hoisting the stream anchor if its mass exceeds 200 kg.

Ships having Equipment Number 205 and less may be fitted with hand-operated anchor machinery and may also use other deck machinery for dropping and hoisting the anchors.

The requirements for the design and power of anchor machinery are given in 6.3 of Part IX "Machinery".

In fiber-reinforced plastic ships fastening of the anchor machinery shall comply with the requirements of [3.6.1.4](#).

### **3.8 SPARE PARTS**

**3.8.1** Each ship carrying a spare anchor and equipped with a chain cable (cables) for bower anchor (anchors) accordance with the provisions of [3.3.1](#) and [3.4](#) shall have: spare anchor length of chain — 1 pc, spare joining link — 2 pcs, spare end shackle — 1 pc.

**3.8.2** Each ship equipped with a spare anchor and wire rope (ropes) for bower anchor (anchors) in accordance with the provisions of [3.3.1](#) and [3.4.7](#) shall have a spare set of parts for joining the wire rope and anchor shackle.

## 4 MOORING ARRANGEMENT

### 4.1 GENERAL

**4.1.1** Each ship shall be supplied with mooring arrangement for warping to coastal or floating berths and for reliable fastening of the ship to them.

For shipborne barges the mooring arrangement shall comply with the requirements of Section 4 of Part III "Equipment, Arrangements and Outfit" of the Rules for the Classification and Construction of Inland Navigation Ships (for European Inland Waterways).

For shipboard fittings not selected from an industry standard accepted (approved) by the Register, the corrosion addition  $t_c$  and the wear allowance  $t_w$ , given in [4.3.5](#), respectively, shall be considered.

The requirements of this Section for selection of mooring arrangement do not apply to oil tankers of 150 m in length and above as well as bulk carriers of 90 m in length and above, contracted for construction on or after 1 July 2015, but before 1 January 2022. The requirements for mooring lines and mooring arrangements of the said ships are regulated by the IACS Common Structural Rules.

**4.1.2** For all ships other than fishing vessels, the number, length and minimum breaking strength of mooring lines shall be as recommended values given in [Table 3.1.3-1](#), and for fishing values — in [Table 3.1.3-2](#). For fishing vessels, when Equipment Number exceeds 720, the number, length and minimum breaking strength of mooring lines, given as recommended values, shall be selected from [Table 3.1.3-1](#) based on Equipment Number determined in compliance with [3.2](#).

**4.1.3** For ships with  $EN \leq 2000$  and having the ratio  $A/EN > 0,9$ , the following number of lines shall be added to the number of mooring lines as given by [Table 3.1.3-1](#):

one line where  $0,9 < A/EN \leq 1,1$ ;  
two lines where  $1,1 < A/EN \leq 1,2$ ;  
three lines where  $A/EN > 1,2$

where  $EN$  and  $A$  = Equipment Number and side-projected area (windage area), respectively, specified under [3.2](#).

The minimum recommended strength and number of mooring lines for ships with an Equipment Number  $EN > 2000$  are given in [4.1.3.1](#) and [4.1.3.2](#), respectively. The length of mooring lines is specified in [4.1.3.3](#).

The strength of mooring lines and the number of head, stern, and breast lines ([refer to the Note](#)) for ships with an Equipment Number  $EN > 2000$  are based on the side-projected area  $A_1$ . Side-projected area  $A_1$  shall be calculated similar to the side-projected area  $A$  according to [3.2.1](#) but considering the following conditions:

the ballast draught shall be considered for the calculation of the side-projected area  $A_1$ . For ship types having small variation in the draught, like e.g. passenger and ro-ro ships, the side-projected area  $A_1$  may be calculated using the summer load waterline;

wind shielding of the pier can be considered for the calculation of the side-projected area  $A_1$  unless the ship is intended to be regularly moored to jetty type piers. A height of the pier surface of 3 m over waterline may be assumed, i.e. the lower part of the side-projected area with a height of 3 m above the waterline for the considered loading condition may be disregarded for the calculation of the side-projected area  $A_1$ ;

deck cargoes at the ship nominal capacity condition shall be included for the determination of side-projected area  $A_1$ . For the condition with cargo on deck, the summer load waterline may be considered. Deck cargoes may not need to be considered if ballast draught condition generates a larger side-projected area  $A_1$  than the full load condition with cargoes on deck. The larger of both side-projected areas shall be chosen as side-projected area  $A_1$ .

The nominal capacity condition is defined as the theoretical condition where the maximum possible deck cargoes are included in the ship arrangement in their respective positions. For container ships the nominal capacity condition represents the theoretical condition where the maximum possible number of containers is included in the ship arrangement in their respective positions.

The mooring lines as given here under are based on a maximum current speed of 1,0 m/s and the following maximum wind speed  $v_w$ , in m/s:

$v_w = 25,0 - 0,002 (A_1 - 2000)$	—	for passenger ships, ferries, and car carriers with $2000 \text{ m}^2 < A_1 \leq 4000 \text{ m}^2$ ;
$v_w = 21,0$	—	for passenger ships, ferries, and car carriers with $A_1 > 4000 \text{ m}^2$ ;
$v_w = 25,0$	—	for other ships.

The wind speed is considered representative of a 30 second mean speed from any direction and at a height of 10 m above the ground. The current speed is considered representative of the maximum current speed acting on bow or stern ( $\pm 10^\circ$ ) and at a depth of one-half of the mean draught. Furthermore, it is considered that ships are moored to solid piers that provide shielding against cross current.

Additional loads caused by, e.g., higher wind or current speeds, cross currents, additional wave loads, or reduced shielding from non-solid piers may need to be particularly considered. Furthermore, it shall be observed that unbeneficial mooring layouts can considerably increase the loads on single mooring lines.

Note: The following is defined with respect to the purpose of mooring lines, refer also to [Fig. 4.1.3](#):

breast line — a mooring line that is deployed perpendicular to the ship, restraining the ship in the off-berth direction;

spring line — a mooring line that is deployed almost parallel to the ship, restraining the ship in fore or aft direction;

head/stern line — a mooring line that is oriented between longitudinal and transverse direction, restraining the ship in the off-berth and in fore or aft direction. The amount of restraint in fore or aft and off-berth direction depends on the line angle relative to these directions.




Fig. 4.1.3

#### 4.1.3.1 Ship design minimum breaking load.

The ship design minimum breaking load, in kN, of the mooring lines shall be taken as:

$$MBL_{SD} = 0,1 \cdot A_1 + 350. \quad (4.1.3.1-1)$$

The ship design minimum breaking load may be limited to 1275 kN (130 t). However, in this case the moorings shall be considered as not sufficient for environmental conditions specified in [4.1.3](#). For these ships, the acceptable wind speed  $v_w^*$ , in m/s, can be estimated as follows:

$$v_w^* = v_w \cdot \sqrt{\frac{MBL_{SD}^*}{MBL_{SD}}} \quad (4.1.3.1-2)$$

where  $v_w$  = is the wind speed as per [4.1.3](#);  
 $MBL_{SD}^*$  = the ship design minimum breaking load of the mooring lines intended to be supplied; and  
 $MBL_{SD}$  = the ship design minimum breaking load as recommended according to [Formula \(4.1.3.1-1\)](#).

However, the ship design minimum breaking load shall not be taken less than corresponding to an acceptable wind speed of 21 m/s:

$$MBL_{SD}^* v_w^* \geq \left(\frac{21}{v_w}\right)^2 \cdot MBL_{SD}. \quad (4.1.3.1-3)$$

If lines are intended to be supplied for an acceptable wind speed  $v_w^*$  higher than  $v_w^*$  as per [4.1.3](#), the ship design minimum breaking load shall be taken as:

$$MBL_{SD}^* \geq \left(\frac{v_w^*}{v_w}\right)^2 \cdot MBL_{SD}. \quad (4.1.3.1-4)$$

#### 4.1.3.2 Number of mooring lines.

The total number of head, stern and breast lines (refer to the Note in [4.1.3](#)) shall be taken as follows:

$$n = 8,3 \cdot 10^{-4} \cdot A_1 + 6. \quad (4.1.3.2-1)$$

For oil tankers, chemical tankers, bulk carriers, and ore carriers the total number of head, stern and breast lines shall be taken as follows:

$$n = 8,3 \cdot 10^{-4} \cdot A_1 + 4. \quad (4.1.3.2-2)$$

The total number of head, stern and breast lines shall be rounded to the nearest whole number.

The number of head, stern and breast lines may be increased or decreased in conjunction with an adjustment to the ship design minimum breaking load of the lines. The adjusted ship design minimum breaking load  $MBL_{SD}^{**}$  shall be taken as:

$$MBL_{SD}^{**} = 1,2 \cdot MBL_{SD} \cdot n/n^{**} \leq MBL_{SD} \quad \text{for increased number of lines;}$$

$$MBL_{SD}^{**} = MBL_{SD} \cdot n/n^{**} \quad \text{for reduced number of lines}$$

where  $MBL_{SD}$  =  $MBL_{SD}$  or  $MBL_{SD}^*$  specified in [4.1.3.1](#), as appropriate;  
 $n^{**}$  = the increased or decreased total number of head, stern and breast lines;  
 $n$  = the number of lines for the considered ship type as calculated by [Formulae \(4.1.3.2-1\)](#) and [\(4.1.3.2-2\)](#) without rounding.

Vice versa, the ship design minimum breaking load of head, stern and breast lines may be increased or decreased in conjunction with an adjustment to the number of lines.

The total number of spring lines (refer to the Note in [4.1.3.2](#)) shall be taken not less than:

two lines where  $EN < 5000$ ;  
four lines where  $EN \geq 5000$ .

The ship design minimum breaking load of spring lines shall be the same as that of the head, stern and breast lines. If the number of head, stern and breast lines is increased in conjunction with an adjustment to the ship design minimum breaking load of the lines, the number of spring lines shall be taken as follows, but rounded up to the nearest even number:

$$n_S^* = MBL_{SD}/MBL_{SD}^{**} \cdot n_S \quad (4.1.3.2-3)$$

where  $MBL_{SD}$  =  $MBL_{SD}$  or  $MBL_{SD}^*$ , specified in [4.1.3.1](#), as appropriate;  
 $n_S$  = the number of spring lines as given above;  
 $n_S^*$  = the increased number of spring lines.

#### 4.1.3.3 Length of mooring lines.

The length of mooring lines for ships with  $EN \leq 2000$  may be taken from [Table 3.1.3-1](#). For ships with  $EN > 2000$  the length of mooring lines may be taken as 200 m.

The lengths of individual mooring lines may be reduced by up to 7 % of the above given lengths, but the total length of mooring lines shall not be less than would have resulted had all lines been of equal length.

**4.1.4** For individual mooring lines with breaking strength above 490 kN according to [Table 3.1.3-1](#) the latter may be reduced with corresponding increase of the number of mooring lines, provided that the total breaking strength of all mooring lines aboard the ship is not less than the value selected from [Table 3.1.3-1](#) with regard to [4.1.3](#) and [4.1.6](#). The number of lines shall be not less than 6 and none of the lines shall have the breaking strength less than 490 kN.

**4.1.5** The length of individual mooring lines may be reduced by up to 7 % as against the prescribed value provided that the total length of all mooring lines is not less than that specified in [Table 3.1.3-1](#) and [4.1.3](#) or [Table 3.1.3-2](#).

**4.1.6** For polyamide ropes the line design breaking strength shall be increased by 20 % and for other synthetic ropes by 10 % to account for strength loss due to aging and wear.

## **4.2 MOORING LINES**

**4.2.1** Mooring lines may be of steel wire, natural fibre or synthetic fibre construction or of a mixture of wire and fibre.

Notwithstanding the breaking strength recommendations given in [Tables 3.1.3-1](#) or [3.1.3-2](#), no fibre rope shall be less than 20 mm in diameter.

For synthetic fibre ropes it is recommended to use lines with reduced risk of recoil (snap-back) to mitigate the risk of injuries or fatalities in the case of breaking mooring lines.

**4.2.2** Steel wire ropes shall have at least 144 wires and not less than 7 fibre cores. The exception is made for wire ropes for automatic mooring winches which may have only one fibre core but the number of wires in such ropes shall be not less than 216. The wires of the ropes shall have a zinc coating according to recognized standards.

In all other respects, the steel wire ropes shall meet the requirements of 3.15 of Part XIII "Materials".

**4.2.3** Natural fibre ropes shall be either manilla or sizal. The ships having Equipment Number 205 and less are permitted to use hemp ropes.

In all other respects, the natural fibre ropes shall meet the requirements of 6.6 of Part XIII "Materials".

**4.2.4** The synthetic fibre ropes shall be manufactured from approved homogeneous materials (polypropylene, capron, nylon, etc.).

In all other respects, the ropes of synthetic fibre material shall meet the requirements of 6.6 of Part XIII "Materials".



## 4.3 MOORING EQUIPMENT

**4.3.1** The number and position of mooring bollards, fairleaders and other mooring equipment depend on the constructional features, purpose and general arrangement of the ship.

Shipboard fittings may be selected from an industry standard accepted (approved) by the Register in accordance with ship design minimum breaking load selected from [Table 3.1.3-1](#).

When the shipboard fitting is not selected from an accepted (approved) industry standard, the strength of the fitting and of its attachment to the ship shall be in accordance with [4.3.4](#) and [4.3.5](#).

Mooring bitts (double bollards) are required to resist the loads caused by the mooring line attached in figure-of-eight fashion ([refer to Note](#)). For strength assessment beam theory or finite element analysis using net scantlings (without corrosion additions and wear down allowances specified in [4.3.5](#)) shall be applied, as appropriate. Load tests may be accepted as alternative to strength assessment by calculations.

Note. With the line attached to a mooring bitt in the usual way (figure-of-eight fashion), either of the two posts of the mooring bitt can be subjected to a force twice as large as that acting on the mooring line. Disregarding this effect, depending on the applied industry standard and fitting size, overload may occur.

**4.3.2** Bollards may be of steel or cast iron. Small ships equipped only with natural fibre or synthetic fibre ropes are permitted to use the bollards made of light alloys. As to the method of manufacture, the bollards may be welded or cast.

It is not permitted to use bollards cut directly in the deck which is the top of cargo tanks intended for carriage or stowage of flammable liquids with the flash point 60 °C and below.

**4.3.3** The outside diameter of the bollard column shall be not less than 10 diameters of the steel wire rope, not less than 5,5 diameters of the synthetic fibre rope, and not less than one circumference of the natural fibre rope for which the bollard is designed. The distance between the axes of bollard columns shall not be less than 25 diameters of the steel wire rope or 3 circumferences of the natural fibre rope.

**4.3.4** Shipboard fittings, winches and capstans for mooring shall be located on stiffeners and/or girders, which are part of the deck construction so as to facilitate efficient distribution of the mooring load.

**4.3.4.1** The minimum design load applied to supporting hull structures for shipboard fittings shall be 1,15 times the minimum breaking strength of the mooring line according to [Table 3.1.3-1](#).

**4.3.4.2** The minimum design load applied to supporting hull structures for winches shall be 1,25 times the intended maximum brake holding load, where the maximum brake holding load shall be assumed not less than 80 % of the minimum breaking strength of the mooring line according to [Table 3.1.3-1](#); for supporting hull structures of capstans, 1,25 times the maximum hauling-in force shall be taken as the minimum design load.

**4.3.4.3** When a safe working load (SWL) greater than that determined according to [4.3.6](#) is specified by the designer/shipowner, then the design load shall be increased accordingly.

**4.3.4.4** The design load shall be applied to fittings in all directions that may occur by taking into account the arrangement shown on the towing and mooring arrangements plan.

However, in no case does the design load applied to the fitting need to be greater than twice the design load on the line.

Notes: 1. Side-projected area including that of deck cargoes shall be taken into account for selection of mooring lines and the loads applied to shipboard fittings and supporting hull structure. The nominal capacity condition is defined as the theoretical condition where the maximum possible deck cargoes are included in the ship arrangement in their respective positions. For container ships the nominal capacity condition represents the theoretical condition where the maximum possible number of containers is included in the ship arrangement in their respective positions.

2. The increase of the minimum breaking strength for synthetic ropes according to IACS recommendation No. 10 (Rev.4 Sep 2020) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)) needs not to be taken into account for the loads applied to shipboard fittings and supporting hull structure.

The arrangement of reinforced members beneath shipboard fittings, winches and capstans shall consider any variation of direction (horizontally and vertically) of the mooring forces acting upon the shipboard fittings, refer to [Fig. 5.3.6](#). Proper alignment of fitting and supporting hull structure shall be ensured.

The acting point of the mooring force on shipboard fittings shall be taken at the attachment point of a mooring line or at a change in its direction. For bollards and bitts the attachment point of the mooring line shall be taken not less than  $4/5$  of the tube height above the base, refer to [Fig. 4.3.4.4, a](#). However, if fins are fitted to the bollard tubes to keep the mooring line as low as possible, the attachment point of the mooring line may be taken at the location of the fins, refer to [Fig. 4.3.4.4, b](#).




Fig. 4.3.4.4

**4.3.5** The total corrosion addition  $t_c$ , shall not be less than the following values:  
for ships covered by the IACS Common Structural Rules: total corrosion addition, shall be as defined in the rules mentioned above;

other ships:

for the supporting hull structure, according to Part II "Hull" of these Rules for the surrounding structure (e.g. deck structures, bulwark structures);

for pedestals and foundations on deck which are not part of a fitting, according to an accepted (approved) industry standard, 2,0 mm;

for shipboard fittings not selected from an accepted (approved) industry standard, 2,0 mm.

Wear allowance:

in addition to the corrosion addition the wear allowance  $t_w$ , for shipboard fittings not selected from an accepted (approved) industry standard shall not be less than 1,0 mm, added to surfaces which are intended to regularly contact the line.

**4.3.6** Safe working load (SWL) of shipboard fittings used for mooring purpose shall not exceed the ship design minimum breaking load determined according to [4.3.4](#). The SWL, in t, of each shipboard fitting shall be marked (by weld bead or equivalent) on the deck fittings used for mooring.

#### **4.4 MOORING MACHINERY**

**4.4.1** Special mooring machinery (mooring capstans, mooring winches, etc.) as well as other deck machinery (windlasses, cargo winches, etc.) fitted with mooring drums may be used for warping the hawsers.

**4.4.2** The choice of the number and type of mooring machinery is within the owner's and designer's discretion, however, the rated pull of the machinery shall not exceed 1/3 of the breaking strength of the mooring ropes used in the ship and, besides, the requirements of 6.4 of Part IX "Machinery" shall be satisfied.

## 4.5 TOWING AND MOORING ARRANGEMENTS PLAN

**4.5.1** The *SWL* (Safe Working Load) and *TOW* (Safe Towing Load) for the intended use for each shipboard fitting shall be noted in the towing and mooring arrangements plan available on board for the guidance of the master.

*TOW* is the load limit for towing purpose and *SWL* that for mooring purpose. If not otherwise chosen, for towing bitts it should be noted that *TOW* is the load limit for a towing line attached with eye-splice.

**4.5.2** Information provided on the plan shall include in respect of each shipboard fitting intended for mooring and towing purposes:

- location on the ship;

- fitting type;

- SWL/TOW*;

- purpose (mooring/harbour towing/other towing);

- manner of applying towing or mooring line load including limiting fleet angles i.e. angle of change in direction of a line at the fitting.

Furthermore, information provided on the plan shall include:

- the arrangement of mooring lines showing number of lines (*N*);

- the ship design minimum breaking load (*MBL<sub>SD</sub>*);

- the acceptable environmental conditions as given in IACS recommendation No. 10 (Rev.4 Sep 2020) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)), for the recommended ship design minimum breaking load for ships with Equipment Number *EN* > 2000:

- 30 s mean wind speed from any direction ( $v_W$  or  $v_W^*$  according to IACS recommendation No. 10 (Rev.4 Sep 2020) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)));

- maximum current speed acting on bow or stern ( $\pm 10^\circ$ ).

**4.5.3** The information as given in [4.5.2](#) shall be incorporated into the pilot card in order to provide the pilot proper information on harbour and other towing operations.

## 5 TOWING ARRANGEMENT

### 5.1 GENERAL

**5.1.1** Ships, other than fishing vessels and those referred to in [5.1.2](#), of 500 gross tonnage and upwards intended to be towed by other ships or tugs shall meet the requirements of [5.2](#) and [5.3](#).

Ships having the descriptive notation **Tug** in the class notation shall meet the requirements of [5.4 — 5.6](#).

**5.1.2** Oil tankers, oil tankers (> 60 °C), combination carriers, gas carriers and chemical tankers of 20000 t deadweight and over shall comply with the requirements of [5.7](#).

**5.1.3** The towing arrangements of berth-connected ships shall comply with the requirements of 5.3 of Part III "Equipment, Arrangements and Outfit" of the Rules for the Classification and Construction of Inland Navigation Ships (for European Inland Waterways).

**5.1.4** The requirements of this Section for selection of towing arrangement do not apply to oil tankers of 150 m in length and above as well as bulk carriers of 90 m in length and above, contracted for construction on or after 1 July 2015, but before 1 January 2022. The requirements for tow lines and towing arrangements of the said ships are regulated by the IACS Common Structural Rules.

**5.1.5** Ships shall be provided with a ship-specific emergency towing procedure. Such a procedure shall be carried aboard the ship for use in emergency situations and shall be based on existing arrangements and equipment available on board the ship.

The procedure shall include:

drawings of fore and aft deck showing possible emergency towing arrangements;

inventory of equipment on board that can be used for emergency towing;

means and methods of communication;

sample procedures to facilitate the preparation for and conducting of emergency towing operations.

## 5.2 TOW LINE

**5.2.1** The need for the ship to be provided with the tow line for emergency towing in accordance with [Table 3.1.3-1](#) is determined by the shipowner.

The length and the minimum breaking strength of the tow line shall be as recommended values given in [Table 3.1.3-1](#) based on an Equipment Number calculated in compliance with [3.2](#).

For shipborne barges the actual breaking strength of the tow line  $F_b$ , in kN, shall be calculated by the formula

$$F_b = 16nBd \quad (5.2.1)$$

where  $n$  = number of barges intended to be towed in the wake of the tug in tandem;  
 $B$  = breadth of the barge, in m;  
 $d$  = draught of the barge, in m.

The breaking strength of the tow line is used in the strength calculations of the towing appliances of the shipborne barges. At the discretion of the shipowner the tow lines of the shipborne barges may be stored in the barge carrier or tug, and they do not form a part of the equipment of the shipborne barge.

**5.2.2** The tow lines may be of steel wire, natural fibre or synthetic fibre material. The requirements of [4.1.6](#), [4.2.1 — 4.2.4](#) for mooring ropes are also applicable to the tow line.

### 5.3 TOWING EQUIPMENT

**5.3.1** The number and location of towing bollards and chocks depend on the constructional features, purpose and general arrangement of the ship.

Ships having the descriptive notation **Tug** added to the character of classification, and equipped with a bow towing winch with a tow line may have no towing bitts provided the technical characteristics of this winch, its foundation and tow line comply with the requirements of [5.3.3 — 5.3.6](#)

**5.3.2** Requirements of [4.3.2](#) and [4.3.3](#) introduced for the mooring bollards also apply to towing bollards.

**5.3.3** Shipboard fittings for towing shall be located on longitudinals, which are part of the deck construction so as to facilitate efficient distribution of the towing load.

**5.3.4** The minimum design load applied to supporting hull structures for shipboard fittings shall be:

- .1 for normal towing operations — 1,25 times the intended maximum towing load (e.g. static bollard pull) as indicated on the towing and mooring arrangements plan;
- .2 for other towing service — the ship design minimum breaking load according to [Table 3.1.3-1](#) based on the ship's Equipment Number;
- .3 for fittings intended to be used for, both, normal and other towing operations, the greater of the design loads according to [5.3.4.1](#) and [5.3.4.2](#).

**5.3.5** The design load applied to supporting hull structure shall be in accordance with [5.3.4](#).

The reinforced members beneath shipboard fittings shall be effectively arranged for any variation of direction (horizontally and vertically) of the towing forces acting upon the shipboard fittings, [refer to Fig. 5.3.5-1](#). Proper alignment of fitting and supporting hull structure shall be ensured.

The acting point of the towing force on shipboard fittings shall be taken at the attachment point of a towing line or at a change in its direction. For bollards and bitts the attachment point of the towing line shall be taken not less than 4/5 of the tube height above the base, [refer to Fig. 5.3.5-2](#).

For strength assessment using beam theory or grillage analysis, as well as finite element analysis, the stresses in supporting hull structures shall be determined in the same manner as specified in [4.3.5](#).




Fig. 5.3.5-1






Fig. 5.3.5-2

**5.3.6** When a safe towing load (*TOW*) greater than that determined according to 5.3.8 is specified by the designer/shipowner, then the design load shall be increased in accordance with the appropriate *TOW*/design load relationship given by 5.3.4 and 5.3.8.

The design load shall be applied to fittings in all directions that may occur by taking into account the arrangement shown on the towing and mooring arrangements plan. Where the towing line takes a turn at a fitting the total design load applied to the fitting is equal to the resultant of the design loads acting on the line, refer to Fig. 5.3.6. However, in no case does the design load applied to the fitting need to be greater than twice the design load on the line.




Fig. 5.3.6

### 5.3.7 Shipboard fittings.

Shipboard fittings may be selected from an accepted (approved) industry standard by the Register and at least based on the following loads:

- .1 for normal towing operations, the intended maximum towing load (e.g. static bollard pull) as indicated on the towing and mooring arrangements plan;
- .2 for other towing service, the ship design minimum breaking load of the tow line according to IACS recommendation No. 10 (Rev.4 Sep 2020) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)) (refer to Notes in 4.3.4.4);
- .3 for fittings intended to be used for, both, normal and other towing operations, the greater of the loads according to 5.3.7.1 and 5.3.7.2.

When the shipboard fitting is not selected from an accepted (approved) industry standard, the strength of the fitting and of its attachment to the ship shall be in accordance with 5.3.4 and 5.3.5.

Towing bitts (double bollards) are required to resist the loads caused by the towing line attached with eye splice. For strength assessment, beam theory or finite element analysis using net scantlings (without corrosion additions and wear down allowances specified in [4.3.5](#)) shall be applied, as appropriate. Load tests may be accepted as alternative to strength assessment by calculations.

**5.3.8 Safe Towing Load (*TOW*).**

**5.3.8.1** *TOW* is the safe load limit of shipboard fittings used for towing purpose.

**5.3.8.2** *TOW* used for normal towing operations shall not exceed 80 % of the design load per [5.3.4.1](#).

**5.3.8.3** *TOW* used for other towing operations shall not exceed 80 % of the design load according to [5.3.4.2](#).

**5.3.8.4** For fittings used for both normal and other towing operations, the greater of the safe towing loads according to [5.3.8.2](#) and [5.3.8.3](#) shall be used.

**5.3.8.5** Fittings intended to be used for, both, towing and mooring, shall comply with the requirements of [Section 4](#).

**5.3.8.6** *TOW*, in t, of each shipboard fitting shall be marked (by weld bead or equivalent) on the deck fittings used for towing. For fittings intended to be used for, both, towing and mooring *SWL*, in t, shall be marked in addition to *TOW*.

**5.3.8.7** The above requirements on *TOW* apply for the use with no more than one line. If not otherwise chosen, for towing bitts (double bollards) *TOW* is the load limit for a towing line attached with eye-splice.

## 5.4 SPECIAL ARRANGEMENT FOR TUGS

**5.4.1** The number and type of equipment and outfit forming special arrangement for tugs which ensures towing operations under different service conditions are determined by the shipowner considering that such equipment and outfit shall satisfy the requirements of this Chapter.

**5.4.2** The main determining factor in providing the tugs with a special arrangement is a bollard pull (*BP*).

**5.4.2.1** The numerical value of the rated towing pull is within the shipowner's and designer's discretion, and all calculations pertaining to the determination of this value are not subject to agreement with the Register. Nevertheless, during mooring and sea trials of the tug, the Register will check this value, and, if the parts of the special arrangement prove to be calculated from a smaller value, the Register may require the strengthening of these parts or may introduce restriction of power during towing operations.

**5.4.2.2** Minimum breaking strength (*MBL*) of the tow line shall be in accordance with [Table 5.4.2.2](#):

Table 5.4.2.2

<i>BP</i> , in t	< 40	40 – 90	> 90
<i>MBL</i> , in t	$3,0 \times BP$	$(3,8 - BP/50)BP$	$2,0 \times BP$

The tow line for towing operations on the hook may be of steel wire, natural fibre or synthetic fibre material. The requirements of [4.2](#) for mooring lines are also applicable to the tow line for towing operations on the hook.

**5.4.3** All stressed parts of the towing arrangement (such as the tow hook, towing rails, etc.) as well as the fastenings for securing these parts to the ship's hull shall be designed to take the breaking load of the tow line. The stresses in these parts shall not exceed 0,95 times the upper yield stress of their material.

**5.4.4** The cramp iron of the tow hook shall be calculated as a curvilinear bar. Where such calculations are not carried out, i.e. the formulae for a rectilinear bars are used, permissible stresses shall be reduced by 35 %.

**5.4.5** All parts of the towing arrangement which are subjected to tension or bending under the hull of the tow line shall not be manufactured of cast iron.

**5.4.6** The cramp iron of the tow hook shall be either solid forged or manufactured of a solid rolled blank. Percentage elongation of the cramp iron material shall not be less than 18 % on a fivefold sample.

**5.4.7** Tow hooks shall be of slip-type and have a tow line releasing device operating efficiently in the range of loads on the tow hook from zero to three times the rated towing pull and at any practically possible deflection of the tow line from the centreline of the ship.

The device shall be controlled both at the tow hook and from the navigation bridge. Where the ship is fitted with a spshallw hook, in addition to the main one, this hook need not be of slip-type and have a device for releasing the tow line.

**5.4.8** When applying tow hooks with shock absorbers, their ultimate damping load shall not be less than 1,3 times the rated towing pull.

**5.4.9** Prior to installation on board the ship the tow hooks shall be tested by application of a proof load equal to twice the rated towing pull.

**5.4.10** The wire stopper and its fastenings shall be such that their breaking load is not less than 1,5 times the rated towing pull.

**5.4.11** The requirements of 3.7 of Part IV "Stability" shall be taken into consideration when assigning the position of the tow hook and towing winch.

## **5.5 TOWING WINCHES**

**5.5.1** The requirements for the design of towing winches are specified in 6.5 and 6.6 of Part IX "Machinery".

**5.5.2** Provision shall be made for operating the towing winch from a site at the winch; it is recommended to allow for operating the towing winch from the navigation bridge.

When placing the control station on the navigation bridge at the towing winch and having possibility of supervision for its operation, it is allowed not to provide for operating the towing winch directly from the place of its installation.

## **5.6 TOW LINE FOR TOWING WINCH**

**5.6.1** The tow line for towing winch shall be selected by the shipowner depending on the structural particulars and purpose of the ship. The recommended requirements for tow line for towing winch are given in [5.4.2.2](#).

## 5.7 EMERGENCY TOWING ARRANGEMENTS ON SHIPS

**5.7.1** Ships referred to in [5.1.2](#) shall be fitted with emergency towing arrangements forward and aft of the ship. The arrangements shall be capable of rapid deployment in the absence of main power on the ship to be towed and easy connection to the towing ship. At least one of the emergency towing arrangements shall be pre-rigged ready for rapid deployment.

**5.7.2** The components of the emergency towing arrangement are listed in [Table 5.7.2](#).

Table 5.7.2

Components of emergency towing arrangement	Non pre-rigged	Pre-rigged
Pick-up gear	Optional	Yes
Towing pennant	Optional	Yes
Chafing gear	Yes	Depending on design
Fairlead	Yes	Yes
Strongpoint	Yes	Yes
Roller pedestal	Yes	Depending on design

**5.7.3** Except the pick-up gear and roller pedestal, the components of the emergency towing arrangement specified in [Table 5.7.2](#) shall have a working strength of at least:

1000 kN for ships of 20000 t deadweight and over, but less than 50000 t deadweight,  
2000 kN for ships of 50000 t deadweight and over.

Under the above forces, the stresses shall not exceed 0,5 of the ultimate strength.

The strength shall be sufficient for all relevant angles of towline, i.e. up to 90° from the ship's centreline to port and starboard and 30° vertically downwards.

**5.7.4** The towing pennant shall have a length of at least twice the lightest seagoing ballast freeboard at the fairlead plus 50 m. The towing pennant shall have a hard eye-formed termination allowing connection to a standard shackle.

The bow and stern strongpoints and fairleads shall be located so as to facilitate towing from either side of the bow or stern and minimize the stress on the towing system.

The inboard end fastening shall be a stopper or bracket or other fitting of equivalent strength. The strongpoint can be designed integral with the fairlead.

**5.7.5** Fairleads shall have an opening large enough to pass the largest portion of the chafing gear, towing pennant or towing line.

The fairlead shall give adequate support for the towing pennant during towing operation which means bending 90° to port and to starboard side and 30° vertically downwards. The bending ratio (towing pennant bearing surface diameter to towing pennant diameter) shall be not less than 7:1.

The fairlead shall be located as close as possible to the deck and, in any case, in such a position that the chafing chain is approximately parallel to the deck when it is under strain between the strongpoint and the fairlead.

**5.7.6** The chafing gear shall be fitted at the forward and, depending on design, aft ends of the ship. A chafing chain or another design approved by the Register may be used as the chafing gear. The chafing chain shall be a stud link chain.

The chafing chain shall be long enough to ensure that the towing pennant remains outside the fairlead during the towing operation. A chain extending from the strongpoint to a point at least 3 m beyond the fairlead shall meet this criterion.

**5.7.7** One end of the chafing chain shall be suitable for connection to the strongpoint. The other end shall be fitted with a standard pear-shaped open link allowing connection to a standard bow shackle.

The chafing chain shall be stowed in such a way that it can be rapidly connected to the strongpoint.

**5.7.8** The emergency towing arrangement shall be pre-rigged and be capable of being deployed in a controlled manner in harbour conditions in not more than 15 min.

The pre-rigged pick-up gear shall be designed for manual operation by one person taking into account the absence of power and the potential for adverse environmental conditions that may prevail during such emergency towing operations. The pick-up gear shall be protected against the weather and other adverse conditions that may prevail.

**5.7.9** The non pre-rigged emergency towing arrangement shall be capable of being deployed in harbour conditions in not more than 1 h. To facilitate connection of the towing pennant to the chafing gear and to prevent chafing of the pennant, a suitably positioned pedestal roller may be used.

Pre-rigged emergency towing arrangements at both ends of the ship may be accepted.

A type emergency towing arrangement is shown in [Fig. 5.7.9](#).




Fig. 5.7.9

**5.7.10** All emergency towing arrangements shall be clearly marked to facilitate safe and effective use even in darkness and poor visibility.

## **6 SIGNAL MASTS**

### **6.1 GENERAL**

**6.1.1** The requirements given in the present Section refer only to the signal masts, i.e. the masts which are intended for carrying the signal means: navigation lights, day signals, aerals, etc. Where the masts or their parts carry derrick booms or other cargo handling gear in addition to the signal means, such masts or their parts shall comply with the requirements of the Rules for the Cargo Handling Gear of Sea-Going Ships.

The requirements of [6.2 — 6.4](#) do not apply to berth-connected ships. The signal masts of berth-connected ships shall be designed to carry prescribed signal means.

**6.1.2** Arrangement, height and provision of signal means on the signal masts shall comply with the requirements of Part III "Signal Means" of the Rules for the Equipment of Sea-Going Ships.

**6.1.3** If in ships of restricted areas of navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** the signal masts are collapsible, special machinery shall be installed for their operation or provision shall be made for appropriate connection with other deck machinery. The drive of the machinery may be hand-operated provided the machinery is self-braking and the load on the handle is not more than 160 N at any moment of jackknifing or hoisting the mast.



## 6.2 STAYED MASTS

**6.2.1** The outside diameter  $d$  and the plate thickness  $t$ , in mm, at the heel of the masts made of steel having the upper yield stress from 215 up to 255 MPa and stayed by two shrouds on each side of the ship, shall not be less than:

$$d = 22l; \quad (6.2.1-1)$$

$$t = 0,2l + 3 \quad (6.2.1-2)$$

where  $l$  = mast length, in m, from the heel to the shroud eyeplates.

The diameter of the mast may be gradually decreased upwards to a value of  $0,75d$  at the shroud eyeplates, while the thickness of the mast plates is maintained constant throughout the length  $l$ .

The mast length from the shroud eyeplates to the top shall not exceed  $1/3$  of  $l$ .

The mast shall be stayed by the shrouds as follows:

**.1** horizontal distance  $a$ , in m, from the deck (or bulwark) stay eyeplate to the transverse plane through the mast stay eyeplate shall not be less than

$$a = 0,15h \quad (6.2.1.1)$$

where  $h$  = vertical distance, in m, from the mast stay eyeplate to the deck (or bulwark) stay eyeplate;

**.2** horizontal distance  $b$ , in m, from the deck (or bulwark) stay eyeplate to the longitudinal plane through the mast stay eyeplate shall not be less than

$$b = 0,30h; \quad (6.2.1.2)$$

**.3** the value  $a$  shall not exceed the value  $b$ .

**6.2.2** Breaking strength  $F$  of the ropes, in kN, used for the mast shrouds as specified in 6.2.1 shall not be less than

$$F = 0,49(l^2 + 10l + 25). \quad (6.2.2)$$

In other respects, the ropes for shroud shall comply with the requirements of 3.15 of Part XIII "Materials".

The loose gear of shrouds (shackles, turnbuckles, etc.) shall be such that their safe working load is not less than 0,25 times the breaking strength of the ropes referred to above.

**6.2.3** Where:

the mast is made of high tensile steel, light alloys, fiber-reinforced plastics or wood (the wood shall be of the 1st grade);

the mast is stayed in a way other than that specified in [6.2.1](#);

in addition to a yard arm, lights and day signals, the mast is fitted with other equipment having considerable weight, such as radar reflectors with platforms for their servicing, "crow's nests", etc., proceed as specified in [6.4](#).

**6.2.4** The wires of shrouds shall have a zinc coating according to recognized standards.

### 6.3 UNSTAYED MASTS

**6.3.1** The outside diameter  $d$  and the plate thickness  $t$ , in mm, at the heel of masts made of steel having the upper yield stress from 215 to 255 MPa shall not be less than:

$$d = 3l^2(0,674l + a + 13) \times \left( 1 + \sqrt{1 + \frac{51,5 \cdot 10^4}{l^2(0,674l + a + 13)^2}} \right) \cdot 10^{-2}; \quad (6.3.1-1)$$

$$t = \frac{1}{70} d \quad (6.3.1-2)$$

where  $l$  = length of the mast from heel to top, in m;  
 $a$  = elevation of the mast heel above centre of gravity of the ship, in m.

The outside diameter of the mast may be gradually decreased upwards to a value  $0,5d$  at the distance  $0,75l$  from the heel.

In no case the thickness of the mast plate shall be less than 4 mm.

The mast heel shall be rigidly fixed in all directions.

**6.3.2** Where:

the mast is made of high tensile steel, light alloys, fiber-reinforced plastics or wood (the wood shall be of the 1st grade);

in addition to a yard arm, lights and day signals, the mast is fitted with other equipment having considerable weight, such as radar reflectors with platforms for their servicing, "crow's nests", etc. proceed as provided in [6.4](#).

## 6.4 MASTS OF SPECIAL CONSTRUCTION

**6.4.1** In the cases specified in [6.2.3](#) and [6.3.2](#) as well as where bipod, tripod and other similar masts are installed, detailed strength calculations of these masts shall be carried out. These calculations shall be submitted to the Register for review.

**6.4.2** The calculations shall be performed on the assumption that each part of the mast is affected by a horizontal force  $F_i$ , in kN,

$$F_i = \left[ m_i \frac{4\pi^2}{T^2} (\theta z_i + r \sin \theta) + m_i g \sin \theta + p A_i \cos \theta \right] \cdot 10^{-3} \quad (6.4.2)$$

where  $m_i$  = mass of each part, in kg;  
 $z_i$  = elevation of the centre of gravity of each part above that of the ship, in m;  
 $A_i$  = side-projected area of each part, in m<sup>2</sup>;  
 $T$  = rolling or pitching period, in s;  
 $\theta$  = amplitude of roll or pitch, in rad.;  
 $r$  = wave half-height, in m;  
 $g$  = 9,81 m/s<sup>2</sup> — acceleration due to gravity;  
 $p$  = 1960 Pa — specific wind pressure.

The calculations shall be carried out both for rolling and pitching of the ship,  $r$  being taken as equal to  $L/40$  where  $L$  is the ship's length, in m, and  $\theta$ , in rad., as corresponding to an angle of 40° at roll and of 5° at pitch.

**6.4.3** Under the loads specified in [6.4.2](#) of this Part, the stresses in the parts of the mast shall not exceed 0,7 times the upper yield stress of their material where they are made of metal, and 12 MPa where they are made of wood. The safety factor of the standing ropes under the same loads shall not be less than 3.

For fiber-reinforced plastic masts under the loads specified in [6.4.2](#) of this Part the stresses in the parts of the mast shall not exceed the allowable stress value indicated in Table 3 of Appendix 3 to Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships" for the case of short-time action of the load for the relevant type of deformation.

## 7 OPENINGS IN HULL, SUPERSTRUCTURES AND DECKHOUSES AND THEIR CLOSING APPLIANCES

### 7.1 GENERAL

**7.1.1** The requirements of this Section apply to ships of unrestricted service as well as to ships of restricted areas of navigation **R1**, **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** engaged on international voyages. The requirements for ships of restricted areas of navigation **R1**, **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** not engaged on international voyages, as well as for ships of restricted area of navigation **R3** may be relaxed; the extent of relaxation shall be confirmed by technical background.

**7.1.2** The requirements of this Section apply to ships to which a minimum freeboard is assigned. Deviation from these requirements may be permitted for the ships to which a greater than minimum freeboard is assigned on condition that the Register is satisfied with safety conditions provided.

**7.1.3** The arrangement of openings and their closing appliances in the hull, superstructures and deckhouses shall also comply with the requirements of Part VI "Fire Protection" and Part XI "Electrical Equipment".

**7.1.4** As far as deck openings are concerned, the following two positions are distinguished in this Section.

#### **7.1.4.1** Position 1.

Upon exposed freeboard and raised quarter decks, and upon exposed superstructure decks situated forward of a point located a quarter of the ship's length from the forward perpendicular.

#### **7.1.4.2** Position 2.

Upon exposed superstructure decks situated abaft a quarter of the ship's length from the forward perpendicular and located at least at one standard height of superstructure above the freeboard deck.

Upon exposed superstructure decks situated forward of a point located a quarter of the ship's length from the forward perpendicular and located at least two standard heights of superstructure above the freeboard deck.

**7.1.5** The height of coamings specified in this Section is measured from the upper surface of the steel deck plating or from the upper surface of the wood or other sheathing, if fitted.

**7.1.6** In supply vessels the access to the spaces situated below the open cargo deck shall preferably be provided from the location inside the enclosed superstructure or deckhouse or from the location above the superstructure deck or deckhouse top. The arrangement of companion or other hatches on the open cargo deck leading to the spaces below this deck may be allowed when adequate degree of protection of these hatches from possible damage during cargo handling operations is provided.

**7.1.7** The requirements of the present Section for floating docks apply to openings and their closing appliances arranged above the margin line at docking.

**7.1.8** In docklift ships, regardless of the provisions of [7.4 — 7.7](#), it is not permitted to arrange openings for doors, companion hatches, skylights, ventilating trunks and other hatches in sides and boundary bulkheads of holds if their lower edges are below the margin line at docking, with the exception of the openings to the watertight spaces of a restricted volume not communicating with other spaces below the level of the margin line at docking.

**7.1.9** Doors and hatchways in sides and boundary bulkheads of holds in docklift ships, if their sills are above the margin line at docking by less than 600 mm or 0,05 times the distance between the openings and the centreline whichever is the greater, shall be provided with the light signalling system comprising the indicators installed in the control post of the ship's docking operations. The light indicators shall clearly show the position of the door or hatch cover (secured or open).

**7.1.10** The light signals specified in [7.1.9](#) need not be provided for doors and hatchways to the watertight spaces of a restricted volume not communicating with other spaces below the level which is by 600 mm or 0,05 times the distance between the opening and the centreline, whichever is the greater, above the margin line at docking.

**7.1.11** In cargo ships covered by the requirements of Part V "Subdivision", the openings for access, piping, ventilation, electric cables, etc. in watertight internal bulkheads and decks shall be provided with watertight doors or hatch covers normally closed when at sea which, in their turn, shall be provided with indication means, positioned in their close proximity and on the bridge, to indicate whether such doors or hatch covers are open or closed. On each side of such a door or hatch cover there shall be an inscription to the effect the closure shall not be left open.

**7.1.12** In ships mentioned under [7.1.11](#), all external openings which do not, by their location, conform to the requirements of 3.4.4 of Part V "Subdivision" shall be fitted with strong enough watertight closures for which, except cargo hatch covers, provision shall be made for bridge indication.

The watertight closures of shell openings located below the bulkhead deck shall be permanently closed at sea shall be fitted with devices preventing their uncontrolled opening. Plates shall be attached to such closures with inscriptions to the effect the openings shall be permanently closed at sea.

**7.1.13** In dry cargo ships not covered by the requirements of [7.1.11](#) and [7.1.12](#) all the doors of sliding or hinged type in watertight bulkheads shall be fitted up with indication means positioned on the bridge to indicate whether such doors are open or closed. Similar indicators shall be provided for shell doors and other closing appliances which, if left open or not properly secured, can lead to solid flooding of the ship.

**7.1.14** The requirements of [Section 7](#) do not apply to berth-connected ships. For these ships, the following provisions apply:

- the coaming height of openings of companion hatches, skylights, ventilation trunks and ventilation heads shall not be less than 100 mm;

- weathertight hatch covers shall be provided;

- the external doors of superstructures shall be watertight, but where the lower edge of an external door is not less than 600 mm away from the waterline corresponding to the maximum draught, such doors may be weathertight;

- the lower edge of a side light shall not be less than 150 mm away from the waterline corresponding to the maximum draught;

- on the freeboard deck, the superstructure and deckhouse windows shall be watertight.

## 7.2 SIDE SCUTTLES

### 7.2.1 Position of side scuttles.

**7.2.1.1** The number of side scuttles in the shell plating below the freeboard deck shall be reduced to a minimum compatible with the design and proper working of the ship.

Fishing vessels mooring alongside each other or other ships at sea shall not have side scuttles under freeboard deck in the mooring zone, wherever possible. If in this zone side scuttles are fitted in the shell plating, they shall be so positioned that the possibility of their damage during mooring operations is excluded.

No side scuttles are permitted within the boundaries of the ice belt of the shell plating specified in Part II "Hull" in icebreakers and ice class ships.

It is permitted to reduce the thickness of side scuttle glasses provided that their strength characteristics are confirmed by comparative tests with hardened glass according to the relevant national or international standards.

**7.2.1.2** No side scuttle shall be fitted in a position so that its sill is below a line drawn parallel to the freeboard deck at side and having its lowest point located 0,025 of the ship's breadth  $B$  or 500 mm, whichever is the greater, above the summer load waterline or above the summer timber load waterline where timber load lines are assigned to the ship.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)**, **R3-RSN** and **R3** not engaged on international voyages the specified distance 500 mm may be disregarded.

If the length of the ship is less than 24 m, the specified distance may be reduced to 300 mm for ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** and to 150 mm for ships of restricted area of navigation **R3**.

**7.2.1.3** Side scuttles in the shell plating, below the bulkhead deck of passenger ships and the freeboard deck of cargo ships in front bulkheads of enclosed superstructures and deckhouses of the first tier and also in front bulkheads of enclosed superstructures and deckhouses of the second tier within 0,25 $L$  from the forward perpendicular shall be of a heavy type and fitted with efficient deadlights hinged inside (refer also to 2.4.5 of Part VI "Fire Protection").

In tugs of restricted areas of navigation **R2** and **R3** the side scuttles fitted below the bulkhead deck shall be not only of heavy but also of non-opening type.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** having the length below 24 m and in ships of restricted area of navigation **R3** it is allowed to fit side scuttles of normal type instead of those of heavy type.

**7.2.1.4** In ships to which the requirements of Part V "Subdivision" apply the side scuttles outside a floodable compartment or a specified group of compartments, fitted in a position so that their sills are by less than 0,3 m or  $(0,1 + \frac{L-10}{150})$  m, whichever is less, above the corresponding damage waterline and the side scuttles in the floating cranes the sills of which are by less than 0,3 m above the waterline corresponding to the actual maximum statical heel in case the hook is under load, shall be not only of heavy but also of non-opening type.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** having the length below 24 m and in ships of restricted area of navigation **R3** it is allowed to fit side scuttles of normal non-opening type instead of those of heavy non-opening type.

**7.2.1.5** Side scuttles in enclosed superstructures and deckhouses of the first tier, except those in their front bulkheads, and also side scuttles in enclosed superstructures and deckhouses of the second tier within 0,25 of the ship's length  $L$  from the forward perpendicular, except those in their front bulkheads, may be of normal type.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** having the length below 24 m and in ships of restricted area of navigation **R3** it is allowed to fit side

scuttles of light type instead of those of normal type. Side scuttles shall be fitted with efficient deadlights hinged inside.

**7.2.1.6** Side scuttles in enclosed superstructures and deckhouses of the second tier, except those fitted in a position within 0,25 of the ship's length from the forward perpendicular shall be as required in [7.2.1.5](#), provided these side scuttles give direct access to an open stairway leading to spaces situated below.

In cabins and similar spaces of enclosed superstructures and deckhouses of the second tier it is allowed that instead of side scuttles specified in [7.2.1.5](#), the side scuttles or windows could be fitted without deadlights.

**7.2.1.7** On no account shall the side scuttles be fitted in the outer wall sides of the floating docks and in the sides of the docklift ships so that their sills are below the margin line at docking.

In the inner wall sides of the floating docks and in the boundary bulkheads of the docklift ships installation of the side scuttles is not permitted.

**7.2.1.8** In the outer wall sides of the floating docks and in the sides of the docklift ships the side scuttles, the sills of which are above the margin line at docking by less than 300 mm or 0,025 times the ship's breadth, whichever is the greater, shall be of heavy type, fitted with hinged inside deadlights, and of non-opening type.

**7.2.1.9** In the outer wall sides of the floating docks the side scuttles, the sills of which are above the margin line at docking by 300 mm or more, shall be of normal type and fitted with hinged inside deadlights.

**7.2.1.10** Ships having distinguishing marks **FF1**, **FF2** and **FF3** in the class notation shall be fitted with side scuttles having deadlights permanently attached to their primary structure, wheelhouse windows shall be fitted with detachable screens, except side scuttles and windows in the wheelhouse, and search and rescue operation control station.

**7.2.1.11** No side scuttles shall be fitted in any spaces, which are appropriated exclusively to the carriage of cargo.

## **7.2.2 Construction and attachment of side scuttles and windows.**

**7.2.2.1** These Rules distinguish three types of side scuttle construction:

**.1** heavy type with the glass thickness of not less than 10 mm for inner diameter of 200 mm and below, not less than 15 mm for inner diameter from 300 mm to 350 mm and not less than 19 mm for inner diameter of 400 mm. The inner diameter shall not exceed 400 mm. For intermediate inner diameters (from 200 mm to 300 mm and from 350 mm to 400 mm) the glass thickness shall be determined by linear interpolation. In addition, heavy side scuttles if they are of the opening type shall have a nut (instead of one of the ear-nuts securing their glassholder) being screwed off with the aid of a special wrench;

**.2** normal type with the glass thickness of not less than 8 mm for inner diameter of 250 mm and below, and not less than 12 mm for inner diameter of 350 mm and over, however, the inner diameter shall not exceed 400 mm. For intermediate inner diameters the thickness of the glass shall be determined by linear interpolation;

**.3** light type with the glass thickness of not less than 6 mm for inner diameter of 250 mm and below and not less than 10 mm for inner diameter of 400 mm and over, however, the inner diameter shall not exceed 450 mm. For intermediate inner diameters the thickness of the glass shall be determined by linear interpolation.

**7.2.2.2** Normal and heavy side scuttles may be of non-opening type, i.e. with the glass fixed in the main frame, or of opening type, i.e. with the glass fixed in the glassholder efficiently hinged on the main frame. Exception shall be made for the cases specified in [7.2.1.3](#), [7.2.1.4](#) and [7.2.1.8](#) where the side scuttles shall be of non-opening type only.

The glasses of side scuttles shall be reliably and weathertight secured by means of a metal ring provided with screws or by other equivalent device and a gasket.

**7.2.2.3** The main frame, glassholder and deadlight of side scuttles shall have sufficient strength. The glassholder and deadlight shall be fitted with gaskets and shall be capable of being effectively closed and secured weathertight by means of ear-nuts or nuts being screwed off with the aid of a special wrench.

**7.2.2.4** The main frame, glassholder, deadlight and glass retaining ring shall be manufactured from steel, brass, aluminium alloy or other material approved by the Register.

The ear-nuts and nuts being screwed off by a special wrench shall be made of corrosion-resistant material.

Glass used for the side scuttles shall be hardened.

Other types of safe glasses with strength characteristics not less than those of the hardened ones may be used for the side scuttles.

**7.2.2.5** In fiber-reinforced plastic ships side scuttles shall be attached to the outside plating and to the bulkheads of superstructures and deckhouses in accordance with the requirements of 1.7.4 of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".

**7.2.2.6** The construction of the windows shall comply with the requirements of [7.2.2.2 — 7.2.2.4](#), except for the requirements for the deadlights.

The thickness of the window glass  $t$ , in mm, shall be not less than determined by the formula

$$t = 0,32kb\sqrt{p} \quad (7.2.2.6-1)$$

where  $b$  = lesser clear size of the window, in m;

$p$  = pressure head, in kPa, calculated according to 2.12.3 of Part II "Hull"; distance  $z_1$  being taken up to the middle of the window height;

$k$  = factor determined by the formula

$$k = 13,42 - 5,125(b/a)^2 \quad (7.2.2.6-2)$$

where  $a$  = greater clear size of the window, in m.

It is permitted to reduce the thickness of window glasses in accordance with that specified in [7.2.2.1](#).



### **7.3 FLUSH DECK SCUTTLES**

**7.3.1** Flush deck scuttles in positions 1 and 2 shall be provided with deadlights hinged or attached by other method (for example, by means of a chain) and capable of being easily and efficiently closed and secured.

**7.3.2** The largest of clear dimensions of the flush deck scuttles shall not be over 200 mm, with the glass being at least 15 mm thick. The flush deck scuttles shall be attached to the metal deck plating by means of frames.

**7.3.3** When secured, the deadlights of the flush deck scuttles shall be weathertight. The tightness shall be ensured by a rubber or other suitable gasket.

For the same purpose, along their contour the glasses of the flush deck scuttles shall be provided with a gasket made of rubber or other suitable material.

**7.3.4** The strength and materials of the flush deck scuttles parts are governed by applicable requirements specified in [7.2.2.3](#) and [7.2.2.4](#). As regards attachment of flush deck scuttles in fiber-reinforced plastic ships, [refer to 7.2.2.5](#).

## **7.4 OPENINGS IN SHELL PLATING AND THEIR CLOSING APPLIANCES**

### **7.4.1 General.**

**7.4.1.1** This Chapter contains requirements for the arrangement of bow, side and stern doors in the shell plating, strength of structural elements of the doors, securing, locking and supporting devices.

**7.4.1.2** The number of doors shall be reduced to a minimum consistent with the structure and normal operational conditions of the ship.

**7.4.1.3** When closed and secured, doors in the shell plating shall be weathertight. Weathertightness shall be ensured with a rubber or other suitable packing.

**7.4.1.4** The plating thickness of the doors made of steel, irrespective of the fulfilment of the requirements given in [7.4.1.10](#), shall be not less than the thicknesses referred to in 2.2.4.8 and 2.12.4.1 of Part II "Hull" for the appropriate position of the door; the minimum plating thickness of the doors made of other materials may be allowed provided it is confirmed by calculations and tests that they have a strength at least equivalent to that of the doors made of steel.

**7.4.1.5** Doors with a clear area of 12 m<sup>2</sup> and more shall be secured by means of a power system or by a hand gear used for securing the door from a readily accessible position. Stern, bow and side doors of large dimensions, when manual devices would not be readily accessible, shall be normally secured by means of power systems. Alternative means of securing shall also be provided for emergency use in case of failure of the power systems.

**7.4.1.6** When power-operated securing devices or devices with a hand gear are used, it is necessary to ensure that the doors shall remain tight in the secured position and shall remain secured in case of failure of any part of the power system or hand gear of the securing device.

Hydraulically operated securing devices shall be manually or mechanically lockable in the secured position.

**7.4.1.7** When power-operated securing devices or devices with a hand gear are used, provision shall be made for the indicators which clearly show whether the door is totally secured or not.

These indicators shall be fitted in a position from which the securing operation is performed, and in case of the power-operated securing device, also on the navigation bridge.

**7.4.1.8** If, due to the ship's purpose, it is specially provided to open and close the doors not only in ports but also at sea, arrangements approved by the Register shall be made (with regard to the operational conditions) to ensure closure and complete securing of the open door, even in case of failure of the door gear and securing device gear, or other arrangements approved by the Register shall be made to prevent penetration of water into the ship spaces when the door is open.

Provision shall be made for devices ensuring proper locking of the door in the open position.

The drives of such doors shall comply with the requirements of Part IX "Machinery" and Part XI "Electrical Equipment".

**7.4.1.9** There shall be a readily seen notice plate near each door, indicating that the door shall be closed and secured before the ship leaves the port; for doors referred to in [7.4.1.8](#) provision shall be also made for a notice plate indicating that at sea only the master is allowed to open the door.

**7.4.1.10** When doors are under the action of the design loads determined in accordance with [7.4.2](#) and [7.4.3](#), except [7.4.2.5](#), stresses, in MPa, in the primary members of the doors as well as of securing, locking and supporting devices shall not exceed the following values:

normal stress

$$\sigma = 120/k; \quad (7.4.1.10-1)$$

shear stress

$$\tau = 80/k; \quad (7.4.1.10-2)$$

equivalent stress

$$\sigma_{eq} = \sqrt{\sigma^2 + 3\tau^2} = 150/k \quad (7.4.1.10-3)$$

where  $k = 1,0$  for steel with upper yield stress of the material  $R_{eH} = 235$  MPa;

$k = 0,78$  for steel with  $R_{eH} = 315$  MPa;

$k = 0,72$  for steel with  $R_{eH} = 335$  MPa.

## **7.4.2 Bow doors.**

**7.4.2.1** Bow doors shall be situated above the freeboard deck.

**7.4.2.2** Where the bow door leads to a complete or long forward enclosed superstructure a weathertight inner door shall be installed as part of the collision bulkhead above the freeboard deck of the ship.

Bow and inner doors shall be so arranged as to preclude the possibility of the bow door causing structural damage to the inner door or to the collision bulkhead in case of damage to or detachment of the bow door.

**7.4.2.3** The design external pressure  $P_e$ , in kPa, for the scantlings of primary members, securing, locking and supporting devices of the bow doors is determined by the following formula:

$$P_e = C_H(0,6 + 0,41\text{tg}\alpha)(0,4v\sin\beta + 0,6\sqrt{L})^2 \quad (7.4.2.3)$$

where  $C_H$  is a coefficient equal to:

$C_H = 0,0125L$  for ships less than 80 m in length;

$C_H = 1,0$  for ships 80 m and more in length;

$v$  = contractual ship's forward speed, in knots;

$\alpha$  and  $\beta$  = angles to be obtained from [Fig. 7.4.2.3](#).

The design external pressure may be reduced by 20 % for ships of restricted areas of navigation **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** and by 40 % for ships of restricted area of navigation **R3**.

In any case, the design external pressure  $P_e$  shall not be taken less than the values determined according to 1.3.2.2 or 2.8.3.3 of Part II "Hull", whichever is the greater.




Fig. 7.4.2.3

**7.4.2.4** The design internal pressure  $P_i$ , in kPa, for scantlings of primary members, securing, locking and supporting devices of inner doors shall be determined by the formula

$$P_i = 10z \quad (7.4.2.4)$$

where  $z$  = vertical distance from the centre of gravity of the door area to the deck above, in m.

In all cases, the value of the design internal pressure  $P_i$  shall not be less than 25 kPa.

**7.4.2.5** The scantlings of primary members of visor doors shall be chosen in accordance with the requirements of 2.8.5.1 of Part II "Hull".

**7.4.2.6** Securing and locking devices of bow doors shall be designed to withstand the forces  $F_e$  or  $F_i$ , in kN, to be determined by the following formulae:

for the doors opening inwards

$$F_e = AP_e + p_p l_p; \quad (7.4.2.6-1)$$

for the doors opening outwards

$$F_i = AP_i + 10Q + p_p l_p \quad (7.4.2.6-2)$$

where  $A$  = clear area of the door, in  $m^2$ ;

for  $P_e$ , refer to 7.4.2.3;

for  $P_i$ , refer to 7.4.2.4;

$p_p$  = pressure of the packing when it is compressed for the maximum depth possible, in kN/m, is assumed in calculations equal to at least 5 kN/m;

$l_p$  = length of the packing, in m;

$Q$  = mass of the door, in t.

**7.4.2.7** Securing and locking devices, as well as supports of the visor doors shall be designed to withstand forces  $F_{xf}$ ,  $F_{xa}$ ,  $F_y$  and  $F_z$ , in kN.

The forces acting in the longitudinal direction shall be determined by the following formulae:

bow

$$F_{xf} = \frac{10Qc + P_{xe}a - P_zb}{d}; \quad (7.4.2.7-1)$$

stern

$$F_{xa} = \frac{10Qc - P_{xi} a}{d}. \quad (7.4.2.7-2)$$

The force acting in the transverse direction shall be determined by the formula

$$F_y = P_e A_y. \quad (7.4.2.7-3)$$

The force acting in the vertical direction shall be determined by the formula

$$F_z = P_z - 10Q \quad (7.4.2.7-4)$$

or

$$F_z = 10(V - Q), \text{ whichever is the greater} \quad (7.4.2.7-5)$$

where for  $Q$ , refer to [7.4.2.6](#);  
for  $P_e$ , refer to [7.4.2.3](#);

$$P_{xe} = P_e A_x, \text{ in kN} \quad (7.4.2.7-6)$$

where  $A_x$  = area of the transverse vertical projection of the door ([refer to Fig. 7.4.2.7](#)), in m<sup>2</sup>;

$$P_z = P_e A_z, \text{ in kN} \quad (7.4.2.7-7)$$

where  $A_z$  = area of horizontal projection of the door ([refer to Fig. 7.4.2.7](#)), in m<sup>2</sup>;

$$P_{xi} = P_i A_x, \text{ in kN} \quad (7.4.2.7-8)$$

where for  $P_i$ , refer to [7.4.2.4](#);

$A_y$  = area of the longitudinal vertical projection of the door ([refer to Fig. 7.4.2.7](#)), in m<sup>2</sup>;

$a$  = vertical distance, in m, from visor pivot to the centroid of the transverse vertical projected area of the visor door ([refer to Fig. 7.4.2.7](#));

$b$  = vertical distance, in m, from visor pivot to the centroid of the horizontal projected area of the visor door  $A_z$  ([refer to Fig. 7.4.2.7](#));

$c$  = horizontal distance, in m, from visor pivot to the centre of gravity of the visor mass ([refer to Fig. 7.4.2.7](#));

$d$  = vertical distance, in m, from visor pivot to the bottom of the door ([refer to Fig. 7.4.2.7](#));

$V$  = inner volume of the door, in m<sup>3</sup>.





Fig. 7.4.2.7

**7.4.2.8** For side-opening doors, thrust bearing shall be provided in way of girder ends at the closing of two leaves to prevent one leaf shifting towards the other one under effect of unsymmetrical pressure ([refer to Fig. 7.4.2.8](#)). Each part of the thrust bearing shall be kept secured on the other part by means of securing devices.

Fig. 7.4.2.8  
Thrust bearing

**7.4.2.9** Lifting arms of the visor doors and thrust bearing shall be designed to withstand static and dynamic loads arising when the door is opened and closed with due regard to the minimum wind pressure 1,5 kN/m<sup>2</sup>.

**7.4.3 Side and stern doors.**

**7.4.3.1** The lower edge of the door openings shall not be lower than the line which is parallel to the freeboard deck and has its lowest point at the uppermost cargo waterline.

The lower edge of side doors of the ships which are not passenger ships, may be lower than that specified above provided it is proved by the designer that safety of the ship will not be thus impaired.

In such cases, provision shall be made for: the second (inner) doors, strength and tightness of which is equivalent to those of the outer doors; a device enabling to determine water presence in the space between the doors; water drainage from this space to bilges or drain wells, controlled by a readily accessible valve or other arrangements approved by the Register.

**7.4.3.2** The doors shall open outwards so that forces acting under the effect of the sea press the door against the supporting contour of the sill. Installation of the doors opening inside may be allowed provided it is proved by the designer that safety of the ship will not be thus impaired.

**7.4.3.3** The number of securing devices on each edge of the door shall be not less than two; a securing device shall be provided in the vicinity of each door corner. The distance between securing devices shall not exceed 2,5 m.

**7.4.3.4** The design external pressure  $P$ , in kPa, for structural members of doors shall be determined in accordance with the requirements of 1.3.2 of Part II "Hull". In any case, the value of  $P$  shall not be taken less than 25 kPa.

**7.4.3.5** Securing and locking devices shall be designed to withstand the forces  $F_1$  or  $F_2$ , in kN, determined by the formulae:

for doors opening inwards

external force

$$F_1 = AP + p_p l_p; \quad (7.4.3.5-1)$$

internal force

$$F_2 = F_c + 10Q; \quad (7.4.3.5-2)$$

for doors opening outwards

external force

$$F_1 = AP; \quad (7.4.3.5-3)$$

internal force

$$F_2 = F_c + 10Q + p_p l_p \quad (7.4.3.5-4)$$

where for  $A$ ,  $p_p$  and  $l_p$ , [refer to 7.4.2.6](#);

for  $P$ , [refer to 7.4.3.4](#)

$F_c$  = an accidental force due to loose of cargo, to be uniformly distributed over the area  $A$  and to be taken not less than 300 kN or  $5A$ , in kN, whichever is the greater.

For small doors, such as bunker doors or pilot doors, the value of  $F_c$  may be reduced provided the appropriate technical background has been submitted. However, the value of  $F_c$  may be taken as zero, provided an additional structure such as an inner ramp is fitted, which is capable of protecting the door from accidental forces due to loose cargoes;

for  $Q$ , [refer to 7.4.2.6](#).

Supporting structures of doors shall be designed to withstand forces  $F_3$  and  $F_4$ , in kN, determined by the formulae:

external force

$$F_3 = AP; \quad (7.4.3.5-5)$$

internal force

$$F_4 = F_c + 10Q. \quad (7.4.3.5-6)$$



## 7.5 SUPERSTRUCTURES AND DECKHOUSES

### 7.5.1 Construction, openings and closing appliances.

**7.5.1.1** Openings in the freeboard deck other than those defined in [7.3](#), [7.6 — 7.11](#) and [7.13](#) shall be protected by the enclosed superstructure or enclosed deckhouse. The similar openings in the deck of enclosed superstructure or enclosed deckhouse shall be protected by enclosed deckhouse of the second tier.

**7.5.1.2** Superstructures and deckhouses are considered enclosed if:  
their construction complies with the requirements of 2.12 of Part II "Hull";  
all access openings comply with the requirements of [7.5.2](#) and [7.7](#);  
all other openings in their outside contour comply with requirements of [7.2 — 7.4](#) and [7.7 — 7.10](#).

### 7.5.2 Doors in enclosed superstructures and enclosed deckhouses.

**7.5.2.1** All access openings in the end bulkheads of enclosed superstructures and outside bulkheads of enclosed deckhouses shall be fitted with doors (refer to 2.4.4 of Part VI "Fire Protection").

**7.5.2.2** The height of the sills to access openings specified in [7.5.2.1](#) shall be at least 380 mm. However, the bridge or poop shall not be regarded as enclosed unless access is provided for the crew to machinery and other working spaces inside these superstructures from any place in the uppermost continuous open deck or above it by alternative means which are available at all times when bulkhead openings are closed; the height of the sills of the openings in the bulkheads of such bridge or poop shall be at least 600 mm in position 1 and at least 380 mm in position 2.

In ships of restricted area of navigation **R3** having the length of 24 m and over (except for passenger ships) the specified height of the sills to access openings may be reduced from 600 mm down to 450 mm and from 380 mm down to 230 mm, respectively.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)**, **R3-RSN** and **R3** having the length below 24 m the height of the above sills may be reduced to 230 mm for all open decks.

**7.5.2.3** The doors shall be so designed as to withstand the pressure head  $p$  calculated according to 2.12.3 of Part II "Hull", the distance  $z_1$  being taken up to the middle of the door height. Under the pressure head  $p$  the stresses in the door elements shall not exceed 0,8 times the upper yield stress of the material.

Whatever the stresses, the thickness of the steel door plate shall be not less than that specified in 2.12.4.4 of Part II "Hull". For steel doors manufactured by stamping the minimum thickness of the door plate may be reduced by 1 mm.

The minimum thickness of the door plate made of other materials may be allowed provided it is confirmed by calculations and tests that they have a strength at least equivalent to that of the doors made of steel.

**7.5.2.4** The doors shall be permanently and strongly attached to the bulkhead and fitted with clamping devices or other equivalent means for expeditiously opening, closing and securing them weathertight; such devices shall be so arranged that they can be operated from both sides of the bulkhead. The doors shall open outwards, opening of doors inside the superstructure or deckhouse space may be allowed when security against the impact of the sea is provided.

**7.5.2.5** The doors shall be weathertight when secured. The tightness shall be ensured by a rubber or other suitable gasket.

**7.5.2.6** The doors shall be made of steel or other material approved by the Register.

**7.5.2.7** In fiber-reinforced plastic ships the doors shall be attached to the bulkheads of superstructures and deckhouses in the same manner as the side scuttles, in accordance with the requirements of [7.2.2.5](#).

**7.5.2.8** In floating docks the height of the sills to access openings in superstructures and deckhouses of the top deck shall be at least 200 mm if access is provided from these superstructures and deckhouses into the spaces situated below.

## 7.6 ENGINE AND BOILER CASINGS

**7.6.1** Engine and boiler space openings in positions 1 and 2 shall be efficiently enclosed by casings of ample strength raised above decks to the extent, which is reasonable and practicable, and being in their turn decked or terminated in skylights. The construction of the casings shall meet the requirements of 2.13 of Part II "Hull", and in case of fiber-reinforced plastic ships, the requirements of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".

**7.6.2** Casings shall be made weathertight.

**7.6.3** Casings shall be made of steel or other materials approved by the Register (refer also to 2.1.1.2 of Part VI "Fire Protection").

**7.6.4** The access openings in the casings shall be fitted with permanently attached doors complying with the requirements of [7.5.2.3 — 7.5.2.6](#). The height of the sills to the access openings shall be at least 600 mm in position 1 and at least 380 mm in position 2.

If the length of the ship is less than 24 m, the specified height of the sills may be reduced down to 300 mm for ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)**, **R3-RSN** and **R3**.

In ships of restricted area of navigation **R3** having the length of 24 m and over (except passenger ships) the specified height of the sills may be reduced from 600 mm down to 450 mm and from 380 mm down to 230 mm, respectively.

**7.6.5** In type "A" ships and also in type "B" ships which are permitted to have the tabular freeboard less than that prescribed by Table 4.1.3.2, 6.4.2.3 or 6.4.3.3 of the Load Line Rules for Sea-Going Ships, the engine and boiler casings shall be protected by enclosed poop or bridge of at least standard height, or by a deckhouse of equal height and equivalent strength. However, engine and boiler casings may be exposed if there are no openings giving direct access from the freeboard deck to the machinery space. A door complying with requirements of [7.5.2.3 — 7.5.2.6](#) may, however, be permitted in the machinery casing provided that it leads to a space or passageway which is as strongly constructed as the casing and is separated from the stairway to the engine and boiler room by a second similar door. The opening for the outside door shall be provided with a sill at least 600 mm in height, and that for the inside door with a sill of at least 230 mm in height.

**7.6.6** In supply vessels the doors in the casings giving access to the engine or boiler rooms shall be located, where possible, inside the enclosed superstructure or deckhouse. The door in the casing for access to the engine or boiler room may be fitted directly on the open cargo deck provided that, in addition to the first outside door, the second inside door is fitted; in this case, the outside and inside doors shall satisfy the requirements of [7.5.2.3 — 7.5.2.6](#), the height of the outside door sill shall be at least 600 mm, and of the inside door sill, at least 230 mm.

**7.6.7** In floating docks the height of sills to the top deck access openings in the engine and boiler casings shall be at least 200 mm.

## 7.7 COMPANION HATCHES, SKYLIGHTS AND VENTILATING TRUNKS

### 7.7.1 Design and securing.

**7.7.1.1** Deck openings in positions 1 and 2 intended for stairways to the ship's spaces located below, as well as light and air openings to these spaces shall be protected by strong companion hatches, skylights or ventilating trunks.

Where the openings intended for stairways to the ship's spaces located below are protected by superstructures or deckhouses instead of companion hatches, these superstructures and deckhouses shall comply with the requirements of [7.5](#).

Hatch covers intended for emergency escape to the lifeboat and liferaft embarkation deck ([refer to 8.5.1](#)), shall be constructed in such a manner that the securing devices shall be of a type which can be opened from both sides of the hatch cover, and the maximum force needed to open the hatch cover shall not exceed 150 N. The use of a spring equalizing, counterbalance or other suitable device on the hinge side to reduce the force needed for opening is acceptable.

For oil tankers of 150 m in length and above as well as bulk carriers of 90 m in length and above, contracted for construction on or after 1 July 2015, the requirements for cargo hatch covers are regulated by the IACS Common Structural Rules.

**7.7.1.2** Height of coamings of companion hatches, skylights and ventilating trunks shall be at least 600 mm in position 1 and at least 450 mm in position 2. In ships of restricted area of navigation **R3** having the length of 24 m and over (except passenger ships) the specified height of coamings may be reduced from 600 mm down to 450 mm and from 450 mm down to 380 mm, respectively. If the length of the ship is less than 24 m, the height of the coamings may be reduced down to 380 mm for ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** and down to 300 mm for ships of restricted area of navigation **R3**.

Height of a coaming may be reduced if such a height would interfere with the normal operation of the ship, provided the seaworthiness and deck wetness assessment is submitted by the designer. Such assessment verifies the ship safety with sea condition in respect to the assigned area of navigation.

Construction of coamings shall comply with the requirements of 2.6.5.2 of Part II "Hull" and in case of fiber-reinforced plastic ships, with the requirements of Part XVI "Structure and Strength of Fiber-Reinforced Plastic Ships".

**7.7.1.3** All the companion hatches, skylights and ventilating trunks shall be provided with covers made of steel or other material approved by the Register and being permanently attached to the coamings.

Where the covers are made of steel, the thickness of their plate shall be equal to at least 0,01 times the spacing of stiffeners, but not less than 6 mm.

For ships of less than 500 gross tonnage, the minimum required thickness of 6 mm maybe reduced if the cover is made by stamping in accordance with [Fig. 7.7.1.3](#) and [Table 7.7.1.3](#).

In small ships having the deck thickness less than 6 mm the required minimum thickness 6 mm may be reduced down to the deck thickness regardless of whether the cover is made by stamping, but in no case the plate thickness shall be less than 4 mm.




Fig 7.7.1.3

Table 7.7.1.3

Clear sizes of hatches $l \times b$ , in mm	Material of cover	Height of stamping $h$ , in mm	Minimum thickness $s$ , in mm
450×600	Steel	25	4
	Light alloy		
600×600	Steel	28	4
	Light alloy		
700×700	Steel	40	4
	Light alloy		6
800×800	Steel	55	4
	Light alloy		6
800×1200	Steel	55	5
	Light alloy		6
1000×1400	Steel	90	5

**7.7.1.4** Covers of companion hatches, skylights and ventilating trunks shall have securing devices workable at least from outside of the hatch. However, where the hatches are used as emergency exits in addition to their primary application, the securing device shall be capable of being operated from each side of the cover.

When secured, the covers shall be weathertight. The tightness shall be provided by a rubber or other suitable gasket.

**7.7.1.5** The glass for windows in the covers of skylights shall be hardened and at least 6 mm thick if the inner diameter is 150 mm and below, and at least 12 mm with the inner diameter of 450 mm. For intermediate inner diameters, the thickness of glass shall be determined by linear interpolation. However, where wire-reinforced glass is used, its thickness may be 5 mm, and the requirement relating to its hardening will not be applicable.

Glass shall be efficiently attached to the covers by means of a frame and have on its contour a weathertight gasket of rubber or other equivalent material.

Skylights installed in the machinery spaces of category A, shall comply with the requirements of 2.1.4.2 of Part VI "Fire Protection".

**7.7.1.6** Each window or group of adjacent windows shall be provided with portable shields of the same material as the cover being at least 3 mm in thickness and capable of being efficiently fastened outside the cover by means of ear-nuts; such portable shields shall be stowed adjacent to the skylights.

**7.7.1.7** In floating docks the height of coamings of companion hatches, skylights and ventilating trunks situated on the top deck shall be at least 200 mm.

The portable shields mentioned in [7.7.1.6](#) need not be provided for covers of skylights situated on the top deck of the floating docks.

**7.7.2 Design and securing of small hatches on the exposed for deck.**

**7.7.2.1** The requirements of [7.7.2](#) apply to hatches generally having an area of not more than  $2,5 \text{ m}^2$  located on the exposed deck at a distance of  $0,25L$  from the fore perpendicular of ships of 80 m in length and more, where the height of the exposed deck in way of the hatch is less than  $0,1L$  or 22 m above the summer load waterline, whichever is less. The ship length  $L$  is determined according to 1.1.3 of Part II "Hull".

**7.7.2.2** For rectangular or square steel hatch covers, the plate thickness, stiffener arrangement and scantlings shall be in accordance with [Table 7.7.2.2](#) and [Fig. 7.7.2.2](#). Stiffeners, where fitted, shall be aligned with contact points of the hatch cover edge with the welded pad (metal-to-metal contact points) required in accordance with [7.7.2.6](#) ([refer to Fig. 7.7.2.2](#)). Primary stiffeners shall be continuous. All stiffeners shall be welded to the inner edge stiffener ([refer to Fig. 7.7.2.8](#)).

Table 7.7.2.2

Nominal size, mm×mm	Cover plate thickness, in mm	Primary stiffeners	Secondary stiffeners
		Flat bar, mm×mm; number	
630×630	8	—	—
630×830	8	100×8; 1	—
830×630	8	100×8; 1	—
830×830	8	100×10; 1	—
1030×1030	8	120×12; 1	80×8; 2
1330×1330	8	150×12; 2	100×10; 2








Fig. 7.7.2.2

Nominal sizes of hatch covers:

$a = 630 \times 630$  mm;  $b = 630 \times 830$  mm;  $c = 830 \times 830$  mm;  $d = 830 \times 630$  mm;  $e = 1030 \times 1030$  mm;  
 $f = 1330 \times 1330$  mm

Symbols:

-  — hinge;
-  — securing device/metal-to-metal contact;
-  — primary stiffener;
-  — secondary stiffener

**7.7.2.3** The hatchway coaming shall be suitably reinforced by a horizontal flat bar, normally not more than 170 — 190 mm from the upper edge of the coaming.

**7.7.2.4** For hatch covers constructed of materials other than steel, the required scantlings shall provide equivalent strength.

**7.7.2.5** Weathertightness of hatch covers shall be ensured by securing devices of the following types: butterfly nuts tightening onto forks (clamps); quick acting cleats; central locking device. Dogs (twist tightening handles) with wedges are not acceptable.

Where the hatch covers are also used as emergency exits, they shall be also fitted with the central quick acting locking device designed for handling on both sides.

**7.7.2.6** The hatch cover shall be fitted with a gasket of elastic material. This shall be designed to allow a contact of the hatch cover edge to the welded pad (metal-to-metal contact) at a designed compression and to prevent over compression of the gasket by green sea forces that may cause the securing devices to be loosened or dislodged. The contacts of the hatch cover edge to the welded pad (metal-to-metal contact) shall be arranged close to each securing device in accordance with [Fig. 7.7.2.2](#), and shall be of sufficient capacity to withstand the bearing force.

**7.7.2.7** The primary securing device shall be designed and manufactured so that the designed compression pressure is achieved by one person without the need of any tools.

**7.7.2.8** Where butterfly nuts are used in the primary securing device, the forks (clamps) shall be of the robust design, which minimizes the risk of the butterfly nuts being dislodged while in use. It is ensured by curving the forks upward, a raised surface on the free end, or a similar method ([refer to Fig. 7.7.2.8](#)). The plate thickness of unstiffened steel forks (clamps) shall not be less than 16 mm.




Fig. 7.7.2.8:

- 1 — butterfly nut; 2 — bolt; 3 — pin; 4 — centre of pin; 5 — fork (damp) plate; 6 — hatch cover; 7 — gasket;  
8 — hatch coaming; 9 — bearing pad welded on the bracket for metal-to-metal contact; 10 — stiffener;  
11 — inner edge stiffener

**7.7.2.9** For hatch covers located on the exposed deck forward of the fore-most cargo hatch, the hinges shall be fitted such that the predominant direction of green sea will cause the cover to close, which means that the hinges are normally to be located on the fore edge.

**7.7.2.10** On hatches located between the cargo hatches, the hinges shall be placed on the fore edge or outboard edge, whichever is practicable for protection from green water in beam sea and bow quartering conditions.

**7.7.2.11** Hatches, excepting those which may also be used as emergency exits, shall be fitted with an independent secondary securing device like, e.g. a sliding bolt, a hasp or a backing bar of slack fit, which is capable of keeping the hatch cover in place, even in the event that the primary securing device became loosened or dislodged. It shall be fitted on the side opposite to the hatch cover hinges.



## **7.8 VENTILATORS**

**7.8.1** Ventilators to spaces below freeboard deck or deck of enclosed superstructures and deckhouses shall be fitted with coamings efficiently connected to the deck.

The coamings of ventilators shall be at least 900 mm in height in position 1 and at least 760 mm in position 2.

In ships of restricted area of navigation **R3** having the length of 24 m and over (except passenger ships) the specified height of the coamings may be reduced from 900 mm down to 760 mm and from 760 mm down to 600 mm, respectively.

In ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)**, **R3-RSN** and **R3** having the length below 24 m the height of the coamings may be reduced down to 300 mm for all open decks.

Construction of coamings shall comply with the requirements of 2.6.5.2 of Part II "Hull". The strength of ventilators, connections of ventilators to coamings and connections of ventilator parts, if any, shall be equivalent to that of the coaming.

**7.8.2** Ventilators in position 1 the coamings of which extend to more than 4500 mm above the deck and in position 2 the coamings of which extend to more than 2300 mm above the deck need not be fitted with closing appliances. In all other cases, each ventilator shall be fitted with a strong cover made of steel or other material approved by the Register.

In ships of less than 100 m in length, the covers shall be permanently attached; in ships of 100 m in length and over they may be conveniently stowed near the ventilators to which they shall be fitted.

**7.8.3** When secured, the covers of ventilators shall be weathertight. The tightness shall be provided by a rubber or other suitable gasket.

**7.8.4** In supply vessels, in order to minimize the possibility of flooding of the spaces situated below, the ventilators shall be positioned in the protected locations where the probability of their damage by cargo is excluded during cargo handling operations. Particular attention shall be given to the arrangement of ventilators of the engine and boiler rooms for which the location is preferable above the deck level of the first tier of superstructures or deckhouses.

**7.8.5** In floating docks the height of coamings of ventilators situated on the top deck shall be at least 200 mm.

## **7.9 MANHOLES**

**7.9.1** The height of coamings of manholes for deep and other tanks, except for those indicated in 2.4.5.3 of Part II "Hull", air spaces, cofferdams, etc. is not regulated by the Register.

**7.9.2** Covers of manholes shall be made of steel or other material approved by the Register.

The thickness of the covers shall not be less than that of the plating on which they are fitted. The thickness of the covers, where the thickness of plating is greater than 12 mm, may be reduced based on appropriate technical background confirming that covers have a sufficient strength.

**7.9.3** The covers of manholes shall be efficiently attached to the coaming or doubling ring by means of bolts or pins with nuts.

**7.9.4** When secured, the covers shall be tight both for water and liquid cargoes or stores for which the tanks are intended under the inner pressure corresponding to the test pressure of the tank under consideration.

The tightness shall be provided by a rubber or other suitable gasket. The gasket shall be resistant to the liquids referred to above.

## 7.10 HATCHWAYS OF DRY CARGO HOLDS

### 7.10.1 General.

The deck openings through which cargoes or ship's stores are loaded and unloaded shall be protected by strong hatchways. If these hatchways are situated in positions 1 and 2, the hatchway covers shall be weathertight. The tightness shall be provided by one of the following two methods:

- .1 by portable covers and tarpaulins as well as battening devices;
- .2 by weathertight covers made of steel or other equivalent material fitted with rubber or other suitable gaskets and clamping devices.

The requirements of this Chapter apply to all ships except bulk carriers, self-unloading bulk carriers, ore carriers and combination carriers, and are for all cargo hatch covers and coamings on exposed decks.

### 7.10.2 Coamings.

**7.10.2.1** The height of hatchway coamings in positions 1 and 2 shall be at least 600 mm and 450 mm, respectively.

If the length of the ship is less than 24 m, the height of the coamings may be reduced down to 380 mm for ships of restricted area of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** and down to 300 mm for ships of restricted area of navigation **R3**.

In ships of restricted area of navigation **R3** having the length of 24 m and over (except passenger ships) the specified height of cargo hatchway coamings may be reduced from 600 mm down to 450 mm and from 450 mm down to 380 mm, respectively.

In fishing vessels, the height of cargo hatchway coamings in position 2 may be reduced down to 300 mm.

**7.10.2.2** The height of coamings of the hatchways specified in [7.10.1.2](#) may be reduced as compared to that required by [7.10.2.1](#) or the coamings may be omitted entirely provided that the cover tightness and securing means are found efficient and the following is submitted:

for hatches that are closed at sea — technical background containing operational limitations considering designation and nature of hatch application;

for hatches that may be open at sea — technical background containing assessment of seaworthiness and deck flooding as well as confirmation that the safety of the ship is provided at any sea condition in accordance with the designated area of navigation.

### 7.10.3 Materials.

**7.10.3.1** For steel of top plate, bottom plate and primary supporting members, refer to [1.6](#).

**7.10.3.2** The wood of hatchway covers shall be of good quality and of the type and grade which proved to be satisfactory for this purpose. Wedges shall be of hard wood.

**7.10.3.3** Canvas used for making tarpaulins shall be impregnated to make them moisture-resistant and shall not contain jute thread. Mass of 1 m<sup>2</sup> of canvas before impregnation shall be not less than 0,55 kg. Breaking stress of impregnated canvas band 200×50 mm in size shall be at least 3 kN and 2 kN in longitudinal and transverse directions, respectively. When tested for watertightness, the impregnated canvas shall not get wet under water head of 0,15 m acting for 24 h.

**7.10.3.4** The rubber for packing gaskets of hatchway covers shall be elastic, strong, and resistant to atmospheric changes. The rubber shall be of sufficient hardness.

**7.10.3.5** All internal and external surfaces of steel hatch covers in bulk carriers (except inaccessible spaces in box type covers) shall have effective epoxy or other equivalent protective coating applied in accordance with the recommendations of the manufacturer (refer to 1.1.4.7 and 3.3.5.1 of Part II "Hull").

**7.10.4 Design loads.**

Hatchway covers shall be designed to sustain deck cargoes which are intended to be carried on these covers. Where operation of the cargo handling cars on hatchways covers is anticipated in the course of the ship's service, during cargo handling operations, the loads induced by such cars shall be taken into consideration. For hatchway covers in positions 1 and 2 the design load shall be calculated in accordance with 3.2.5.2 of the Load Line Rules for Sea-Going Ships; design of hatch covers shall comply with the requirements of 3.2.5.3 — 3.2.5.5 of the above Rules.

For ships of less than 24 m in length of restricted area of navigation engaged on international voyages and for all ships of restricted area of navigation not engaged on international voyages the load intensity reduced by the following values may be used instead of load intensity specified in 3.2.5.2 of the Load Line Rules for Sea-Going Ships:

15 % for ships of restricted areas of navigation **R2**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN**;

30 % for ships of restricted area of navigation **R3**.

**7.10.5 Design of hatch covers specified in 7.10.1.1.**

**7.10.5.1** Design of these hatch covers shall meet the requirements of 3.2.4 of the Load Line Rules for Sea-Going Ships.

**7.10.6 Structure of hatch covers indicated in 7.10.1.2.**

**7.10.6.1** Structure of these covers shall meet the requirements of 3.2.5 of the Load Line Rules for Sea-Going Ships.

**7.10.6.2** Primary supporting members and secondary stiffeners of hatch covers shall be continuous over the breadth and length of hatch covers, as far as practical. When this is impractical, sniped end connections shall not be used and appropriate arrangements shall be adopted to provide sufficient load carrying capacity.

**7.10.6.3** The spacing of primary supporting members parallel to the direction of secondary stiffeners shall not exceed 1/3 of the span of primary supporting members. When strength calculation is carried out by FE analysis using plane strain or shell elements, this requirement can be waived.

Secondary stiffeners of hatch coamings shall be continuous over the breadth and length of hatch coamings.

**7.10.6.4** Unless otherwise quoted, the thickness  $t$  of the following sections is the net thickness.

Net thickness is the member thickness necessary to obtain the minimum net scantlings. The required gross thicknesses are obtained by adding corrosion additions  $t_s$ . Strength calculations using beam theory, grillage analysis or FEM shall be performed with net scantlings.

**7.10.6.5** Structural assessment of hatch covers and hatch coamings shall be carried out using the design loads, defined in this Chapter and the following definitions shall be used:

$L$  — length of ship, in m, as defined in 1.1.3 of Part II "Hull";

$L_{LL}$  — length of ship, in m, as defined in the present Part;

$x$  — longitudinal coordinate of mid point of assessed structural member measured from aft end of length  $L$  or  $L_{LL}$ , as applicable;

$D_{min}$  — the least moulded depth, in m, as defined in 1.2.1 of the Load Line Rules for Sea-Going Ships;

$h_N$  — standard superstructure height, in m;

$h_N = 1,05 + 0,01L_{LL}$ , and  $1,8 \leq h_N \leq 2,3$ .


**7.10.6.6** The pressure  $p_H$ , in kN/m<sup>2</sup>, on the hatch cover panels is given in [Table 7.10.6.6](#). The vertical weather design load needs not to be combined with cargo loads. In [Fig. 7.10.6.6](#) positions 1 and 2 are illustrated for an example ship.

Table 7.10.6.6

**Design load  $p_H$  of weather deck hatch covers**

Position	Design load $p_H$ , in kN/m <sup>2</sup>	
	$x/L_{LL} \leq 0,75$	$0,75 < x/L_{LL} \leq 1,0$
1	for $24 \text{ m} \leq L_{LL} \leq 100 \text{ m}$	
	$\frac{9,81}{76} (1,5L_{LL} + 116)$	on freeboard deck: $\frac{9,81}{76} [(4,28L_{LL} + 28) \frac{x}{L_{LL}} - 1,71L_{LL} + 95]$ upon exposed superstructure decks located at least one superstructure standard height above the freeboard deck: $\frac{9,81}{76} (1,5L_{LL} + 116)$
	for $L_{LL} > 100 \text{ m}$	
	9,81×3,5	on freeboard deck for type B ships according to the International Convention on Load Lines: $9,81 \left[ (0,0296L_1 + 3,04) \frac{x}{L_{LL}} - 0,0222L_1 + 1,22 \right]$ on freeboard deck for ships with less freeboard than type B according to the International Convention on Load Lines: $9,81 \left[ (0,1452L_1 + 8,52) \frac{x}{L_{LL}} - 0,1089L_1 + 9,89 \right]$ $L_1 = L_{LL}$ but not more than 340 m upon exposed superstructure decks located at least on superstructure standard height above the freeboard deck: 9,81×3,5
2	for $24 \text{ m} \leq L_{LL} \leq 100 \text{ m}$	
	$\frac{9,81}{76} (1,1L_{LL} + 87,6)$	
	for $L_{LL} > 100 \text{ m}$	
	9,81×2,6 upon exposed superstructure decks located at least one superstructure standard height above the lowest position 2 deck: 9,81×2,1	

Positions 1 and 2



Positions 1 and 2 for an increased freeboard




Fig. 7.10.6.6

\* Reduced load upon exposed superstructure decks located at least one superstructure standard height above the freeboard deck.

\*\* Reduced load upon exposed superstructure decks of ships with  $L_{LL} > 100$  m located at least one superstructure standard height above the lowest position 2 deck.

**7.10.6.7** Where an increased freeboard is assigned, the design load for hatch covers according to [Table 7.10.6.6](#) on the actual freeboard deck may be as required for a superstructure deck, provided the summer freeboard is such that the resulting draught will not be greater than that corresponding to the minimum freeboard calculated from an assumed freeboard deck situated at a distance at least equal to the standard superstructure height  $h_N$  below the actual freeboard deck ([refer to Fig. 7.10.6.6](#)).

**7.10.6.8** The horizontal weather design load  $p_A$ , in  $\text{kN/m}^2$ , for determining the scantlings of outer edge girders (skirt plates) of weather deck hatch covers and of hatch coamings shall be determined by the formula

$$p_A = ac(bc_L f - z) \quad (7.10.6.8)$$

where  $f = L/25 + 4,1$  for  $L < 90$  m;

$$f = 10,75 - \left(\frac{300-L}{100}\right)^{1,5} \quad \text{for } 90 \text{ m} \leq L < 300 \text{ m};$$

$$f = 10,75 \quad \text{for } 300 \text{ m} \leq L < 350 \text{ m};$$

$$f = 10,75 - \left(\frac{L-350}{150}\right)^{1,5} \quad \text{for } 350 \text{ m} \leq L \leq 500 \text{ m};$$

$$\begin{aligned}
 c_L &= \sqrt{L/90} \quad \text{for } L < 90; \\
 c_L &= 1 \quad \text{for } L \geq 90; \\
 a &= 20 + L_1/12 \quad \text{for unprotected front coamings and hatch cover skirt plates;} \\
 a &= 10 + L_1/12 \quad \text{for unprotected front coamings and hatch cover skirt plates, where the distance} \\
 &\quad \text{from the actual freeboard deck to the summer load line exceeds the minimum non-corrected} \\
 &\quad \text{tabular freeboard according to the International Convention on Load Lines by at least one} \\
 &\quad \text{standard superstructure height } h_N; \\
 a &= 5 + L_1/15 \quad \text{for side and protected front coamings and hatch cover skirt plates;} \\
 a &= 7 + L_1/100 - 8x'/L \quad \text{for aft ends of coamings and aft hatch cover skirt plates abaft amidships;} \\
 a &= 5 + L_1/100 - 4x'/L \quad \text{for aft ends of coamings and aft hatch cover skirt plates forward of} \\
 &\quad \text{amidships;} \\
 L_1 &= L, \text{ need not be taken greater than 300 m;} \\
 b &= 1,0 + \left( \frac{x'/L - 0,45}{C_B + 0,2} \right)^2 \quad \text{for } x'/L < 0,45; \\
 b &= 1,0 + 1,5 \left( \frac{x'/L - 0,45}{C_B + 0,2} \right)^2 \quad \text{for } x'/L \geq 0,45
 \end{aligned}$$

where  $0,6 \leq C_B \leq 0,8$  when determining scantlings of aft ends of coamings and aft hatch cover skirt plates forward of amidships,  $C_B$  need not be taken less than 0,8;

$x'$  = distance, in m, between the transverse coaming or hatch cover skirt plate considered and aft end of the length  $L$ . When determining side coamings or side hatch cover skirt plates, the side shall be subdivided into parts of approximately equal length, not exceeding  $0,15 L$  each, and  $x'$  shall be taken as the distance between aft end of the length  $L$  and the centre of each part considered;

$z$  = vertical distance, in m, from the summer load line to the midpoint of stiffener span, or to the middle of the plate field;

$$c = 0,3 + 0,7 \frac{b'}{B'}$$

where  $b'$  = breadth of coaming, in m, at the position considered;

$B'$  = actual maximum breadth of ship, in m, on the exposed weather deck at the position considered;

$b'/B'$  shall not be taken less than 0,25.

The design load  $p_A$  shall not be taken less than the minimum values given in [Table 7.10.6.8](#).

Note. The horizontal weather design load need not be included in the direct strength calculation of the hatch cover, unless it is utilized for the design of substructures of horizontal support according to [7.10.6.51](#).

Table 7.10.6.8

$L$	Minimum design load $p_{A \min}$	
	$p_{A \min}$ , in kN/m <sup>2</sup> , for	
	unprotected fronts	elsewhere
$\leq 50$	30	15
$> 50$	$25 + \frac{L}{10}$	$12,5 + \frac{L}{20}$
$< 250$		
$\geq 250$	50	25

$$p_l = p_c(1 + a_p) \quad (7.10.6.9)$$
$$a_{\gamma} = Fm$$

where  $m_0 = 1,5 + F$ ;  
 $v_0$  = maximum speed at summer load line draught;  
 $v_0$  shall not be taken less than  $\sqrt{L}$ , in knots.

$$P = P_{\zeta}(1 + a_{\eta}) \quad (7.10.6.10)$$

**7.10.6.11** The loads defined in [7.10.6.11.1](#) shall be applied where containers are stowed on the hatch cover.




Fig 7.10.6.11  
Forces due to container loads



**7.10.6.11.1** The load  $P$ , in kN, applied at each corner of a container stack, and resulting from heave and pitch (i.e. ship in upright condition) shall be determined as follows:

$$P = 9,81 \frac{M}{4} (1 + a_v) \quad (7.10.6.11.1)$$

where  $a_v$  = acceleration addition according to [7.10.6.9](#);  
 $M$  = maximum designed mass of container stack, in t.

**7.10.6.11.2** The loads, in kN, applied at each corner of a container stack, and resulting from heave, pitch, and the ship's rolling motion (i.e. ship in heel condition) shall be determined as follows, (refer also to [Fig. 7.10.6.11](#)):

$$A_z = 9,81 \frac{M}{2} (1 + a_v) (0,45 - 0,42 \frac{h_m}{b}); \quad (7.10.6.11.2-1)$$

$$B_z = 9,81 \frac{M}{2} (1 + a_v) (0,45 + 0,42 \frac{h_m}{b}); \quad (7.10.6.11.2-2)$$

$$B_y = 2,4M \quad (7.10.6.11.2-3)$$

where  $a_v$  = acceleration addition according to [7.10.6.9](#);  
 $M$  = maximum designed mass of container stack, in t;  
 $h_m$  = designed height of centre of gravity of stack above hatch cover top, in m, may be calculated as weighted mean value of the stack, where the centre of gravity of each tier is assumed to be located at the centre of each container,  
 $h_m = \Sigma(z_i \cdot W_i) / M$ ;  
 $z_i$  = distance from hatch cover top to the centre of  $i$ -th container, in m;  
 $W_i$  = weight of  $i$ -th container, in t;  
 $b$  = distance between midpoints of foot points, in m, refer to [Fig. 7.10.6.11](#).  
 $A_z, B_z$  = support forces in  $z$ -direction at the forward and aft stack corners;  
 $B_y$  = support force in  $y$ -direction at the forward and aft stack corners.

When strength of the hatch cover structure is assessed by grillage analysis according to [7.10.6.21](#),  $h_m$  and  $z_i$  shall be taken as shown in [Fig. 7.10.6.11](#). Force  $B_y$  does not need to be considered in this case.

Values of  $A_z$  and  $B_z$  applied for the assessment of hatch cover strength shall be shown in the drawings of the hatch covers.

**Note.** It is recommended that container loads as calculated above are considered as limit for foot point loads of container stacks in the calculations of cargo securing (container lashing).

**7.10.6.12** The load cases defined in [7.10.6.11.1](#) and [7.10.6.11.2](#) shall also be considered for partial non homogeneous loading which may occur in practice, e.g. where specified container stack places are empty. For each hatch cover, the heel directions, as shown in [Table 7.10.6.12](#) shall be considered.







The load case *partial loading of container hatch covers* can be evaluated using a simplified approach, where the hatch cover is loaded without the outermost stacks that are located completely on the hatch cover. If there are additional stacks that are supported partially by the hatch cover and partially by container stanchions then the loads from these stacks shall also be neglected, refer to [Table 7.10.6.12](#).

In addition, the case where only the stack places supported partially by the hatch cover and partially by container stanchions are left empty shall be assessed in order to consider the maximum loads in the vertical hatch cover supports.

It may be necessary also to consider partial load cases where more or different container stack places are left empty.

In the case of mixed stowage (20' + 40' container combined stack), the foot point forces at the fore and aft end of the hatch cover shall not be higher than resulting from the design stack weight for 40' containers, and the foot point forces at the middle of the cover shall not be higher than resulting from the design stack weight for 20' containers.

Table 7.10.6.12

Partial loading of container hatch covers		
Heel direction	←	→
Hatch covers supported by the longitudinal hatch coaming with all container stacks located completely on the hatch cover		
Hatch covers supported by the longitudinal hatch coaming with the outermost container stack supported partially by the hatch cover and partially by container stanchions		
Hatch covers not supported by the longitudinal hatch coaming (center hatch covers)		

**7.10.6.13** Hatch covers, which in addition to the loads according to [7.10.6.6](#), [7.10.6.7](#) and [7.10.6.11](#) are loaded in the ship's transverse direction by forces due to elastic deformations of the ship's hull, shall be designed such that the sum of stresses does not exceed the permissible values given in [7.10.6.14](#).

**7.10.6.14** The equivalent stress  $\sigma_v$  in steel hatch cover structures related to the net thickness shall not exceed  $0,8\sigma_F$ , where  $\sigma_F$  is the minimum yield stress, in  $\text{N/mm}^2$ , of the material. For design loads according to [7.10.6.8 — 7.10.6.13](#), the equivalent stress  $\sigma_v$  related to the net thickness shall not exceed  $0,9\sigma_F$  when the stresses are assessed by means of FEM.

For grillage analysis, the equivalent stress may be taken as follows:

$$\sigma_v = \sqrt{\sigma^2 + 3\tau^2}, \text{ in } \text{N/mm}^2 \quad (7.10.6.14-1)$$

where  $\sigma$  = normal stress, in  $\text{N/mm}^2$ ;  
 $\tau$  = shear stress, in  $\text{N/mm}^2$ .

For FEM calculations, the equivalent stress may be taken as follows:

$$\sigma_v = \sqrt{\sigma_x^2 - \sigma_x\sigma_y + \sigma_y^2 + 3\tau^2}, \text{ in } \text{N/mm}^2 \quad (7.10.6.14-2)$$

where  $\sigma_x$  = normal stress, in  $\text{N/mm}^2$ , in  $x$ -direction;  
 $\sigma_y$  = normal stress, in  $\text{N/mm}^2$ , in  $y$ -direction;  
 $\tau$  = shear stress, in  $\text{N/mm}^2$ , in  $x$ - $y$  plane.

Indices  $x$  and  $y$  are coordinates of a two-dimensional Cartesian system in the plane of the considered structural element.

In case of FEM calculations using shell or plane strain elements, the stresses shall be read from the centre of the individual element. It shall be observed that, in particular, at flanges of unsymmetrical girders, the evaluation of stress from element centre may lead to non-conservative results. Thus, a sufficiently fine mesh shall be applied in these cases or, the stress at the element edges shall not exceed the allowable stress. Where shell elements are used, the stresses shall be evaluated at the mid plane of the element.

**7.10.6.15** The vertical deflection of primary supporting members due to the vertical weather design load according to [7.10.6.6](#) and [7.10.6.7](#) shall not be more than  $0,0056l_g$  where  $l_g$  is the greatest span of primary supporting members.

**Note.** Where hatch covers are arranged for carrying containers and mixed stowage is allowed, i.e. a 40' container stowed on top of two 20' containers, particular attention shall be paid to the deflections of hatch covers. Further the possible contact of deflected hatch covers with in hold cargo shall be observed.

**7.10.6.16** The local net plate thickness  $t$ , in mm, of the hatch cover top plating shall not be less than

$$t = F_p 15,8s \sqrt{\frac{p}{0,95\sigma_F}} \quad (7.10.6.16)$$

and shall not be less than 1 % of the spacing of the stiffener or 6 mm if that be greater

where  $F_p$  = 1,5 in general;  
 $F_p$  =  $1,9 \sigma/\sigma_a$ , for  $\sigma/\sigma_a \geq 0,8$  for the attached plate flange of primary supporting members;  
 $s$  = stiffener spacing, in m;  
 $p$  = pressure  $p_H$  and  $p_L$ , in  $\text{kN/m}^2$ , as defined in [7.10.6.6](#) and [7.10.6.9](#);  
 $\sigma$  = maximum normal stress, in  $\text{N/mm}^2$ , of hatch cover top plating, determined according to [Fig. 7.10.6.16](#);  
 $\sigma_a$  =  $0,8\sigma_F$ , in  $\text{N/mm}^2$ .

For flange plates under compression sufficient buckling strength according to [7.10.6.24](#) shall be demonstrated.




Fig. 7.10.6.16

**7.10.6.17** The thickness of lower plating of double skin hatch covers and box girders shall fulfill the strength requirements and shall be obtained from the calculation according to [7.10.6.21](#) under consideration of permissible stresses according to [7.10.6.14](#). When the lower plating is taken into account as a strength member of the hatch cover, the net thickness, in mm, of lower plating shall be taken not less than 5 mm. When project cargo is intended to be carried on a hatch cover, the net thickness shall not be less than

$$t = 6,5s, \text{ in mm,} \quad (7.10.6.17)$$

where  $s$  = stiffener spacing, in m.

**Note.** Project cargo means especially large or bulky cargo lashed to the hatch cover. Examples are parts of cranes or wind power stations, turbines, etc. Cargoes that can be considered as uniformly distributed over the hatch cover, e.g. timber, pipes or steel coils need not to be considered as project cargo.

**7.10.6.18** The net section modulus  $Z$  and net shear area  $A_s$  of uniformly loaded hatch cover stiffeners constraints at both ends shall not be less than:

$$Z = \frac{104psl^2}{\sigma_F}, \text{ in cm}^3, \quad (7.10.6.18-1)$$

for design load according to [7.10.6.6](#);

$$Z = \frac{94psl^2}{\sigma_F}, \text{ in cm}^3, \quad (7.10.6.18-2)$$

for design load according to [7.10.6.9](#);

$$A_s = \frac{10,8slp}{\sigma_F}, \text{ in cm}^2, \quad (7.10.6.18-3)$$

for design load according to [7.10.6.6](#);

$$A_s = \frac{9,6slp}{\sigma_F}, \text{ in cm}^2, \quad (7.10.6.18-4)$$

for design load according to [7.10.6.9](#);

- where  $l$  = secondary stiffener span, in m, to be taken as the spacing, in m, of primary supporting members or the distance between a primary supporting member and the edge support, as applicable;  
 $s$  = secondary stiffener spacing, in m;  
 $p$  = pressure  $p_H$  and  $p_L$ , in kN/m<sup>2</sup>, as defined in [7.10.6.6](#) and [7.10.6.9](#).

For secondary stiffeners of lower plating of double skin hatch covers, requirements mentioned above are not applied due to the absence of lateral loads.

The net thickness, in mm, of the stiffener (except U-beams/trapeze stiffeners) web shall be taken not less than 4 mm.

The net section modulus of the secondary stiffeners shall be determined based on and attached plate width assumed equal to the stiffener spacing.

For flat bar secondary stiffeners and buckling stiffeners, the ratio  $h/t_w$  shall not be greater than  $15k^{0,5}$ , where  $h$  = height of the stiffener;

$t_w$  = net thickness of the stiffener;

$k = 235/\sigma_F$ .

Stiffeners parallel to primary supporting members and arranged within the effective breadth according to [7.10.6.22](#) shall be continuous at crossing primary supporting member and may be regarded for calculating the cross sectional properties of primary supporting members. It shall be verified that the combined stress of those stiffeners induced by the bending of primary supporting members and lateral pressures does not exceed the permissible stresses according to [7.10.6.14](#). These requirements are not applied to stiffeners of lower plating of double skin hatch covers if the lower plating is not considered as strength member.

For hatch cover stiffeners under compression sufficient safety against lateral and torsional buckling according to [7.10.6.28 — 7.10.6.32](#) shall be verified.

For hatch covers subject to wheel loading or point loads stiffener scantlings shall be determined under consideration of the permissible stresses according to [7.10.6.14](#).

**7.10.6.19** Scantlings of primary supporting members are obtained from calculations according to [7.10.6.22](#) and [7.10.6.23](#) under consideration of permissible stresses according to [7.10.6.14](#).

For all components of primary supporting members sufficient safety against buckling shall be verified according to [7.10.6.24 — 7.10.6.32](#). For biaxial compressed flange plates this shall be verified within the effective widths according to [7.10.6.29](#).

The net thickness, in mm, of webs of primary supporting members shall not be less than:

$$t = 6,5 s, \text{ in mm};$$

$$t_{\min} = 5 \text{ mm}$$

where  $s$  = stiffener spacing, in m.

The net thickness, in mm, of the outer edge girders exposed to wash of sea shall not be less than the largest of the following values:

$$t_{\min} = 5 \text{ mm}$$

where  $p_A$  = horizontal pressure as defined in 7.10.6.8;  
 $s$  = stiffener spacing, in m.

where  $q$  = packing line pressure, in N/mm, minimum 5 N/mm;  
 $s_{SD}$  = spacing, in m, of securing devices.

For flange plates under compression with secondary stiffeners perpendicular to the web of the primary supporting member, the effective width shall be determined according to [7.10.6.29](#).

Table 7.10.6.22

Effective breadth $e_m$ of plating of primary supporting members									
$l/e$	0	1	2	3	4	5	6	7	$\geq 8$
$e_{m1}/e$	0	0,36	0,64	0,82	0,91	0,96	0,98	1,00	1,00
$e_{m2}/e$	0	0,20	0,37	0,52	0,65	0,75	0,84	0,89	0,90

$e_{m1}$  shall be applied where primary supporting members are loaded by uniformly distributed loads or else by not less than 6 equally spaced single loads;  
 $e_{m2}$  shall be applied where primary supporting members are loaded by 3 or less single loads. Intermediate values may be obtained by direct interpolation;  
 $l$  = length of zero-points of bending moment curve;  
 $l = l_0$  for simply supported primary supporting members;  
 $l = 0,6l_0$  for primary supporting members with both ends constraint, where  $l_0$  is the unsupported length of the primary supporting member;  
 $e$  = width of plating supported, measured from centre to centre of the adjacent unsupported fields

**7.10.6.23** For strength calculations of hatch covers by means of finite elements, the cover geometry shall be idealized as realistically as possible. Element size shall be appropriate to account for effective breadth. In no case element width shall be larger than stiffener spacing. In way of force transfer points and cutouts the mesh shall be refined, where applicable. The ratio of element length to width shall not exceed 4.

The element height of webs of primary supporting member shall not exceed one-third of the web height. Stiffeners, supporting plates against pressure loads, shall be included in the idealization. Stiffeners may be modelled by using shell elements, plane stress elements or beam elements. Buckling stiffeners may be disregarded for the stress calculation.

**7.10.6.24** For hatch cover structures sufficient buckling strength shall be demonstrated ([refer to Fig. 7.10.6.24](#)).

Definitions in [7.10.6.24 — 7.10.6.32](#):

$a$  = length of the longer side of a single plate field, in mm ( $x$ -direction);

$b$  = breadth of the shorter side of a single plate field, in mm ( $y$ -direction);

$\alpha$  = aspect ratio of single plate field;  $\alpha = a/b$ ;

$n$  = number of single plate field breadths within the partial or total plate field;

$t$  = net plate thickness, in mm;

$\sigma_x$  = membrane stress, in N/mm<sup>2</sup>, in  $x$ -direction;

$\sigma_y$  = membrane stress, in N/mm<sup>2</sup>, in  $y$ -direction;

$\tau$  = shear stress, in N/mm<sup>2</sup>, in the  $x - y$  plane;

$E$  = modulus of elasticity, in N/mm<sup>2</sup>, of the material;

$E = 2,06 \times 10^5$ , in N/mm<sup>2</sup>, for steel;

$\sigma_F$  = minimum yield stress, in N/mm<sup>2</sup> of the material.

Compressive and shear stresses shall be taken positive, tension stresses shall be taken negative.

Note. If stresses in the  $x$ - and  $y$ -direction already contain the Poisson-effect (calculated using FEM), the following modified stress values may be used. Both stresses  $\sigma_x^*$  and  $\sigma_y^*$  shall be compressive stresses, in order to apply the stress reduction according to the following formulae:

$$\sigma_x = (\sigma_x^* - 0,3\sigma_y^*)/0,91; \quad (7.10.6.24-1)$$

$$\sigma_y = (\sigma_y^* - 0,3\sigma_x^*)/0,91 \quad (7.10.6.24-2)$$

where  $\sigma_x^*, \sigma_y^*$  = stresses containing the Poisson-effect.

Where compressive stress fulfils the condition  $\sigma_y^* < 0,3\sigma_x^*$ , then  $\sigma_y = 0$  and  $\sigma_x = \sigma_x^*$ .

Where compressive stress fulfils the condition  $\sigma_x^* < 0,3\sigma_y^*$ , then  $\sigma_x = 0$  and  $\sigma_y = \sigma_y^*$ ;

$F_1$  = correction factor for boundary condition at the longitudinal stiffeners according to [Table 7.10.6.24](#).

$\sigma_e$  = reference stress, in N/mm<sup>2</sup>, taken equal to

$$\sigma_e = 0,9E(t/b)^2;$$

$\psi$  = edge stress ratio taken equal to

$$\psi = \sigma_2/\sigma_1;$$

$\sigma_1$  = maximum compressive stress;

$\sigma_2$  = minimum compressive stress or tension stress;

$S$  = safety factor (based on net scantling approach), taken equal to:

$S = 1,25$  for hatch covers when subjected to the vertical weather design load according to [7.10.6.6](#);

$S = 1,10$  for hatch covers when subjected to loads according to [7.10.6.8](#) and [7.10.6.14](#);

$\lambda$  = reference degree of slenderness, taken equal to

$$\lambda = \sqrt{\frac{\sigma_F}{K\sigma_e}};$$

$K$  = buckling factor according to [7.10.6.26](#).




Fig. 7.10.6.24  
General arrangement of panel

Table 7.10.6.24

Correction factor  $F_1$

Stiffeners sniped at both ends	1,00
Guidance values <sup>1</sup> where both ends are effectively connected to adjacent structures	1,05 for flat bars
	1,10 for bulb sections
	1,20 for angle and tee-sections
	1,30 for U-type sections <sup>2</sup> and girders of high rigidity
<sup>1</sup> Exact values may be determined by direct calculations. <sup>2</sup> Higher value may be taken if it is verified by a buckling strength check of the partial plate field using non-linear FEA and deemed appropriate by the individual classification society but not greater than 2,0. Note. An average value of $F_1$ shall be used for plate panels having different edge stiffeners.	

**7.10.6.25** Proof shall be provided that the following condition is complied with for the single plate field  $ab$ :

$$\left(\frac{|\sigma_x|S}{k_x\sigma_F}\right)^{e_1} + \left(\frac{|\sigma_y|S}{k_y\sigma_F}\right)^{e_2} - B\left(\frac{\sigma_x\sigma_y S^2}{\sigma_F^2}\right) + \left(\frac{|\tau|S\sqrt{3}}{k_\tau\sigma_F}\right)^{e_3} \leq 1,0.$$

The first two terms and the last term of the above condition shall not exceed 1,0.

The reduction factors  $k_x$ ,  $k_y$  and  $k_\tau$  are given in [Table 7.10.6.26](#).

Where  $\sigma_x \leq 0$  (tension stress),  $k_x = 1,0$ .

Where  $\sigma_y \leq 0$  (tension stress),  $k_y = 1,0$ .

The exponents  $e_1$ ,  $e_2$ ,  $e_3$ , as well as the factor  $B$  shall be taken as given in [Table 7.10.6.25](#).



Table 7.10.6.25




Coefficients  $e_1, e_2, e_3$  and factor  $B$ 



Exponents $e_1, e_2, e_3$ and factor $B$	Plate panel
$e_1$	$1 + k_x^4$
$e_2$	$1 + k_y^4$
$e_3$	$1 + k_x k_y k_t^2$
$B$ $\sigma_x$ and $\sigma_y$ — positive (compression stress)	$(k_x k_y)^5$
$B$ $\sigma_x$ and $\sigma_y$ — negative (tension stress)	1

**7.10.6.26** Buckling and reduction factors for plane elementary plate panels are given in [Table 7.10.6.26](#).

Table 7.10.6.26

## Buckling and reduction factors for plane elementary plate panels

Buckling-load case	Edge stress ratio considering unevenness of plate edge compression	$\alpha = a/b$	Buckling factor $K$ depending on the plate loading and side ratio	Reduction factor $k$
<b>1</b> 	$1 \geq \psi \geq 0$	$\alpha \leq 1$	$K = \frac{8,4}{\psi + 1,1}$	$k_x = 1$ for $\lambda \leq \lambda_c$ $k_x = c (1/\lambda - 0,22/\lambda^2)$ for $\lambda > \lambda_c$ $c = (1,25 - 0,12\psi) \leq 1,25$ $\lambda_c = \frac{c}{2} \left( 1 + \sqrt{1 - \frac{0,88}{c}} \right)$
	$0 > \psi > -1$		$K = 7,63 - \psi(6,26 - 10\psi)$	
	$\psi \leq -1$		$K = (1 - \psi)^2 5,975$	
<b>2</b> 	$1 \geq \psi \geq 0$	$\alpha \leq 1$	$K = F_1 \left( 1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1}{\psi + 1,1}$	$k_y = c \left( \frac{1}{\lambda} - \frac{R + F^2(H - R)}{\lambda^2} \right)$ $c = (1,25 - 0,12\psi) \leq 1,25$ $R = \lambda(1 - \lambda/c)$ for $\lambda < \lambda_c$ $R = 0,22$ for $\lambda \geq \lambda_c$ $\lambda_c = \frac{c}{2} \left( 1 + \sqrt{1 - \frac{0,88}{c}} \right)$ $F = \left( 1 - \frac{K/0,91 - 1}{\lambda_p^2} \right) c_1 \geq 0$ $\lambda_p^2 = \lambda^2 - 0,5$ for $1 \leq \lambda_p \leq 3$ $c_1 = (1 - F_1/\alpha) \geq 0$ $H = \lambda - \frac{2\lambda}{c(T + \sqrt{T^2 - 4})} \geq R$ $T = \lambda + 14/15\lambda + 1/3$
	$0 > \psi > -1$	$1 \leq \alpha \leq 1,5$	$K = F_1 \left( 1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1(1 + \psi)}{1,1} - \frac{\psi}{\alpha^2} (13,9 - 10\psi)$	
		$\alpha > 1,5$	$K = F_1 \left( 1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1(1 + \psi)}{1,1} - \frac{\psi}{\alpha^2} \left( 5,87 + 1,87\alpha^2 + \frac{8,6}{\alpha^2} - 10\psi \right)$	
	$\psi \leq -1$	$1 \leq \alpha \leq \frac{3(1 - \psi)}{4}$	$K = F_1 \left( \frac{1 - \psi}{\alpha} \right)^2 5,975$	
		$\alpha > \frac{3(1 - \psi)}{4}$	$K = F_1 \left[ \left( \frac{1 - \psi}{\alpha} \right)^2 3,9675 + +0,5375 \left( \frac{1 - \psi}{\alpha} \right)^4 + 1,87 \right]$	
	$\psi \leq -1$			
<b>3</b> 	$1 \geq \psi \geq 0$	$\alpha > 0$	$K = \frac{4(0,425 + 1/\alpha^2)}{3\psi + 1}$	$K_x = 1$ for $\lambda \leq 0,7$ $K_x = \frac{1}{\lambda^2 + 0,51}$ for $\lambda > 0,7$
	$0 > \psi \geq -1$		$K = 4 \left( 0,425 + \frac{1}{\alpha^2} \right) (1 + \psi) - 5\psi(1 - 3,42\psi)$	

Buckling-load case	Edge stress ratio considering unevenness of plate edge compression	$\alpha = a/b$	Buckling factor $K$ depending on the plate loading and side ratio	Reduction factor $k$
<b>4</b> 	$1 \geq \psi \geq -1$	$\alpha > 0$	$K = (0,425 + 1/\alpha^2) \frac{3 - \psi}{2}$	
<b>5</b> 	===	$\alpha \geq 1$ $0 < \alpha < 1$	$K = K_\tau \sqrt{3}$ $K_\tau = [5,34 + 4/\alpha^2]$ $K_\tau = [4 + 5,34/\alpha^2]$	$k_\tau = 1$ for $1 \leq 0,84$ $k_\tau = 0,84/\lambda$ for $\lambda > 0,84$
Explanation for boundary conditions: - - - - - plate edge free; ——— plate edge simply supported				

**7.10.6.27** For non-stiffened webs and flanges of primary supporting members not supported by stiffeners, sufficient buckling strength as for the hatch cover top and lower plating shall be demonstrated according to [7.10.6.25](#).

**7.10.6.28** It shall be demonstrated that the continuous longitudinal and transverse stiffeners of partial and total plate fields comply with the conditions set out in [7.10.6.30](#) and [7.10.6.31](#).

For U-type stiffeners, the proof of torsional buckling strength according to [7.10.6.31](#) can be omitted.

Single-side welding is not permitted to use for secondary stiffeners except for U-stiffeners.

**7.10.6.29** For demonstration of buckling strength according to [7.10.6.30](#) and [7.10.6.31](#), the effective width of plating may be determined by the following formulae:

$$b_m = k_x b \text{ for longitudinal stiffeners;} \quad (7.10.6.29-1)$$

$$a_m = k_y a \text{ for transverse stiffeners;} \quad (7.10.6.29-2)$$

refer also to [Fig. 7.10.6.24](#).

The effective width of plating shall not be taken greater than the value obtained from [7.10.6.22](#).

The effective width  $e'_m$  of stiffened flange plates of primary supporting members may be determined as follows:




Fig. 7.10.6.29-1  
Stiffening parallel to web of primary supporting member

$$b < e_m;$$

$$e'_m = nb_m;$$

$n$  = integer number of stiffener spacings  $b$  inside the effective breadth  $e_m$  according to [7.10.6.22](#);

$$n = \text{int}(e_m/b).$$




Fig. 7.10.6.29-2

Stiffening perpendicular to web of primary supporting member

$$a \geq e_m;$$

$$e'_m = na_m < e_m;$$

$$n = 2,7 \frac{e_m}{a} \leq 1;$$

 $e$  = width of plating supported according to [7.10.6.22](#).

 For  $b \geq e_m$  or  $a < e_m$ , respectively,  $b$  and  $a$  shall be exchanged.

 $a_m$  and  $b_m$  for flange plates shall be in general determined for  $\psi = 1$ .

Note. Scantlings of plates and stiffeners shall be in general determined according to the maximum stresses  $\sigma_x(y)$  at webs of primary supporting member and stiffeners, respectively. For stiffeners with spacing  $b$  under compression arranged parallel to primary supporting members, no value less than  $0,25\sigma_F$  shall be inserted for  $\sigma_x(y = b)$ .

The stress distribution between two primary supporting members can be obtained by the following formulae:

$$\sigma_x(y) = \sigma_{x1} \left\{ 1 - \frac{y}{e} [3 + c_1 - 4c_2 - 2\frac{y}{e} (1 + c_1 - 2c_2)] \right\};$$

 where  $c_1 = \sigma_{x2}/\sigma_{x1}$ ;  $0 \leq c_1 \leq 1$ ;

$$c_2 = \frac{1,5}{e} (e''_{m1} + e''_{m2}) - 0,5$$

 $e''_{m1}$  = proportionate effective breadth  $e_{m1}$  or proportionate effective width  $e'_{m1}$  of primary supporting member 1 within the distance  $e$ , as appropriate;

 $e''_{m2}$  = proportionate effective breadth  $e_{m2}$  or proportionate effective width  $e'_{m2}$  of primary supporting member 2 within the distance  $e$ , as appropriate;

 $\sigma_{x1}, \sigma_{x2}$  = normal stresses in flange plates of adjacent primary supporting member 1 and 2 with spacing  $e$ , based on cross-sectional properties considering the effective breadth ( $e_{m1}, e_{m2}$ ) or effective width ( $e'_{m1}, e'_{m2}$ ), as appropriate;

 $y$  = distance of considered location from primary supporting member 1.

Shear stress distribution in the flange plates may be assumed linearly.

**7.10.6.30** Lateral buckling of secondary stiffeners shall be the following:

$$\frac{\sigma_a + \sigma_b}{\sigma_F} S \leq 1 \quad (7.10.6.30)$$

where  $\sigma_a$  = uniformly distributed compressive stress, in N/mm<sup>2</sup>, in the direction of the stiffener axis;  
 $\sigma_a = \sigma_x$  for longitudinal stiffeners;  
 $\sigma_a = \sigma_y$  for transverse stiffeners;  
 $\sigma_b$  = bending stress, in N/mm<sup>2</sup>, in the stiffener  

$$\sigma_b = \frac{M_0 + M_1}{Z_{st} 10^3}$$
 $M_0$  = bending moment, in N·mm, due to the deformation  $w$  of stiffener, taken equal to  
 $M_0 = F_{Ki} \frac{p_z w}{c_f - p_z}$  with  $(c_f - p_z) > 0$ ;  
 $M_1$  = bending moment, in N·mm, due to the lateral load  $p$  equal to:  
 $M_1 = \frac{p b a^2}{24 \times 10^3}$  for longitudinal stiffeners;  
 $M_1 = \frac{p a (n b)^2}{c_s 8 \times 10^3}$  for transverse stiffeners;  
 $n$  shall be equal to  $l$  for ordinary transverse stiffeners;  
 $p$  = lateral load, in N/mm<sup>2</sup>;  
 $F_{Ki}$  = ideal buckling force, in N, of the stiffener;  
 $F_{Kix} = \frac{\pi^2}{a^2} E I_x \times 10^4$  for longitudinal stiffeners;  
 $F_{Kiy} = \frac{\pi^2}{(n b)^2} E I_y \times 10^4$  for transverse stiffeners;  
 $I_x, I_y$  = net moments of inertia, in cm<sup>4</sup>, of the longitudinal or transverse stiffener, including effective width of attached plating according to 7.10.6.29.  $I_x$  and  $I_y$  shall comply with the following criteria:  

$$I_x \geq \frac{b t^3}{12 \times 10^4};$$

$$I_y \geq \frac{a t^3}{12 \times 10^4};$$
 $p_z$  = nominal lateral load, in N/mm<sup>2</sup>, of the stiffener due to  $\sigma_x, \sigma_y$  and  $\tau$ ;  

$$p_{zx} = \frac{t}{b} \left( \sigma_{xl} \left( \frac{\pi b}{a} \right)^2 + 2 c_y \sigma_y + \sqrt{2 \tau_1} \right)$$
 for longitudinal stiffeners;  

$$p_{zy} = t \left( 2 c_x \sigma_{xl} + \sigma_y \left( \frac{\pi a}{n b} \right)^2 \left( 1 + \frac{A_y}{a t} \right) + \sqrt{2 \tau_1} \right)$$
 for transverse stiffeners;  
 $\sigma_{xl} = \sigma_x \left( 1 + \frac{A_x}{b t} \right);$   
 $c_x, c_y$  = factors taking into account the stresses perpendicular to the stiffener's axis and distributed variable along the stiffener's length;  
 $c_x, c_y = 0,5(1 + \psi)$  for  $0 \leq \psi \leq 1$ ;  
 $c_x, c_y = \frac{0,5}{1 - \psi}$  for  $\psi < 0$ ;  
 $A_x, A_y$  = net sectional area, in mm<sup>2</sup>, of the longitudinal or transverse stiffener, respectively, without attached plating;  

$$\tau_1 = [\tau - t \sqrt{\sigma_F E (m_1/a^2 + m_2/b^2)}] \geq 0;$$
 for longitudinal stiffeners:  
 $a/b \geq 2,0: m_1 = 1,47 \quad m_2 = 0,49;$   
 $a/b < 2,0: m_1 = 1,96 \quad m_2 = 0,37;$   
 for transverse stiffeners:  
 $a/nb \geq 0,5: m_1 = 0,37 \quad m_2 = 1,96/n^2;$   
 $a/nb < 0,5: m_1 = 0,49 \quad m_2 = 1,47/n^2;$   
 $w = w_0 + w_1;$   
 $w_0$  = assumed imperfection, in mm;  
 $w_{0x} \leq \min(a/250, b/250, 10)$  for longitudinal stiffeners;  
 $w_{0y} \leq \min(a/250, nb/250, 10)$  for transverse stiffeners.

Note. For stiffeners sniped at both ends  $w_0$  shall not be taken less than the distance from the midpoint of plating to the neutral axis of the profile including effective width of plating;

$w_1$  = deformation of stiffener, in mm, at midpoint of stiffener span due to lateral (transverse) load  $p$ .  
 In case of uniformly distributed load the following values for  $w_1$  may be used:

$$w_1 = \frac{pba^4}{384 \times 10^7 EI_x} \text{ for longitudinal stiffeners;}$$

$$w_1 = \frac{5ap(nb)^4}{384 \times 10^7 EI_y c_s^2} \text{ for transverse stiffeners;}$$

$$c_f = \text{elastic support provided by the stiffener, in N/mm}^2.$$

For longitudinal stiffeners:

$$c_{fx} = F_{Kix} \frac{\pi^2}{a^2} (1 + c_{px});$$

$$c_{px} = \frac{1}{1 + \frac{0,91 \left( \frac{12 \times 10^4 I_{x1}}{t^3 b} - 1 \right)}{c_{xa}}};$$

$$c_{xa} = [a/2b + 2b/a]^2 \text{ for } a \geq 2b;$$

$$c_{xa} = [1 + (a/2b)^2]^2 \text{ for } a < 2b.$$

For transverse stiffeners:

$$c_{fy} = c_s F_{Kiy} \frac{\pi^2}{(nb)^2} (1 + c_{py});$$

$$c_{py} = \frac{1}{1 + \frac{0,91 \left( \frac{12 \times 10^4 I_{y1}}{t^3 a} - 1 \right)}{c_{ya}}};$$

$$c_{ya} = [nb/2a + 2a/nb]^2 \text{ for } nb \geq 2a;$$

$$c_{ya} = [1 + (nb/2a)^2]^2 \text{ for } nb < 2a$$

where  $c_s$  = factor accounting for the boundary conditions of the transverse stiffener;

$c_s$  = 1,0 for simply supported stiffeners;

$c_s$  = 2,0 for partially constraint stiffeners;

$Z_{st}$  = net section modulus of stiffener (longitudinal or transverse), in  $\text{cm}^3$ , including effective width of plating according to [7.10.6.29](#).

If no lateral load  $p$  is acting, the bending stress  $\sigma_b$  shall be calculated at the midpoint of the stiffener span for that fibre, which results in the largest stress value. If a lateral load  $p$  is acting, the stress calculation shall be carried out for both fibres of the stiffener's cross sectional area (if necessary for the biaxial stress field at the plating side).

**7.10.6.31** The longitudinal secondary stiffeners shall comply with the following criteria:

$$\frac{\sigma_x S}{k_T \sigma_F} \leq 1,0 \quad (7.10.6.31)$$

where  $k_T$  = coefficient taken equal to:

$k_T$  = 1,0 for  $\lambda_T \leq 0,2$ ;

$k_T = \frac{1}{\Phi + \sqrt{\Phi^2 - \lambda_T^2}}$  for  $\lambda_T > 0,2$ ;

$\Phi = 0,5(1 + 0,21(\lambda_T - 0,2) + \lambda_T^2)$ ;

$\lambda_T$  = reference degree of slenderness taken equal to

$$\lambda_T = \sqrt{\sigma_F / \sigma_{KI T}};$$

$$\sigma_{KI T} = \frac{E}{I_p} \left( \frac{\pi^2 I_{\omega} \times 10^2}{a^2} \varepsilon + 0,385 I_T \right), \text{ in N/mm}^2;$$

for  $I_p, I_T, I_{\omega}$ , refer to [Fig. 7.10.6.31](#) and [Table 7.10.6.31](#).

$I_p$  = net polar moment of inertia of the stiffener, in  $\text{cm}^4$ , related to the point C;

$I_T$  = net St. Venant's moment of inertia of the stiffener, in  $\text{cm}^4$ ;

$I_{\omega}$  = net sectorial moment of inertia of the stiffener, in  $\text{cm}^6$ , related to the point C;

$\varepsilon$  = degree of fixation taken equal to

$$\varepsilon = 1 + 10^{-3} \sqrt{\frac{a^4}{\frac{3}{4} \pi^4 I_{\omega} (b/t^3 + 4h_w/3t_w^3)}},$$

$h_w$  = web height, in mm;

$t_w$  = net web thickness, in mm;

$b_f$  = flange breadth, in mm;

$t_f$  = net flange thickness, in mm;

$A_w$  = net web area equal to  $A_w = h_w t_w$ ;

$A_f$  = net flange area equal to  $A_f = b_f t_f$ ;

$e_f = h_w + t_f/2$ , in mm.




Fig. 7.10.6.31  
Dimensions of stiffener

Table 7.10.6.31

### Moments of inertia

Section	$I_p$	$I_T$	$I_{\omega}$
Flat bar	$\frac{h_w^3 t_w}{3 \times 10^4}$	$\frac{h_w^3 t_w}{3 \times 10^4} \left( 1 - 0,63 \frac{t_w}{h_w} \right)$	$\frac{h_w^3 t_w}{36 \times 10^6}$
Sections with bulb or flange	$\left( \frac{A_w h_w^2}{3} + A_f e_f^2 \right) 10^{-4}$	$\frac{h_w t_w^3}{3 \times 10^4} (1 - 0,63 t_w / h_w) + \frac{b_f t_f^3}{3 \times 10^4} (1 - 0,63 t_f / b_f)$	for bulb and angle sections: $\frac{A_f e_f^2 b_f^2}{12 \times 10^6} \left( \frac{A_f + 2,6 A_w}{A_f + A_w} \right)$ for tee-sections: $\frac{b_f^3 t_f e_f^2}{12 \times 10^6}$

**7.10.6.32** For transverse secondary stiffeners loaded by compressive stresses, which are not supported by longitudinal stiffeners, sufficient torsional buckling strength shall be demonstrated according to [7.10.6.31](#).

**7.10.6.33** Securing and arrangement of containers on the hatch covers shall comply with the technical requirements for the arrangement and securing of the international standard containers on board the ships intended for container transportation. Structures under

container load shall be calculated according to [7.10.6.5 — 7.10.6.13](#) using the permissible stresses as per [7.10.6.14](#).

**7.10.6.34** To ensure weather tightness, the requirements of [7.10.6.45 — 7.10.6.51](#) applicable to hatch covers shall be met.

The packing material of hatch covers gaskets shall be suitable for all expected service conditions of the ship and shall be compatible with the cargoes to be transported. The packing material shall be selected with regard to dimensions and elasticity in such a way that expected deformations can be carried. Forces shall be carried by the steel structure only.

The packings shall be compressed so as to give the necessary tightness effect for all expected operating conditions. Special consideration shall be given to the packing arrangement in ships with large relative movements between hatch covers and coamings or between hatch cover sections.

**7.10.6.35** For hatch covers of cargo holds solely for the transport of containers, at the shipowner's request and subject to compliance with the following conditions, the fitting of weather tight gaskets mentioned in [7.10.6.34](#) may be dispensed with:

the hatchway coamings shall be not less than 600 mm in height;

the exposed deck, on which the hatch covers are located is situated above a depth  $H(x)$ .

$H(x)$  shall be shown to comply with the following criteria:

$$H(x) \geq T_{fb} + f_b + h, \text{ in m} \quad (7.10.6.35)$$

where  $T_{fb}$  = draught, in m, corresponding to the assigned summer load line;

$f_b$  = minimum required freeboard, in m, determined in accordance with regulation 28 of the International Load Line Convention, as amended, where applicable;

$h = 4,6$  for  $x/L_{LL} \leq 0,75$ ;

$h = 6,9$  for  $x/L_{LL} > 0,75$ .

Labyrinths, gutter bars or equivalents shall be fitted proximate to the edges of each panel in way of the coamings. The clear profile of these openings shall be kept as small as possible.

Where a hatch is covered by several hatch cover panels, the clear opening of the gap in between the panels shall be not wider than 50 mm.

The labyrinths and gaps between hatch cover panels shall be considered as unprotected openings with respect to the requirements of intact and damage stability calculations.

Bilge alarms shall be provided in each hold fitted with non-weather-tight covers.

Furthermore, Chapter 3 of IMO circular MSC/Circ. 1087 shall be referred to concerning the stowage and segregation of containers containing dangerous goods.

**7.10.6.36** Cross-joints of multi-panel covers shall be provided with efficient drainage arrangements.

**7.10.6.37** The net thickness of weather deck hatch coamings shall not be less than that determined by the following formulae:

$$t = 14,2s \sqrt{\frac{p_A}{0,95\sigma_F}}, \text{ in mm;} \quad (7.10.6.37-1)$$

$$t_{\min} = 6 + L_1/100, \text{ in mm} \quad (7.10.6.37-2)$$

where  $s$  = stiffener spacing, in m;

$L_1 = L$ , need not be taken greater than 300 m.



Strength aspects of longitudinal hatch coamings shall meet the requirements of 1.6.5 of Part II "Hull".

**7.10.6.38** The stiffeners shall be continuous at the coaming stays. For stiffeners with both ends constraint, the elastic net section modulus  $Z$ , in  $\text{cm}^3$ , and net shear area  $A_s$ , in  $\text{cm}^2$ , calculated on the basis of net thickness, shall not be less than:

$$Z = \frac{83}{\sigma_F} s l^2 p_A; \quad (7.10.6.38-1)$$

$$A_s = \frac{10 s l p_A}{\sigma_F} \quad (7.10.6.38-2)$$

where  $l$  = secondary stiffener span, in m, to be taken as the spacing of coaming stays;  
 $s$  = stiffener spacing, in m.

For sniped stiffeners at coaming corners section modulus and shear area at the fixed support shall be increased by 35 %. The thickness of the coaming plate at the sniped stiffener end shall not be less than those defined as per the formula

$$t = 19,6 \sqrt{\frac{p_A s (l - 0,5s)}{\sigma_F}}, \text{ in mm.} \quad (7.10.6.38-3)$$

Horizontal stiffeners on hatch coamings, which are part of the longitudinal hull structure, shall be designed according to the requirements in 1.6.5 of Part II "Hull".

**7.10.6.39** Coaming stays shall be designed for the loads transmitted through them and permissible stresses according to [7.10.6.14](#).

At the connection of the coaming stays with deck (refer to Figs. 7.1.6.39-1 and 7.1.6.39-2), the net section modulus  $Z$ , in  $\text{cm}^3$ , shall be taken not less than

$$Z = \frac{526}{\sigma_F} e h_s^2 p_A, \text{ in cm}^3 \quad (7.10.6.39)$$

where  $e$  = spacing of coaming stays, in m;  
 $h_s$  = height of coaming stays, in m.

For other designs of coaming stays, such as those shown in [Figs. 7.10.6.39-3](#) and [7.10.6.39-4](#), the stresses shall be determined through a grillage analysis or FEM. The calculated stresses shall comply with the permissible stresses according to [7.10.6.14](#).

Coaming stays shall be supported by appropriate substructures. Face plates may only be included in the calculation if an appropriate substructure is provided and welding provides an adequate joint.




Fig. 7.10.6.39-1




Fig. 7.10.6.39-2




Fig. 7.10.6.39-3




Fig. 7.10.6.39-4

**7.10.6.40** Web gross thickness at the root point shall not be less than

$$t_w = \frac{2}{\sigma_F} \frac{e h_s p_A}{h_w} + t_s \quad (7.10.6.40)$$

where  $h_w$  = web height of coaming stay at its lower end, in m;  
 $t_s$  = corrosion addition, in mm, according to [7.10.6.52](#).

Coaming stays shall be connected to the deck by fillet welds on both sides with a throat thickness of  $a = 0,44t_w$ .

**7.10.6.41** Hatch coamings which are part of the longitudinal hull structure shall be designed according to the requirements of 1.6.5 of Part II "Hull".

Longitudinal hatch coamings with a length exceeding  $0,1L$  shall be provided with tapered brackets or equivalent transitions and a corresponding substructure at both ends. At the end of the brackets they shall be connected to the deck by full penetration welds of minimum 300 mm in length.

**7.10.6.42** Hatch coamings and supporting structures shall be adequately stiffened to accommodate the loading from hatch covers, in longitudinal, transverse and vertical directions. Structures under deck shall be checked against the load transmitted by the stays.

Structures under deck shall be checked against the load transmitted by the stays.

Unless otherwise stated, weld connections shall be dimensioned according to 1.7 of Part II "Hull" and materials shall be selected according to 2.2 of Part XIV "Welding".

**7.10.6.43** On ships carrying cargo on deck, such as timber, coal or coke, the stays shall be spaced not more than 1,5 m apart.

Coaming plates shall extend to the lower edge of the deck beams or hatch side girders shall be fitted that extend to the lower edge of the deck beams. Extended coaming plates and hatch side girders shall be flanged or fitted with face bars or half-round bars. [Fig. 7.10.6.43](#) gives an example.




Fig. 7.10.6.43

**7.10.6.44** If drain channels are provided inside the line of gasket by means of a gutter bar or vertical extension of the hatch side and end coaming, drain openings shall be provided at appropriate positions of the drain channels.

Drain openings in hatch coamings shall be arranged with sufficient distance to areas of stress concentration (e.g. hatch corners, transitions to crane posts).

Drain openings shall be arranged at the ends of drain channels and shall be provided with non-return valves to prevent ingress of water from outside. It is unacceptable to connect fire hoses to the drain openings for this purpose.

If a continuous outer steel contact between cover and ship structure is arranged, drainage from the space between the steel contact and the gasket shall be also provided.

**7.10.6.45** Securing devices between cover and coaming and at cross-joints shall be installed to provide weathertightness.

Securing devices shall be appropriate to bridge displacements between cover and coaming due to hull deformations. These devices shall be of reliable construction and effectively attached to the hatchway coamings, decks or covers. Individual securing devices on each cover shall have approximately the same stiffness characteristics.

Sufficient number of securing devices shall be provided at each side of the hatch cover considering the requirements of [7.10.6.20](#); this applies also to hatch covers consisting of several parts.

**7.10.6.46** Where rod cleats are fitted, resilient washers or cushions shall be incorporated.

Where hydraulic cleating is adopted, positive means shall be provided so that it remains mechanically locked in the closed position in the event of failure of the hydraulic system.

**7.10.6.47** The gross sectional area, in cm<sup>2</sup>, shall not be less than that defined by the formula

$$A = 0,28q s_{SD} k_l \quad (7.10.6.47)$$

where  $q$  = packing line pressure, in N/mm, minimum 5 N/mm;  
 $s_{SD}$  = spacing between securing devices, in m, but not less than 2 m;  
 $k_l = (235/\sigma_F)^e$ ;  
 $\sigma_F$  = minimum yield strength of the material, in N/mm<sup>2</sup>, but not greater than  $0,7\sigma_m$ , where  $\sigma_m$  is the tensile strength of the material, in N/mm<sup>2</sup>.  
 $e = 0,75$  for  $\sigma_F > 235$  N/mm<sup>2</sup>;  
 $e = 1,00$  for  $\sigma_F \leq 235$  N/mm<sup>2</sup>.

For hatchways exceeding 5 m<sup>2</sup>, rods and bolts shall have a gross diameter no less than 19 mm.

Securing devices of special design in which significant bending or shear stresses occur may be designed as anti-lifting devices according to [7.10.6.48](#). As load the packing line pressure  $q$  multiplied by the spacing between securing devices  $s_{SD}$  shall be applied.

**7.10.6.48** The securing devices of hatch covers, on which cargo is lashed, shall be designed for the lifting forces resulting from loads according to [7.10.6.11 — 7.10.6.13](#), refer to [Fig. 7.10.6.48](#). Unsymmetrical loadings, which may occur in practice, shall be considered. Under these loadings the equivalent stress in the securing devices shall not exceed

$$\sigma_V = 150/k_l, \text{ in N/mm}^2. \quad (7.10.6.48)$$

Note. The partial load cases given in [Table 7.10.6.12](#) may not cover all unsymmetrical loadings, critical for hatch cover lifting.

Chapter 5.6 of IACS recommendation No. 14 (Rev.2 July 2005 Corr.1 Oct 2005) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)) shall be referred to for the omission of anti-lifting devices.




Fig. 7.10.6.48  
Lifting forces at a hatch cover

**7.10.6.49** For the design of the hatch cover supports, the horizontal mass forces  $F_h = ma$  shall be calculated with the following accelerations:

$a_x = 0,2g$  in longitudinal direction;

$a_y = 0,5g$  in transverse direction;

$m$  = sum of mass of cargo lashed on the hatch cover and mass of hatch cover.

The accelerations in longitudinal direction and in transverse direction do not need to be considered as acting simultaneously.

**7.10.6.50** For the transmission of the support forces resulting from the load cases specified in [7.10.6.5 — 7.10.6.13](#) and of the horizontal mass forces specified in [7.10.6.49](#), supports shall be provided which shall be designed such that the nominal surface pressures in general do not exceed the following values:

$$p_{n\max} = dp_n, \text{ in N/mm}^2 \quad (7.10.6.50-1)$$

where  $d = 3,75 - 0,015L$ ;

$d_{\max} = 3,0$ ;

$d_{\min} = 1,0$  in general;

$d_{\min} = 2,0$  for partial loading conditions, refer to [7.10.6.12](#);

$p_n$  = refer to [Table 7.10.6.50](#).

For metallic supporting surfaces not subjected to relative displacements, the nominal surface pressure shall be calculated by the formula

$$p_{n\max} = 3p_n, \text{ in N/mm}^2. \quad (7.10.6.50-2)$$

Where large relative displacements of the supporting surfaces are expected, the use of material having low wear and frictional properties is recommended.

The substructures of the supports shall be of such a design, that a uniform pressure distribution is achieved.

Irrespective of the arrangement of stoppers, the supports shall be able to transmit the following force  $P_h$  in the longitudinal and transverse directions:

$$P_h = \mu \frac{P_V}{\sqrt{d}}, \quad (7.10.6.50-3)$$

where  $P_V$  = vertical supporting force;  
 $\mu$  = frictional coefficient, in general equal to 0,5.

For non-metallic, low-friction support materials on steel, the friction coefficient may be reduced but not to be less than 0,35.

Supports as well as the adjacent structures and substructures shall be designed such that the permissible stresses according to [7.10.6.14](#) are not exceeded.

Table 7.10.6.50

**Permissible nominal surface pressure  $p_n$** 

Support material	$p_n$ , in N/mm <sup>2</sup> , when loaded by	
	vertical force	horizontal force (on stoppers)
Hull structural steel	25	40
Hardened steel	35	50
Lower friction materials	50	—

**7.10.6.51** Hatch covers shall be sufficiently secured against horizontal shifting. Stoppers shall be provided for hatch covers, on which cargo is carried.

The greater of the loads resulting from [7.10.6.8](#) and [7.10.6.49](#) shall be applied for the dimensioning of the stoppers and their substructures.

The permissible stress in stoppers, their substructures, in the cover, and of the coamings shall be determined according to [7.10.6.14](#); in addition, the provisions in [7.10.6.50](#) shall be observed.

**7.10.6.52** Corrosion additions (corrosion allowance)  $t_s$ , in mm, for hatch covers and hatch coamings are given in [Table 7.10.6.52](#).

Table 7.10.6.52

**Corrosion additions  $t_s$  for hatch covers and hatch coamings**

Application	Structure	$t_s$ , in mm
Weather deck hatches of container ships, car carriers, paper carriers, passenger vessels	Hatch covers	1,0
	Hatch coamings	According to 1.1.5.1 of Part II "Hull"
Weather deck hatches of all other ship types	Hatch covers in general	2,0
	Weather exposed plating and bottom plating of double skin hatch covers	1,5
	Internal structure of double skin hatch covers and closed box girders (hollow beams)	1,0
	Hatch coamings not part of the longitudinal hull structures	1,5

Application	Structure	$t_s$ , in mm
	Hatch coamings part of the longitudinal hull structures	According to 1.1.5.1, Part II "Hull"
	Coaming stays and stiffeners	1,5

**7.10.6.53** Steel renewal is required where the gauged thickness is less than  $t_{net} + 0,5$  mm for:

single skin hatch covers;

the plating of double skin hatch covers, and

coaming structures the corrosion additions  $t_s$  of which are provided in [Table 7.10.6.52](#).

Where the gauged thickness is within the range  $t_{net} + 0,5$  mm and  $t_{net} + 1,0$  mm, coating (applied in accordance with the coating manufacturer's requirements) or annual gauging may be adopted as an alternative to steel renewal. Coating shall be maintained in GOOD condition, as defined in Chapter 1.2 of IACS UR Z10.2 (Rev.36 May 2019) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)).

For the internal structure of double skin hatch covers, thickness gauging is required when hatch cover top or bottom plating renewal shall be carried out or when this is deemed necessary, at the discretion of the surveyor to the Register, on the basis of the plating corrosion or deformation condition. In these cases, steel renewal for the internal structures is required where the gauged thickness is less than  $t_{net}$ .

For corrosion addition  $t_s = 1,0$  mm, the thickness for steel renewal is  $t_{net}$  and the thickness for coating or annual gauging is when gauged thickness is between  $t_{net}$  and  $t_{net} + 0,5$  mm.

For coaming structures, the corrosion additions  $t_s$  of which are not provided in [Table 7.10.6.52](#) shall be in compliance with the requirements of 1.1.5 of Part II "Hull".

**7.11 HATCHWAYS OF CARGO TANKS IN TYPE "A" SHIPS, OIL TANKERS, OIL TANKERS (>60 °C), OIL RECOVERY SHIPS AND OIL RECOVERY SHIPS (>60 °C)**

**7.11.1** Height of the coamings of cargo tank hatchways intended for the carriage liquid cargoes is not regulated by the Register. Construction of the coamings of cargo tank hatchways shall comply with the requirements of 3.5.5.1 of Part II "Hull".

**7.11.2** Covers of hatches and tank cleaning openings shall be made of steel, bronze or brass.

**7.11.3** Covers of the cargo tank hatchways shall be permanently attached or fixed with closely spaced bolts and tight, when secured, under the inner pressure of liquid carried in tanks to a head of not less than 2,5 m. Tightness shall be provided by a rubber or other suitable gasket being resistant to the liquids which are carried in the cargo tanks.



## 7.12 OPENINGS IN WATERTIGHT SUBDIVISION BULKHEADS AND THEIR CLOSING APPLIANCES

### 7.12.1 General.

**7.12.1.1** Unless expressly provided otherwise, this Chapter covers ships to which the requirements of Part V "Subdivision" apply.

For other ships, the requirements of this Chapter apply to bulkheads which installation is covered by 2.7.1.3 of Part II "Hull"; for these ships, the requirements may be relaxed provided the analysis confirming safety of the ship has been submitted.

In ships indicated in [7.12.6.1](#), the requirements of [7.12.2 — 7.12.5](#) may be relaxed for doors fitted in watertight subdivision bulkheads dividing a cargo space from an adjoining cargo space provided the requirements of [7.12.6](#) are met.

Doors and closing appliances in watertight bulkheads of fishing vessels shall comply with the requirements of [7.12.8](#).

**7.12.1.2** The number of openings in watertight bulkheads shall be reduced to a minimum compatible with the design and normal service conditions of the ship.

**7.12.1.3** Where piping and electric cables are carried through watertight subdivision bulkheads, the requirements of 5.1 of Part VIII "Systems and Piping" and of 16.8.6 of Part XI "Electrical Equipment" shall be taken into consideration.

### 7.12.2 Doors in watertight subdivision bulkheads. General.

**7.12.2.1** The doors shall be made of steel. The use of other materials may be allowed provided it is confirmed by calculations and tests that they have a strength at least equivalent to that of the doors made of steel.

**7.12.2.2** Doors shall withstand the pressure of a water head of the height measured from the lower edge of a doorway at the place of its location to the underside of bulkhead deck plating, the freeboard or the most adverse damage waterline, whichever is greater.

**7.12.2.3** Under the effect of water head specified in [7.12.2.2](#), the stresses in the door frame and door plate shall not exceed 0,6 times the upper yield stress of their material.

**7.12.2.4** When closed, the doors shall be tight under the pressure of a water head of the height specified in [7.12.2.2](#).

**7.12.2.5** Each means of operation of the doors shall alone ensure closure of the door with the ship listed 15° either way and with a trim up to 5°. Doors closed by dropping or by the effect of a dropping weight are not permitted. Portable plates secured by bolts only are not permitted.

**7.12.2.6** Signboard/instructions shall be placed in way of the door advising how to act when the door is in "doors closed" mode.

**7.12.2.7** The central operating console at the navigation bridge shall be provided with a diagram showing the location of each door, with visual indicators to show whether each door is open or closed. A red light shall indicate a door fully open and a green light shall indicate a door fully closed. When a door is closed remotely, the red light shall indicate the intermediate position by flashing. The indicating circuit shall be independent of the control circuit for each door. It shall not be possible to remotely open any door from the central operating console.

This applies to passenger ships and cargo ships.

**7.12.2.8** For passenger ships, failure of the normal power supply of the required alarms shall be indicated by an audible and visual alarm at the central operating console at the navigation bridge. For cargo ships, failure of the normal power supply of the required alarms shall be indicated by an audible and visual alarm at the navigation bridge.

**7.12.2.9** All watertight doors, including sliding doors, operated by hydraulic door actuators, either a central hydraulic unit or an independent hydraulic unit for each door shall

be provided with a low fluid level alarm or low gas pressure alarm, as applicable or some other means of monitoring loss of stored energy in the hydraulic accumulators. For passenger ships, this alarm shall be both audible and visible and shall be located on the central operating console at the navigation bridge. For cargo ships, this alarm shall be both audible and visible and should be located at the navigation bridge.

**7.12.3 Regulations concerning the positioning of doors.**

**7.12.3.1** No doors are permitted in:

collision bulkhead below the bulkhead deck of ships having a subdivision distinguishing mark in the class notation and below the freeboard deck of all other ships;

watertight subdivision bulkheads dividing a cargo space from an adjoining cargo space except where the Register is satisfied that such doors are essential. In this case, the doors may be hinged, sliding or of another equivalent type, but they shall not be remotely controlled.

In passenger ships and special purpose ships, as well as in ships with subdivision distinguishing mark in the class notation, the outboard vertical edges of the doors shall not be located at less than 0,2 of the ship breadth. This distance shall be measured at right angles to the centreline of the ship at the level of the deepest subdivision loadline.

**7.12.3.2** In addition to doors at entrances to propeller shaft tunnels, not more than one door may be provided in each watertight subdivision bulkhead within spaces containing main engines, boilers and auxiliary machinery.

Where two or more propeller shafts are fitted, their tunnels shall be connected by a passageway. In a twin-screw ship, there shall only be one door between the engine room and tunnel spaces, and if the propellers are more than two, only two doors shall be provided. All the doors shall be located as high as practicable.

Hand gear for operating the doors from above the bulkhead deck and for operating doors at entrances to shaft tunnels shall be fitted outside the engine room.

**7.12.4 Doors in cargo ships.**

**7.12.4.1** The requirements of [7.12.4](#) apply to doors fitted in the subdivision bulkheads of cargo ships except the doors of special purpose ships and those mentioned under [7.12.6](#).

**7.12.4.2** Doors provided to ensure the watertight integrity of internal openings which are used while at sea shall be sliding doors with horizontal or vertical motion, they shall be both hand and power-operated.

Access doors and access hatch covers normally closed at sea, intended to ensure the watertight integrity of internal openings, shall be provided with means of indication locally and on the bridge showing whether these doors or hatch covers are open or closed. A notice shall be affixed to each such door or hatch cover to the effect that it shall not be left open.

If hand-operated, it shall be possible to open and close the door from both sides of the bulkhead with the ship listed 30°.

If power-operated, closing of the doors from the control station on the navigation bridge shall be possible.

**7.12.4.3** At the door control stations, visual indicators shall be provided to show whether the doors are open or closed. An alarm shall be provided to control the door closing.

Power source, control station and indicators shall be operable in the case of main power source failure. Special attention shall be paid to minimizing the effects of the control system failure.

**7.12.4.4** For tankers, where there is a permanent access from a pipe tunnel to the main pump room, the watertight door shall be capable of being manually closed from outside the main pump room entrance.

**7.12.5 Doors in passenger ships and special purpose ships.**

**7.12.5.1** The requirements of [7.12.5](#) apply to doors fitted in the subdivision bulkheads of passenger ships and special purpose ships except those mentioned in [7.12.6](#).

**7.12.5.2** The doors shall be sliding doors with horizontal or vertical motion, they shall be both hand- and power-operated.

The maximum width of the door aperture shall not exceed 1,2 m. Installation of doors with the aperture width in excess of 1,2 m shall be substantiated by calculations confirming their equivalent strength to the bulkhead in which they are fitted.

**7.12.5.3** If the door is hand-operated, it shall be possible to manually open and close the door from both sides in the close proximity of the door and, in addition, close the door from an accessible place above the bulkhead deck by means of a hand wheel, handle or any other similar gear ensuring the same degree of safety. The force applied to the hand wheel, handle or similar gear while the door is in motion shall not exceed 157 N.

If the door is not visible from the position above the bulkhead deck where the gear is fitted, indicators shall be provided showing the positions of the hand wheel, handle and similar gear at which the door is open or closed.

When hand-operated, the time necessary for a complete closure of the door shall not exceed 90 s with the ship upright.

The angle of list at which operation by hand shall be possible is 15°.

**7.12.5.4** Door control knobs shall be fitted on either side of the bulkhead at a minimum height of 1,6 m above deck plating and so arranged as to enable persons passing through the doorway to hold both the knobs in a position preventing door closure. The direction of movement of the handles in opening and closing the door shall be in the direction of door movement and shall be clearly indicated.

**7.12.5.5** The power gear shall be controllable (i.e. door opening and closing shall be possible) by local control stations on either side of the bulkhead.

Besides being controlled directly at the door, the power gear shall also be controllable (for door closure) from the main control station.

Remote opening of any door from the main control station shall not be possible.

The main control station for doors shall be located in the wheelhouse.

**7.12.5.6** The power gear shall ensure door closure in not more than 40 s and not less than 20 s with the ship upright, as well as a simultaneous closure of all doors within not more than 60 s.

**7.12.5.7** The power gear of the doors shall have either:

a centralized hydraulic system with two independent power sources each consisting of a motor and pump capable of simultaneously closing all doors. In addition, there shall be for the whole installation hydraulic accumulators of sufficient capacity to operate all the doors at least three times, i.e. closed – open – closed at unfavourable conditions of heel up to 15°; or

an independent hydraulic system for each door with each power source consisting of a motor and pump capable of opening and closing the door. In addition, there shall be a hydraulic accumulator of sufficient capacity to operate the door at least three times, i.e. closed – open – closed at unfavourable conditions of heel up to 15°; or

an independent electrical system and motor for each door with each power source consisting of a motor capable of opening and closing the door. The power source shall be capable of being automatically supplied by a transitional emergency source of electrical power, as required by 19.1.2.7 of Part XI "Electrical Equipment" in the event of failure of either the main or emergency source of electrical power and with sufficient capacity to operate the door at least three times, i.e. closed – open – closed at unfavourable conditions of heel up to 15°.

**7.12.5.8** Door controls, including hydraulic piping and electric cables, shall be kept as close as practicable to the bulkhead in which the doors are fitted, in order to minimize the likelihood of them being involved in any damage which the ship may sustain.

**7.12.5.9** Each door shall be provided with an audible alarm, distinct from any other alarm in the area, which will sound whenever the door is closed remotely by power and which shall sound for at least five seconds, but not more than ten seconds, before the door begins to move, and shall continue sounding until the door is completely closed. In the case of remote hand operation it is sufficient for the audible alarm to sound only when the door is moving.

In passenger areas and areas of high ambient noise the Register may require the audible alarm to be supplemented by an intermittent visual signal at the door.

**7.12.5.10** The central operating console at the navigation bridge shall have a switch with two modes of control:

a "local control" mode which shall allow any door to be locally opened and closed without automatic closure; and

a "doors closed" mode which shall allow doors to be opened locally and shall automatically reclose the doors upon release of the local control mechanism.

The switch shall normally be in the "local control" position. The "doors closed" position shall only be used in an emergency or for testing purposes.

**7.12.5.11** Where trunkways or tunnels for access from crew accommodation to the stokehold, for piping, or for any other purpose are carried through main transverse watertight bulkheads, they shall be watertight. The access to at least one end of each such tunnel or trunkway, if used as a passage at sea, shall be through a trunk extending watertight to a height sufficient to permit access above the margin line. The access to the other end of the trunkway or tunnel may be through a watertight door of the type required by its location in the ship. Such trunkways or tunnels shall not extend through first subdivision bulkhead abaft the collision bulkhead.

**7.12.5.12** Where ventilating trunks in connection with refrigerated cargo and ventilation or forced draught trunks are carried through more than one watertight bulkhead, the means of closure at such openings shall be operated by power and be capable of being closed from the main control station situated above the bulkhead deck.

**7.12.5.13** If the Register is satisfied that such doors are essential, watertight doors of satisfactory construction may be fitted in watertight bulkheads dividing cargo between deck spaces. Such doors may be hinged, rolling or sliding doors but shall not be remotely controlled. They shall be fitted at the highest level and as far from the shell plating as practicable, but in no case shall the outboard vertical edges be situated at a distance from the shell plating which is less than 0,2 of the breadth of the ship, as defined in [7.12.3.1](#).

If any of such doors shall be accessible during the voyage, they shall be fitted with a device, which prevents unauthorized opening.

**7.12.5.14** Portable plates on bulkheads shall not be permitted except in machinery spaces. The Register may permit not more than one power-operated sliding watertight door in each watertight bulkhead larger than those specified in [7.12.5.2](#) to be substituted for these portable plates, provided these doors are intended to remain closed during navigation except in case of urgent necessity at the discretion of the master. These doors need not meet the requirements of [7.12.5.3](#) regarding complete closure by hand-operated gear in 90 s.

**7.12.5.15** For passenger ships and special purpose ships carrying more than 60 persons having length of 120 m or more or having three or more main vertical zones, the power operated doors shall comply with the requirements of 2.2.6.8 of Part VI "Fire Protection" (refer also to 2.2.6.7.3 of the above Part).

#### **7.12.6 Doors in ships designed for the carriage of vehicles.**

**7.12.6.1** The requirements of [7.12.6](#) apply to doors fitted in watertight subdivision bulkheads separating a cargo space from an adjacent cargo space in ships designed for the carriage of vehicles and covered by the requirements of Part V "Subdivision", if the total number of persons on board (excluding the master and the members of the crew or other persons employed or engaged in any capacity on board a ship on the business of that ship, and also a child under one year of age) is not greater than the value  $N$  determined by the formula

$$N = 12 + 0,04A \quad (7.12.6.1)$$

where  $A$  = total deck area, in  $m^2$ , of spaces available for the stowage of vehicles where the clear height at the stowage position and at the entrances to such spaces is not less than 4 m.

**7.12.6.2** The doors specified in [7.12.6.1](#) may be fitted at any level if the Register is satisfied that such doors are essential for the movement of the vehicles in the ship.

**7.12.6.3** The doors specified in [7.12.6.1](#) shall be fitted as far from the shell plating as practicable, but in no case shall the outboard vertical edge of the door be situated at a distance from the shell plating that is less than 0,2 of the breadth of the ship, such distance being measured at right angles to the centreline of the ship at the level of the subdivision loadline.

**7.12.6.4** The doors specified in [7.12.6.1](#) may be of the following types: hinged, sliding or rolling but they shall not be controlled remotely. The doors shall be fitted with devices ensuring watertightness, securing and locking.

When the sealing material of the door is not classed as non-combustible (refer to 1.6.3.1 of Part VI "Fire Protection"), the gasket shall be suitably protected from the effects of fire by a method approved by the Register.

The doors shall be fitted with a device which prevents unauthorized opening.

**7.12.6.5** The doors specified in [7.12.6.1](#) shall be so designed that they could be opened and closed both in case of unloaded and loaded decks, the deck deflections under the effect of the stowed cargo being taken into account.

The securing devices of the door shall be so designed that account is taken of the deck deflections under the effect of the stowed cargo resulting in relative displacement of the structural elements of the bulkhead and the door.

**7.12.6.6** Where watertightness is ensured by rubber or other suitable gaskets and securing devices, at each corner of the door or door section (if any) the securing devices shall be fitted.

The securing devices of such doors shall be designed to withstand the following forces, in kN:

$F_1$  for securing devices fitted at the lower edge of the door;

$F_2$  for securing devices fitted at the upper edge of the door;

$F_3$  for securing devices fitted at the vertical edge of the door.

These forces shall be determined by the formulae:

$$F_1 = \frac{9,81A}{n_1} \left( \frac{H_1}{2} - \frac{h}{6} \right) + 29,42; \quad (7.12.6.6-1)$$

$$F_2 = \frac{9,81A}{n_2} \left( \frac{H_1}{2} - \frac{h}{3} \right) + 29,42; \quad (7.12.6.6-2)$$

$$F_3 = \frac{a}{A} [F_1(n_1 - 1)h_i + F_2(n_2 - 1)(h - h_i)] \quad (7.12.6.6-3)$$

where  $A$  = clear area of the door, in m<sup>2</sup>;

$H_1$  = vertical distance from the lower edge of the door opening to the lower edge of the plating of the bulkhead deck at the centreline of the ship, in m, but not less than 5 m;

$h$  = clear height of the door, in m;

$h_i$  = vertical distance from the securing device considered to the upper edge of the door, in m;

$a$  = half the sum of the vertical distances from the securing device considered to the nearest upper and lower securing devices, in m;

$n_1$  = number of the securing devices fitted on the lower edge of the door;

$n_2$  = number of the securing devices fitted on the upper edge of the door.

When the securing device is under the effect of the design force  $F_1$ ,  $F_2$  or  $F_3$ , the stresses in its parts shall not exceed 0,5 times the upper yield stress of material.

**7.12.6.7** The operation of the doors specified in [7.12.6.1](#) shall be by means of local control only. On the bridge indicators shall be provided to show automatically that each door is closed and all door fastenings are secured.

**7.12.6.8** The requirements of [7.12.2.1 — 7.12.2.4](#) are also applicable to doors specified under [7.12.6.1](#).

**7.12.7 Manholes in watertight subdivision bulkheads.**

**7.12.7.1** The requirements of [7.9](#) relating to the manholes located on the freeboard deck, raised quarter deck or the first tier of superstructures are generally applicable to the manholes fitted in the watertight subdivision bulkheads.

No manholes are permitted:

- .1** in the collision bulkhead below the bulkhead deck for ships having subdivision distinguishing mark in the class notation, and below the freeboard deck for other ships;
- .2** in watertight subdivision bulkheads separating a cargo space from an adjacent cargo space or a fuel oil tank.

**7.12.8 Watertight doors of fishing vessels.**

**7.12.8.1** The number of openings in watertight bulkheads shall be reduced to the minimum compatible with the general arrangements and operational needs of the vessel. Openings shall be fitted with watertight closing appliances. Watertight doors shall be of an equivalent strength to the adjacent unpierced structure.

**7.12.8.2** In vessels of less than 45 m in length, such doors may be of the hinged type, which shall be capable of being operated locally from each side of the door and shall normally be kept closed at sea. A notice shall be attached to the door on each side to state that the door shall be kept closed at sea.

**7.12.8.3** In vessels of 45 m in length and over, watertight doors shall be of the sliding type in:

- .1** spaces where it is intended to open them at sea and if located with their sills below the deepest operating waterline, except where it is impracticable or unnecessary taking into account the type and operation of the vessels; and
- .2** the lower part of a machinery space where there is access from it to a shaft tunnel;
- .3** otherwise watertight doors may be of the hinged type.

**7.12.8.4** Sliding watertight doors shall be capable of being operated when the vessel is listed up to 15° either way.

**7.12.8.5** Sliding watertight doors whether manually operated or otherwise shall be capable of being operated locally from each side of the door; in vessels of 45 m in length and over, these doors shall also be capable of being operated by remote control from an accessible position above the working deck except when the doors are fitted in crew accommodation spaces.

**7.12.8.6** Means shall be provided at remote operating positions to indicate when a sliding door is open or closed.



### 7.13 CARGO HATCH COVERS OF BULK CARRIERS, ORE CARRIERS AND COMBINATION CARRIERS

**7.13.1** The design of cargo hatch covers for bulk carriers, ore carriers and combination carriers shall comply with the requirements in [7.10.1](#), [7.10.2](#), [7.10.3.4](#), [7.10.3.5](#) and [7.10.4](#).

For bulk carriers of 90 m in length and above, contracted for construction on or after 1 July 2015, the requirements for cargo hatch covers are regulated by the IACS Common Structural Rules.

The requirements of [7.13](#) are not applicable to self-unloading bulk carriers.

**7.13.2** Cargo hatch covers shall be made of steel. The use of other materials may be allowed provided it is confirmed by calculations and tests that they have a strength at least equivalent to that of the hatch covers made of steel.

**7.13.3** The pressure  $P$ , in kPa, on the hatch cover panels located on the freeboard deck is determined by the formulae:

for ships of 100 m in length and above

$$P = 34,3 + \frac{P_{FP} - 34,3}{0,25} \left(0,25 - \frac{X}{L}\right) \geq 34,3 \quad (7.13.3-1)$$

where  $P_{FP}$  = pressure at the fore perpendicular to be determined by the formula

$$P_{FP} = 49,1 + (L - 100)a$$

where  $a = 0,0726$  — for type "B" freeboard ships;

$a = 0,356$  — for ships with reduced freeboard;

$L$  = ship's length, but not more than 340 m;

$X$  = distance, in m, of the midlength of the hatch cover under consideration from the forward end of  $L$ .

Where a position 1 hatchway is located at least one superstructure standard height higher than the freeboard deck, the pressure  $P$  may be taken equal to 34,3 kPa;

for ships less than 100 m in length

$$P = 15,8 + \frac{L}{3} \left(1 - \frac{5X}{3L}\right) - 3,6 \frac{X}{L} \geq 0,195L + 14,9. \quad (7.13.3-2)$$

Where two or more panels are connected by hinges, each individual panel shall be considered separately.

**7.13.4** The normal  $\sigma_a$  and shear  $\tau_a$  stresses in the hatch cover structures shall not exceed the permissible values:

$$\sigma_a = 0,8R_{eH};$$

$$\tau_a = 0,46R_{eH}$$

where  $R_{eH}$  = upper yield stress of the hatch cover material.

The normal stressing compression of the attached flange of primary supporting members shall not exceed 0,8 times the critical buckling stress of the structure according to the calculations given in [7.13.9 — 7.13.11](#).

The stresses in hatch covers that are designed as a grillage of longitudinal and transverse primary supporting members shall be determined by a grillage or a finite element analysis.

When a beam or a grillage analysis is used, the secondary stiffeners shall not be included in the attached flange area of the primary members.

When calculating the stresses  $\sigma$  and  $\tau$ , the net scantlings (no allowance for corrosion and wear) of hatch cover structure elements shall be used.

**7.13.5** The effective flange area  $A_F$ , in  $\text{cm}^2$ , of the attached plating, to be considered for the yielding and buckling checks of primary supporting members or grillages, is obtained as the sum of the effective flange areas of each side of the girder web

$$A_F = \sum_{nf} (10 b_{ef} t) \quad (7.13.5)$$

where  $nf = 2$  if attached plate flange extends on both sides of a girder web;  
 $nf = 1$  if attached plate flange extends on one side of a girder web only;  
 $t$  = thickness of attached plate, in mm;  
 $b_{ef}$  = effective breadth, in m, of attached plate flange on each side of a girder web assumed equal to  $b_p$ , but not more than  $0,165l$ ;  
 $b_p$  = half distance, in m, between the considered primary supporting member and the adjacent one;  
 $l$  = span, in m, of primary supporting members.

**7.13.6** The net thickness  $t$ , in mm, of the hatch cover top plating shall be not less than

$$t = F_p 15,8s \sqrt{\frac{p}{0,95\sigma_F}} \quad (7.13.6)$$

where  $F_p$  = factor equal to:  
 1,9 if ratio  $\sigma/\sigma_a \geq 0,8$ ;  
 1,5 in other cases;  
 $s$  = stiffener spacing, in m;  
 $p$  = pressure, in kPa, according to [7.13.3](#);  
 $\sigma$  = according to [7.13.8](#);  
 $\sigma_a$  = according to [7.13.4](#).

and not less than 1 % of the stiffener spacing or 6 mm, whichever is greater.

**7.13.7** The required minimum section modulus  $Z$ , in  $\text{cm}^3$ , of secondary stiffeners of the hatch cover top plates, based on stiffener net member thickness, are given by

$$Z = \frac{1000l^2 s p}{12\sigma_a} \quad (7.13.7)$$

where  $l$  = secondary stiffener span, in m, to be taken as the spacing of primary supporting members or the distance between a primary supporting member and the edge support, as applicable. When brackets are fitted at both ends of all secondary stiffener spans, the secondary stiffener span may be reduced by an amount equal to 2/3 of the minimum brackets arm length, but not greater than 10 % of the gross span, for each bracket;  
 $s$  = secondary stiffener spacing, in m;  
 $p$  = pressure, in kPa, according to [7.13.3](#);  
 $\sigma_a$  = according to [7.13.4](#).

The net section modulus of the secondary stiffeners shall be determined based on an attached plate width assumed equal to the stiffener spacing.

**7.13.8** The section modulus value and web thickness of primary supporting members, based on member net thickness, shall be such that the normal stress  $\sigma$  in both flanges and the shear stress  $\tau$  in the web do not exceed the permissible values  $\sigma_a$  and  $\tau_a$ , respectively, defined according to [7.13.4](#).



The width of the primary supporting members flange shall be not less than 40 % of their depth for laterally unsupported spans greater than 3,0 m. Tripping brackets attached to the flange may be considered as a lateral support for primary supporting members.

The flange outstand shall not exceed 15 times the flange thickness.

**7.13.9** The compressive stress  $\sigma$  in the hatch cover plate panels, induced by the bending of primary supporting members parallel to the direction of secondary stiffeners, shall not exceed 0,8 times the critical buckling stress  $\sigma_{C1}$ , to be evaluated as follows:

$$\begin{aligned}\sigma_{C1} &= \sigma_{E1}, \text{ when } \sigma_{E1} \leq \frac{\sigma_F}{2}; \text{ or} \\ \sigma_{C1} &= \sigma_F [1 - \sigma_F / (4\sigma_{E1})], \text{ when } \sigma_{E1} > \frac{\sigma_F}{2}\end{aligned}\quad (7.13.9-1)$$

where  $\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>;

$$\sigma_{E1} = 3,6E \left( \frac{t}{1000s} \right)^2$$

where  $E$  = modulus of elasticity, in N/mm<sup>2</sup>; to be assumed  $2,06 \cdot 10^5$  for steel;

$t$  = net thickness of plate panel, in mm;

$s$  = spacing of secondary stiffeners, in m.

The mean compressive stress  $\sigma$  in each of the hatch cover plate panels, induced by the bending of primary supporting members perpendicular to the direction of secondary stiffeners, shall not exceed 0,8 times the critical buckling stress  $\sigma_{C2}$  to be evaluated as follows:

$$\begin{aligned}\sigma_{C2} &= \sigma_{E2}, \text{ when } \sigma_{E2} \leq \frac{\sigma_F}{2}; \text{ or} \\ \sigma_{C2} &= \sigma_F [1 - \sigma_F / (4\sigma_{E2})], \text{ when } \sigma_{E2} > \frac{\sigma_F}{2}\end{aligned}\quad (7.13.9-2)$$

where  $\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>;

$$\sigma_{E2} = 0,9mE \left( \frac{t}{1000s_s} \right)^2$$

$$\text{where } m = c \left[ 1 + \left( \frac{s_s}{l_s} \right)^2 \right]^{\frac{2,1}{\psi + 1,1}};$$

$E$  = modulus of elasticity, in N/mm<sup>2</sup>;

$t$  = net thickness of plate panel, in mm;

$s_s$  = length of the shorter side of the plate panel, in m;

$l_s$  = length of the longer side of the plate panel, in m;

$\psi$  = ratio between the smallest and largest compressive stress;

$c$  = factor equal to:

1,3 when plating is stiffened by primary supporting members;

1,21 when plating is stiffened by secondary stiffeners of angle or T-type;

1,1 when plating is stiffened by secondary stiffeners of bulb type;

1,05 when plating is stiffened by flat bar.

**7.13.10** The compressive stress in the top flange of secondary stiffeners, induced by the bending of primary supporting members parallel to the direction of secondary stiffeners, shall not exceed 0,8 times the critical buckling stress  $\sigma_{CS}$ , to be evaluated as follows:

$$\sigma_{CS} = \sigma_{ES}, \text{ when } \sigma_{ES} \leq \frac{\sigma_F}{2}; \text{ or} \quad (7.13.10)$$

$$\sigma_{CS} = \sigma_F [1 - \sigma_F / (4\sigma_{ES})], \text{ when } \sigma_{ES} > \frac{\sigma_F}{2}$$

where  $\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>;  
 $\sigma_{ES}$  = ideal elastic buckling stress, in N/mm<sup>2</sup>, of the secondary stiffener to be assumed as the minimum between  $\sigma_{E3}$  and  $\sigma_{E4}$  values;

$$\sigma_{E3} = \frac{0,001EI_a}{Al^2}$$

where  $E$  = modulus of elasticity, in N/mm<sup>2</sup>;  
 $I_a$  = moment of inertia, in cm<sup>4</sup>, of the secondary stiffener, including an effective flange equal to the spacing of secondary stiffeners;  
 $A$  = cross-sectional area, in cm<sup>2</sup>, of the secondary stiffener, including an effective flange equal to the spacing of secondary stiffeners;  
 $l$  = span, in m, of the secondary stiffener;

$$\sigma_{E4} = \frac{\pi^2 EI_w}{10^4 I_p l^2} \left( m^2 + \frac{K}{m^2} \right) + 0,385E \frac{l_t}{l_p}$$

where  $K = \frac{Cl^4}{\pi^2 EI_w} \cdot 10^6$ ;  
 $m$  = number of half waves, given by the following table:

$0 < K \leq 4$	$4 < K \leq 36$	$36 < K \leq 144$	$(m-1)^2 m^2 < K \leq m^2 (m+1)^2$
$m = 1$	$m = 2$	$m = 3$	$m$ being determined according to $K$ value

$I_w$  = sectional moment of inertia, in cm<sup>6</sup>, of the secondary stiffener about its connection with the plating;

$$I_w = \frac{h_w^3 t_w^3}{36} \cdot 10^{-6} \text{ for flat bar secondary stiffeners;}$$

$$I_w = \frac{t_f b_f^3 h_w^2}{36} \cdot 10^{-6} \text{ for T-section secondary stiffeners;}$$

$$I_w = \frac{b_f^3 h_w^2}{12(b_f + h_w)^2} [t_f(b_f^2 + 2b_f h_w + 4h_w^2) + 3t_w b_f h_w] 10^{-6} \text{ for angles and bulb secondary stiffener;}$$

$I_p$  = polar moment of inertia, in cm<sup>4</sup>, of the secondary stiffener about its connection with the plating;

$$I_p = \frac{h_w^3 t_w^3}{3} 10^{-4} \text{ for flat bar secondary stiffeners;}$$

$$I_p = \left( \frac{h_w^3 t_w^3}{3} + h_w^2 b_f t_f \right) 10^{-4} \text{ for flanged secondary stiffeners;}$$

$I_t$  = moment of inertia, in cm<sup>4</sup>, of the secondary stiffener without an effective flange;

$$I_t = \frac{h_w t_w^3}{3} 10^{-4} \text{ for flat bar secondary stiffeners;}$$

$$I_t = \frac{1}{3} \left[ h_w t_w^3 + b_f t_f^3 \left( 1 - 0,63 \frac{t_f}{b_f} \right) \right] 10^{-4} \text{ for flanged secondary stiffeners}$$

where  $h_w, t_w$  = height and net thickness, in mm, of the secondary stiffener, respectively;

$b_f, t_f$  = width and net thickness, in mm, of the secondary stiffener bottom flange, respectively;

$s$  = spacing of secondary stiffeners, in m;

$$C = \left[ \frac{k_p E t_p^3}{3s \left( 1 + \frac{1,33 k_p h_w t_p^3}{1000 s t_w^3} \right)} \right]$$

where  $k_p = 1 - \eta_p$  but not less than 0. For flanged secondary stiffeners,  $k_p$  need not be taken less than 0,1;

$$\eta_p = \frac{\sigma}{\sigma_{E1}}$$

where for  $\sigma$ , refer to 7.13.8;  
for  $\sigma_{E1}$ , refer to 7.13.9;

$t_p$  = net thickness, in mm, of the hatch cover plate panel.

For flat bar secondary stiffeners and buckling stiffeners, the ratio  $h/t_w$  shall not be greater than  $15k^{0.5}$

where  $h, t_w$  = height and net thickness of the stiffener, respectively;  
 $k = 235/\sigma_F$ ;  
 $\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>.

**7.13.11** The shear stress  $\tau$  in the hatch cover primary supporting members web panels shall not exceed 0,8 times the critical buckling stress  $\tau_C$ , to be determined as follows:

$$\begin{aligned} \tau_C &= \tau_E, \text{ when } \tau_E \leq \frac{\tau_F}{2}, \\ \tau_C &= \tau_F [1 - \tau_F / (4\tau_E)], \text{ when } \tau_E > \frac{\tau_F}{2} \end{aligned} \quad (7.13.11)$$

where  $\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>;  
 $\tau_F = \sigma_F / \sqrt{3}$ ;

$$\tau_E = 0,9k_t E \left( \frac{t_{pr,n}}{1000d} \right)^2$$

where  $E$  = modulus of elasticity, in N/mm<sup>2</sup>, to be assumed equal to  $2,06 \cdot 10^5$  for steel;  
 $t_{pr,n}$  = net thickness, in mm, of primary supporting member;  
 $k_t = 5,35 + 4,0/(a/d)^2$ ;  
 $a$  = greater dimension, in m, of web panel of primary supporting member;  
 $d$  = smaller dimension, in m, of web panel of primary supporting member.

For primary supporting members perpendicular to the direction of secondary stiffeners or for hatch covers built without secondary stiffeners, a presumed square panel of dimension  $d$  shall be taken for the determination of the stress  $\tau_C$ . In such a case, the average shear stress  $\tau_C$  between the values calculated at the ends of this panel shall be considered.

**7.13.12** The vertical deflection of primary supporting members shall be not more than  $0,0056l$ , where  $l$  is the greatest span of primary supporting members.

**7.13.13** The free sectional area  $A$ , in cm<sup>2</sup>, of the securing device shall not be less than determined by the formula

$$A = 1,4a/f \quad (7.13.13-1)$$

where  $a$  = distance between securing devices, in m, which in any case shall not be adopted less than 2 m;  
 $f$  = factor determined by the formula

$$f = (R_{eH}/235)^e \quad (7.13.13-2)$$

where  $R_{eH}$  = the upper yield strength of the securing device material, in MPa, and shall not be adopted greater than 0,7 of the tensile strength of the material;  
 $e$  = index equal to:  
0,75 for  $R_{eH} > 235$  MPa;  
1,00 for  $R_{eH} \leq 235$  MPa.

For hatch covers and hatch cover sections having an area in excess of 5 m<sup>2</sup>, the active diameter of bars and bolts of the securing devices shall not be less than 19 mm.

**7.13.14** Where the packing gasket is compressed to the maximum depth possible and its pressure exceeds 5000 N/m, the area of securing devices as determined in accordance with 7.13.13, shall be increased in a relevant proportion.

**7.13.15** The stiffness of the cover corners shall be sufficient to maintain an adequate pressure of the packing gasket between the securing devices. The cross-sectional inertia moment of the corner members of the covers  $I$ , in cm<sup>4</sup>, shall be not less than that determined by the formula

$$I = 6pa^4 \times 10^{-3} \quad (7.13.15)$$

where  $p$  = pressure of the packing gasket when compressed to the maximum depth possible for the accepted design, in N/m, but not less than 5000 N/m;  
 $a$  = distance between securing devices, in m.

**7.13.16** Where hydraulic securing devices are applied, the securing devices shall be mechanically lockable in closed position in the event of loss of the hydraulic fluid.

**7.13.17** Hatch covers shall be fitted with stoppers designed for longitudinal and transverse design loads of 175 kPa.

Where the design and arrangement of the forecastle on a ship do not meet the requirements in 3.3.5.2.1 of Part II "Hull", the stoppers of the foremost hatch cover (hatch No. 1) shall be designed for a longitudinal load of 230 kPa acting on the forward end of the No. 1 hatch cover.

**7.13.18** The stresses in stoppers and their adjacent structures shall not exceed the permissible values equal to  $0,8\sigma_F$ , where  $\sigma_F$  is minimum upper yield stress of the material.

**7.13.19** For the plating and stiffeners of all type hatch covers, excepting the double skin, the corrosion addition shall be assumed equal to 2 mm. For double skin hatch covers, the corrosion addition shall be 2 mm for the top and bottom plating and 1,5 mm for the internal structures.

**7.13.20** In bulk carriers of 150 m in length and upwards, carrying solid bulk cargoes having a density of 1000 kg/m<sup>3</sup> and above, contracted for construction before 1 April 2006, the protection of the structure of cargo holds from grab wire damage during loading and unloading operations shall be achieved by structural design features:

wire rope grooving in way of cargo holds openings shall be prevented by fitting suitable protection such as half-round bar on the hatch side girders (i.e. upper portion of top side tank plates)/hatch end beams in cargo hold or upper portion of hatch coamings.

Such ships shall have the distinguishing mark **GRAB(X)** in the class notation (refer to 2.2.31 of Part I "Classification").

#### **7.14 ACCESS TO SPACES IN THE CARGO AREA OF OIL TANKERS AND BULK CARRIERS**

**7.14.1** The requirements of [7.14](#) apply to oil tankers of 500 gross tonnage and above and to bulk carriers of 20000 gross tonnage and above.

**7.14.2** Means of access and passages on ships referred to in [7.14.1](#) shall comply with the requirements of IMO resolutions MSC.134(76), MCS.151(78) and MSC.158(78), as well as IACS unified interpretation (UI) SC191 (Rev.8 Apr 2019) (the document is available at the IACS website: [www.iacs.org.uk](http://www.iacs.org.uk)).

## **7.15 ADDITIONAL REQUIREMENTS FOR OPENINGS AND THEIR CLOSING APPLIANCES IN RO-RO SHIPS**

**7.15.1** Where vehicle ramps are installed to give access to spaces below the bulkhead deck, their openings shall be able to be closed weathertight to prevent ingress of water below, alarmed and indicated to the navigation bridge.

**7.15.2** The Register may permit the fitting of particular accesses to spaces below the bulkhead deck provided they are necessary for the essential working of the ship, e.g. the movement of machinery and stores, subject to such accesses being made watertight, alarmed and indicated to the navigation bridge.

**7.15.3** Subject to provisions of [7.15.1](#) and [7.15.2](#) all accesses that lead to spaces below the bulkhead deck shall have a lowest point which is not less than 2,5 m above the bulkhead deck.

**7.15.4** Indicators shall be provided on the navigating bridge for all shell doors, loading doors and other closing appliances which, if left open or not properly secured, could lead to flooding of a special category space or ro-ro cargo space. The indicator system shall be designed on the fail safe principle and shall show by light alarms if the door is not fully closed or if any of the securing arrangements is not in place and fully locked, and by audible alarms if such door or closing appliances become open or the securing arrangements become unsecured.

The indicator panel on the navigation bridge shall be equipped with a mode selection function "harbour/sea voyage" so arranged that an audible alarm is given on the navigation bridge if the ship leaves harbour with the bow doors, inner doors, stern ramp or any other side shell doors not closed or any closing device not in the correct position. The power supply for the indicator system shall be independent of the power supply for operating and securing the doors.

**7.15.5** Television surveillance and a water leakage system shall be arranged to provide an indication to the navigation bridge and to the engine control station of any leakage through inner and outer bow doors, stern doors or any other shell doors which could lead to flooding of special category spaces or ro-ro cargo spaces.

**7.15.6** Special category spaces and ro-ro cargo spaces shall be continuously patrolled or monitored by effective means, such as television surveillance, so that any movement of vehicles in adverse weather conditions and unauthorized access of passengers thereto can be detected whilst the ship is underway.

**7.15.7** Documented operating procedures for closing and securing all shell doors, loading doors and other closing appliances which, if left open or not properly secured could lead to flooding of special category space or ro-ro cargo space, shall be kept on board and posted at an appropriate place.

**7.15.8** Besides specified in [7.15.7](#) the Manual on operation and repair of doors in shell plating shall be kept onboard containing the following information:

- main particulars and structural drawings of doors;
- door operation safety precautions;
- ship characteristics;
- door design loads;
- manufacturer's recommendations for equipment testing;
- description of equipment of bow, side and stern doors, internal bow doors, central power station, indication panel on navigation bridge, control panel in engine room;
- operating characteristics: permissible angles of heel/trim with/without cargo as well as permissible angles of heel/trim during use of doors;
- door operating instruction;

door operating instruction in case of emergency;

operation and repair of doors: description and deadlines of current repair, occurring failures and their acceptable elimination, manufacturer's instructions for operation and repair of doors;

record book of examinations including survey of securing, locking and supporting devices, repair and replacement.

The above manual on operation and repair of doors in shell plating shall be submitted for the Register approval.

## **8 ARRANGEMENT AND EQUIPMENT OF SHIP'S SPACES. OTHER ARRANGEMENTS AND EQUIPMENT**

### **8.1 GENERAL**

**8.1.1** The requirements for the arrangement and equipment of machinery spaces are specified in Part VII "Machinery Installations" and those relating to refrigerating machinery spaces, refrigerant storerooms, as well as refrigerated cargo spaces are set forth in Part XII "Refrigerating Plants".

**8.1.2** In berth-connected ships, the arrangement and equipment of spaces, various devices and equipment shall comply with the relevant requirements of [8.5](#) and [8.6](#).

Furthermore, berth-connected ships which are used as hotels or hostels shall comply with the requirements set out in [8.5](#) as in the case of passenger ships.

Besides, a berth-connected ship shall have at least two companion ladders fitted as far away from each other as possible. The companion ladders shall be not less than 0,2 m wide where the total of passengers and crew on board does not exceed 50.

For each 10 persons above 50, the companion ladder breadth shall be increased by 5 cm.



## **8.2 LOCATION OF SPACES**

**8.2.1** The chart room shall be located in a space adjacent to the wheelhouse. The chart room and the wheelhouse may be situated in a common space.

**8.2.2** No accommodation spaces shall be arranged forward of the collision bulkhead and abaft of the afterpeak bulkhead below the bulkhead deck.

### **8.3 NAVIGATION BRIDGE**

#### **8.3.1 General.**

**8.3.1.1** The ship's control station shall be located in an enclosed space of the wheelhouse on the navigation bridge. The navigation bridge shall be located so as to ensure:

- proper visual control of the ship's running;
- good visibility with maximum view of water surface;
- good audibility of sound signals of the approaching ships;
- for tugs, possibility of visual control of tow line during towing operations.

It is recommended to arrange the steering control station at the ship's centreline.

**8.3.1.2** Visibility from the navigation bridge shall comply with requirements of 3.2 of Part V "Navigational Equipment" of the Rules for the Equipment of Sea-Going Ships.

## 8.4 EQUIPMENT OF DRY CARGO HOLDS

**8.4.1** When in ships not having double bottom wooden ceiling is placed on top of the floors, it shall be solid and shall extend up to the bilge. The ceiling is recommended to be made of portable sections of such dimensions and so constructed as to allow of their ready removal at any place.

The thickness of a ceiling shall be:

at least 40 mm for ships of 30 m in length and less;

at least 60 mm for ships over 30 m in length;

at least 70 mm under cargo hatchways.

**8.4.2** When in ships having double bottom wooden ceiling is fitted, it shall have a thickness as follows:

at least 50 mm for ships of 60 m in length and less;

at least 65 mm for ships over 60 m in length.

**8.4.3** Where cargo is discharged by grabs or other mechanisms, the thickness of the wooden ceiling fitted under cargo hatchways shall be doubled.

**8.4.4** In holds intended for carriage of grain and other bulk cargoes the wooden ceiling on the inner bottom or, in case the latter is omitted, on the top of floors, shall be fitted so as to prevent wells, bilges and suction pipes of the bilge system from clogging.

**8.4.5** The wooden ceiling shall not be laid directly on the inner bottom metal plating, but shall be embedded in a bituminuous or epoxy composition approved by the Register, or placed on battens of 25 — 30 mm in thickness along the floors. The wooden ceiling over the bilges shall be placed so as to be readily removable (refer also to 7.6.9 of Part VIII "Systems and Piping").

**8.4.6** It is recommended that the cargo battens made of wood or metal shall be fitted on sides in holds and spaces intended for carriage of general cargoes. The thickness of wooden battens shall be as follows:

at least 40 mm for ships of 70 m in length and less;

at least 50 mm for ships of length exceeding 70 m.

The distance between adjacent battens shall not exceed 305 mm.

The battens shall be attached to side framing so as to be readily removable and replaceable.

**8.4.7** All projecting parts of various equipment in the holds (manholes, air pipes, sounding pipes, etc.) shall be protected with wooden screens, grids, chutes, etc. in places subject to impacts of cargoes, grabs or other hoisting devices. Requirements for laying pipe lines in cargo holds are given in 5.3 of Part VIII "Systems and Piping".

**8.4.8 Cellular guide members for the carriage of containers in holds.**

**8.4.8.1** The requirements of [8.4.8](#) apply to the cellular guide members used for the carriage of containers, manufactured in accordance with the Rules for the Construction of Containers, in the holds of cargo ships.

**8.4.8.2** Cellular guide members comprise uprights and horizontal shores arranged breadthwise and lengthwise. In the holds, the cellular guide members may be removable or permanent.

**8.4.8.3** Cellular guide members shall not be integrated in the hull structure. They shall be so designed that no stresses are exerted on them when the hull comes under bending or torsion.

**8.4.8.4** Cellular guide members shall be designed to withstand stresses due to the forces  $F_x$  and  $F_y$  affecting the gravity centre of each container, which shall be determined by the formulae:

lengthwise

$$F_x = mga_x, \text{ in N;} \quad (8.4.8.4-1)$$

breadthwise

$$F_y = mga_y, \text{ in N} \quad (8.4.8.4-2)$$

where  $m$  = maximum gross mass of container, in kg;  
 $g$  = gravity acceleration,  $g = 9,81 \text{ m/s}^2$ ;  
 $a_x, a_y$  = dimensionless accelerations to be determined in accordance with [1.7](#), the coordinates of  $x$  and  $z$  being determined up to the gravity centre of each container volume.

The forces  $F_x$  and  $F_y$  shall be determined for each container, and through the four relevant corner fittings of the end or side wall they are uniformly distributed among the uprights. By way of simplification, maximum  $F_x$  and  $F_y$  values may be adopted for each container. Where a number of adjoining containers are supported by a pair of uprights, the  $F_x$  and  $F_y$  values for the particular container tier shall be summed up and distributed among the respective uprights.

Friction forces arising where the corner fittings of containers touch each other or the inner bottom shall be ignored.

**8.4.8.5** The forces resultant from loads to be determined in accordance with [8.4.8.4](#), where the container corner fittings rest upon the uprights, shall not exceed 150 kN per fitting breadthwise or 75 kN per fitting lengthwise.

**8.4.8.6** Where the attachment of uprights to the hull structures is not considered as firm fixing (free resting, flexible fixing, etc.), the cellular guide members shall be calculated as three-dimensional frames.

Where the attachment of uprights to the hull structures can be considered as firm fixing, particular vertical surfaces of cellular guide members may be calculated as plane frames.

The stresses in the cellular guide member components shall not exceed 0,8 times the upper yield stress of their material.

The terms of calculating the stability of cellular guide member components shall be found under [8.4.8.14](#).

**8.4.8.7** In view of the requirements under [8.4.8.6](#), the displacement of the resting points of corner fittings upon the uprights shall not exceed 25 mm breadthwise or 40 mm lengthwise.

**8.4.8.8** When determining the thickness of the uprights components, the thickness of those especially subject to wear shall be increased by 5 mm and equal to at least 12 mm.

**8.4.8.9** Where the uprights comprise separate angular sections, they shall be firmly secured to each other with horizontal plates at the resting points of container corner fittings and at least halfway between those points.

**8.4.8.10** At the upper ends of the uprights, devices shall be fitted to facilitate the insertion of containers into the stowage frames.

**8.4.8.11** Uprights shall, so far as possible without notches, be attached to transverse and longitudinal bulkheads by means of shear- and bend-stiff members.

**8.4.8.12** The total margin between the external scantlings of containers and the internal uprights surfaces shall not exceed 25 mm breadthwise or 40 mm lengthwise.

When fitting the uprights, the deviation from the straight line shall not exceed 5 mm.

**8.4.8.13** Transverse horizontal and longitudinal horizontal shores serve to connect the stand-alone uprights to each other and to secure them to vertical hull structures. The horizontal shores shall, as far as possible, be fitted on the level of the corner fitting rest points and be torsion- and bend-stiff connected to the uprights.

**8.4.8.14** The stability of transverse horizontal and longitudinal horizontal shores and, where necessary, that of uprights shall be checked by a procedure approved by the Register.

When determining the permissible buckling stresses, the relevant safety factor may be adopted equal to 2,0.

The free length of buckling shall be adopted span-equal in the case of a bolted joint or 0,7 times the shore or uprights span in the case of a welded joint. The flexibility shall not exceed 250.

For other types of bar-end fixing, the free length shall be established according to the procedure approved by the Register.

**8.4.8.15** The container rest points on the inner bottom and areas containing the connections and attachments of container stowage frames in way of hull structures shall be strengthened in conformity with the requirements of Part II "Hull".

#### **8.4.9 Movable decks, platforms, ramps and other similar structures.**

**8.4.9.1** The requirements of 8.4.9 apply to the movable decks, platforms, ramps and other similar structures designed to be installed in two positions:

in working position when they are used for carriage, loading or unloading of vehicles or other cargoes;

in non-working position when they are not used for carriage, loading or unloading of vehicles or other cargoes.

**8.4.9.2** The movable decks, platforms, ramps and other similar structures and also their supporting elements at ship's sides, decks and bulkheads. The pillars or suspensions for decks and platforms ensuring their proper installation in the working position shall be designed in accordance with the requirements of Part II "Hull".

**8.4.9.3** Arrangements shall be provided for reliable securing of the movable decks, platforms ramps and other similar structures in the non-working position.

**8.4.9.4** When the movable decks, platforms, ramps and other similar structures are secured in the non-working position, the hoisting gear and elements thereof shall not generally be kept under the load.

It is not permitted to secure the movable decks, platforms, ramps and other similar structures by suspending them on ropes.

**8.4.9.5** The structural elements of the arrangements mentioned in [8.4.9.3](#) and also the associated supporting structures shall be designed to withstand the forces resulting from the application of the loads  $P_x$ ,  $P_y$ ,  $P_z$ , as determined by the formulae given below, to the centres of gravity of the considered section of the deck, platform, ramp or other similar structures:

$$P_x = m g a_x; \quad (8.4.9.5-1)$$

$$P_y = m g a_y; \quad (8.4.9.5-2)$$

$$P_z = m \cdot g(1 + a_z) \quad (8.4.9.5-3)$$

where  $P_x$  = horizontal load parallel to the centreline of the ship, in N. Consideration shall be given to the cases when the load  $P_x$  is directed both forward and aft;

$P_y$  = horizontal load parallel to the midstation plane, in N. Consideration shall be given to the cases when the load  $P_y$  is directed both to the nearest ship's side and to the opposite side;

$P_z$  = vertical load directed downward, in N;

$m$  = mass of the considered section of the deck, platform, ramp or other similar structure, in kg;

$g$  = acceleration due to gravity equal to 9,81 m/s<sup>2</sup>;

$a_x, a_y, a_z$  = dimensionless accelerations to be determined in accordance with [1.7](#).

**8.4.9.6** When determining the forces affecting the structural elements of the arrangements specified in [8.4.9.3](#) and the associated supporting structures with regard to the provisions of [8.4.9.5](#), the loads  $P_x$ ,  $P_y$  and  $P_z$  are regarded as separately applied, i.e. no account is taken of their combined action and of the frictional forces originating on the surfaces of the considered sections of decks, platforms, ramps or other similar structures which are in contact with the associated supporting structures.

**8.4.9.7** When the structural elements of the arrangements specified in [8.4.9.3](#) and the associated supporting structures are under the effect of the loads determined according to the provisions of [8.4.9.5](#) and [8.4.9.6](#), the stresses in their parts shall not exceed 0,8 times the upper yield stress of material.

Under the effect of these loads the safety factor of the wire ropes in relation to their breaking strength shall be not less than 4; the safety factor of the chain cables in relation to the proof load of the chain shall be not less than 2; the margin of safety against buckling of the elements subjected to the compression stress shall be not less than 2.

**8.4.9.8** Wire ropes used in the arrangements specified in [8.4.9.3](#) shall satisfy the requirements of 3.15 and chain cables — those of 7.1 of Part XIII "Materials".

## 8.5 EXITS, DOORS, CORRIDORS, STAIRWAYS AND VERTICAL LADDERS

### 8.5.1 General.

**8.5.1.1** Location and arrangement of exits, doors, corridors, stairways and vertical ladders shall ensure the possibility of quick, safe and free access from spaces to the embarkation stations of lifeboats and liferafts.

Additional means for outdoor escape shall be clearly marked, where necessary, to ensure accessibility, and be provided with a proper design to be used in emergency.

### 8.5.2 Exits and doors.

**8.5.2.1** In passenger ships and in special purpose ships each watertight compartment or similarly restricted space or group of spaces situated below the bulkhead deck shall have at least two means of escape, in any case one of which shall be independent of the door in the subdivision bulkhead.

**8.5.2.2** In passenger ships and in special purpose ships above the bulkhead deck each main vertical fire zone (refer to 2.2.1.2 of Part VI "Fire Protection") or similarly restricted space or group of spaces shall have at least two means of escape one of which shall give access to a stairway forming a vertical means of escape to the embarkation stations of lifeboats and liferafts.

**8.5.2.3** In passenger ships the number and location of means of escape from special category spaces (refer to 1.5.9 of Part VI "Fire Protection") depend on the degree of safety; the degree of safety for escape from these spaces to the embarkation stations of lifeboats and liferafts shall at least correspond to that specified in [8.5.2.1](#) and [8.5.2.2](#).

For cargo ships in all ro-ro cargo spaces where the crew is normally employed, at least two widely separated escape routes shall be provided.

**8.5.2.4** In cargo ships of 500 gross tonnage and upwards at each level of accommodation spaces there shall be at least two means of escape, as widely separated as possible, from each restricted space or group of spaces; from the spaces situated below the open deck the main means of escape shall be formed by a stairway, the other means of escape may be formed by a casing with a vertical ladder or by a stairway; from spaces above the open deck the means of escape shall be stairways or doors to an open deck or a combination thereof. The open deck stated above shall be a category (10) (in accordance with 2.2.1.5 of Part VI "Fire Protection").

**8.5.2.5** Spaces may be dispensed with one of the means of escape required under [8.5.2.1](#) or [8.5.2.4](#), due regard being paid to the nature and location of the spaces and to the number of persons normally employed therein.

**8.5.2.6** Stairways serving only a space and a balcony in that space, as well as lifts shall not be considered as means of escape specified in [8.5.2.1 — 8.5.2.4](#).

**8.5.2.7** Each cinema hall shall be provided with at least two means of escape. Both exits shall be spaced from each other as wide as practicable. A readily seen inscription "Exit" or "Emergency exit" shall be provided above every such exit.

**8.5.2.8** In case of open bridge wings, the wheelhouse shall have two exits, one to each side of the navigation bridge, with a passageway through the house from side to side.

**8.5.2.9** The total width of exits from cinema halls shall be determined on the basis of 0,8 m per 50 persons, however, the width of each exit shall be not less than 1,1 m, when the number of seats is more than 50, and not less than 0,8 m when the number of seats is not more than 50.

The width of each exit from accommodation and service spaces shall be not less than 0,6 m. The sizes of the ladderways from cargo holds shall be not less than 0,6×0,6 m.

**8.5.2.10** The exit doors and ladderway covers shall be so arranged that they can be operated from both sides.

Doors shall open as follows:

- .1 doors of accommodation, excluding public, and service spaces giving access to a corridor inside the spaces;
- .2 doors of public rooms, outwards on each side;
- .3 doors in the end bulkheads of superstructures and in external transverse bulkheads of deckhouses, outwards in the direction of the nearest side;
- .4 doors in the external longitudinal bulkheads of deckhouses, outwards in the forward direction.

In cargo ships the inner doors duplicating the doors specified in [8.5.2.10.3](#) and [8.5.2.10.4](#) may open inside the space.

In ships of 31 m in length and less the doors indicated in [8.5.2.10.1](#) may open outwards (to the corridor) if they are situated at the end of blind corridors and do not hinder the exits from other spaces.

No sliding doors shall be fitted at exits and means of escape, except for doors of the wheelhouse.

The doors referred to in [8.5.2.10.1](#) shall not be provided with hooks for holding the door open. It is permitted that such doors be fitted with buffers and spring catchers to fix the door in the open position and to allow for its closure without entering the space.

The doors specified in [8.5.2.10.3](#) and [8.5.2.10.4](#) may open in a different direction when security against the impact of the sea and safe passage are provided.

**8.5.2.11** In arrangement and disposition of exits and doors in dangerous zones, spaces and areas of oil tankers and oil recovery ships, as well as of ships carrying dangerous goods requirements shall be considered with respect to the safe-type electrical equipment to be used in spaces adjacent to dangerous zones with the doors open into such spaces (refer to 19.2 and 19.11 of Part XI "Electrical Equipment").

### **8.5.3 Corridors and passageways.**

**8.5.3.1** All corridors and passageways shall ensure free movement of persons along them. On passenger ships and special purpose ships carrying more than 60 persons, a lobby, corridor or part of a corridor shall have more than one means of escape.

Cargo ships and special purpose ships carrying not more than 60 persons shall have no dead-end corridors more than 7 m long. By a dead-end corridor, a corridor or part of a corridor is meant which has only one means of escape.

Corridors used as means of escape on cargo ships shall be at least 700 mm wide and shall be fitted with a handrail on either side. Corridors with a width of 1800 mm and more shall be fitted with handrails on each side. Width of a corridor is determined as a distance between a handrail and opposite bulkhead or as a distance between handrails.

**8.5.3.2** Corridors used as means of escape on passenger ships shall be at least 900 mm wide.

**8.5.3.3** The widths of passageways in the cinema hall and in the entrance hall shall not be less than 1,1 m and 1,4 m, respectively.

The width of the main passageways in the restaurant or dining room and also the messroom shall not be less than 0,9 m and that of the side passageways shall be at least 0,65 m. In ships of less than 500 gross tonnage the width of main passageways in the messroom may be reduced down to 0,65 m.

**8.5.3.4** The width of the main passageway in the seating passenger space shall be at least 1 m with number of passengers up to 50 and at least 1,1 m with number of passengers in excess of 50.

**8.5.3.5** In passenger ships the main corridors adjacent to engine and boiler casings shall be at least 1,2 m in width, however, in ships of less than 500 gross tonnage this width may be reduced down to 0,9 m.

**8.5.3.6** The width of passageway on the bridge shall not be less than 0,8 m in ships of 500 gross tonnage and over and at least 0,6 m in ships of less than 500 gross tonnage.



**8.5.3.7** In passenger ships and special purpose ships the width of the deck passageways providing access to the lifeboat and liferaft embarkation deck shall not be less than:

0,9 m if the number of seats in lifeboats is not more than 50 on each side of ship;

1,0 m if the number of seats in lifeboats is 50 and over, but less than 100 on each side of ship;

1,2 m if the number of seats in lifeboats is 100 and over, but less than 200 on each side of ship.

If number of seats in lifeboats is 200 and over on each side, the width of the passageways shall be determined according to the procedure approved by the Register.

In other ships the width of the passageways referred to above shall not be less than 0,8 m.

#### **8.5.4 Stairways and vertical ladders.**

**8.5.4.1** All between deck stairways shall be of steel frame construction or of equivalent material (refer to 1.2 of Part VI "Fire Protection"). Special requirements for arrangement of stairway enclosures and protection of means of escape are specified in 2.1.4.3, 2.1.4.5 and 2.2.2.4 of Part VI "Fire Protection".

**8.5.4.2** On passenger ships and special purpose ships carrying more than 60 persons, in escape routes providing access to the lifeboat and liferaft embarkation deck, the following conditions shall be met:

**.1** the width of stairways shall be not less than 900 mm, with handrails on each side. The minimum width of stairways shall be increased by 10 mm for every one person in excess of 90 persons. The maximum width between handrails where stairways are wider than 900 mm shall be 1800 mm. The total number of persons to be evacuated by such stairways shall be assumed to be two-thirds of the crew and the total number of passengers in the areas served by such stairways;

**.2** all stairways sized for more than 90 persons shall be aligned fore and aft;

**.3** the doorways, corridors and intermediate landings included in means of escape shall be sized in the same manner as stairways;

**.4** stairways shall not exceed 3,5 m in vertical rise without the provision of a landing and shall not have an angle of inclination greater than 45°;

**.5** with the exception of intermediate landings, the landings at each deck level shall not be less than 2 m<sup>2</sup> in area and shall increase by 1 m<sup>2</sup> for every 10 persons provided for in excess of 20 persons but need not exceed 16 m<sup>2</sup>, except for those landings servicing public spaces having direct access onto the stairway enclosure;

**.6** in any case, the width of stairway forming means of escape from enclosed spaces within each main vertical zone shall be in accordance with the requirements of Appendix 1 to this Part.

**8.5.4.3** Stairways used as means of escape on cargo ships shall be at least 700 mm wide and shall be fitted with a handrail on at least one side. Stairways with a width of 1800 mm and more shall be fitted with handrails on each side. In cargo ships of less than 500 gross tonnage the width of stairways may be 600 mm. Angle of slope of ladders shall be usually 45° but not greater than 50°, in the machinery and in small spaces — not greater than 60°. In ships of less than 500 gross tonnage and fishing vessels in case of insufficient space at egress from the stairway, the stairways may be installed with the angle of slope of ladders of 55° — in accommodation and service spaces, with 60° — on decks. The size of doors providing an access to any stairway shall be of the same size as the stairway

**8.5.4.4** Vertical ladders and ladder steps in cargo holds, tanks, etc. shall be at least 300 mm wide.

#### **8.5.5 Low location lighting (LLL) on passenger ships carrying more than 36 passengers and special purpose ships carrying more than 240 persons.**

**8.5.5.1** In addition to the emergency lighting stipulated by 19.1.2 of Part XI "Electrical Equipment", the means of escape, including stairways and exits, of passenger ships carrying more than 36 passengers and special purpose ships carrying more than 240 persons shall be marked by LLL at all points of the escape route including angles and intersections.

**8.5.5.2** Provision shall be made for the following LLL systems:

.1 photoluminescent system which uses photoluminescent material containing a chemical (example: zinc sulfide) that has the quality of storing power when illuminated by visible light;

.2 electrically powered systems which use incandescent bulbs, light emitting diodes, electroluminescent strips or lamps, electrofluorescent lamps, etc. (refer also to 19.1.4 of Part XI "Electrical Equipment").

**8.5.5.3** The LLL system shall function at all times for at least 1 h after its activation. All systems, including those automatically activated or continuously operating, shall be capable of being manually activated by a single action from the main control station.

**8.5.5.4** In all passageways, the LLL shall be continuous except as interrupted by corridors and cabin doors in order to provide a visible delineation along the escape route. The LLL shall be installed at least on one side of the corridor, either on the bulkhead within 300 mm of the deck, or on the deck within 150 mm of the bulkhead. In corridors more than 2 m wide, LLL shall be installed on both sides. In dead-end corridors, LLL shall have arrows placed at intervals of no more than 1 m, or equivalent direction indicators, pointing away from the dead-end.

**8.5.5.5** In all stairways, LLL shall be installed on at least one side at a height less than 300 mm above the steps. LLL shall be installed on both sides if the width of the stairway is two metres or more. The top and bottom of each set of stairs shall be identified to show that there are no further steps.

**8.5.5.6** In all passenger cabins, a placard explaining the LLL system shall be installed on the inside of the cabin door. It shall also have a diagram showing the location of, and the way to, the two closest exits with respect to the cabin.

Materials used in the manufacture of LLL products shall not contain radioactive or toxic materials.

**8.5.5.7** LLL shall indicate the exit door handle; other doors shall not be indicated so.

Sliding, fire-proof and watertight doors shall be provided with LLL sign showing the way of the door opening.

LLL signs shall be also provided at all doors and means of escape. The signs shall be located at a height of 300 mm above the deck or the bottom of the door and be contrast in colour to the background on which they are marked.

All exit door and escape route signs shall be of photoluminescent materials or marked appropriately by lighting.

**8.5.5.8** Photoluminescent (PL) material strips shall be not less than 75 mm wide. The strips having a width less than that stated herein shall be used only if their luminance is increased proportionally to compensate for their width. PL materials shall provide at least 15 mcd/m<sup>2</sup> measured 10 min after removal of all external illuminating sources. The system shall ensure luminance values greater than 2,0 mcd/m<sup>2</sup> for 1 h. Any PL system shall be provided with not less than the minimum level of ambient light necessary to charge the PL material to meet the above luminance requirements.

**8.5.5.9** Electrically powered LLL system shall comply with the requirements of 2.2.8.6.6 of Part VI "Fire Protection".

For ships having length of 120 m or more or having three or more main vertical zones the electrically powered LLL system shall also comply with the requirements of 2.2.7.4.3 of Part VI "Fire Protection".

**8.5.6 Additional requirements for means of escape on ro-ro passenger ships.**

**8.5.6.1** Handrails or other handholds shall be provided in all corridors along entire escape route, so that a firm handhold is available every step of the way, where possible, to the assembly stations and embarkation stations. Such handrails shall be provided on both sides of longitudinal corridors more than 1,8 m in width and transverse corridors more than 1 m in width. Particular attention shall be paid to the need to be able to cross lobbies, atriums and other large open spaces along escape routes. Handrails and other handholds shall be of such strength as to withstand a distributed horizontal load of 750 N/m applied in

the direction of the centre of the corridor or space, and a distributed vertical load of 750 N/m applied in downward direction. There is no need to apply the two loads simultaneously.

**8.5.6.2** Means of escape shall not be obstructed by furniture and other obstructions, with the exception of tables and chairs which may be cleared away to provide open space. Cabinets and other heavy pieces of furniture in public spaces and along escape routes shall be secured in place to prevent shifting if the ship rolls or lists. Floor coverings shall also be secured in place. When the ship is underway, means of escape shall be kept clear of obstructions.

**8.5.6.3** Means of escape shall be provided from every normally occupied space on the ship. These means of escape shall be arranged so as to provide the shortest route possible to the assembly stations and survival craft embarkation stations and shall be marked with appropriate symbols.

**8.5.6.4** Where enclosed spaces adjoin an open deck, openings from the enclosed space to the open deck shall, where it is practicable, be capable of being used as an emergency exit.

**8.5.6.5** Decks shall be sequentially numbered, starting with "1" at the tank top or the lowest deck. These numbers shall be prominently displayed at stair landings and lifts in the lobbies. Decks may also be named, but the deck number shall always be displayed along with the name.

**8.5.6.6** Simple and clear plans showing the "you are here" position and means of escape marked by arrows shall be prominently displayed on the inside of each cabin door and in public spaces.

**8.5.6.7** Cabin and stateroom doors shall not require keys to be unlocked from the inside. Neither shall there be any doors along any designed escape route which require keys to be unlocked.

**8.5.6.8** The lowest 0,5 m of bulkheads along escape routes shall be able to sustain a load of 750 N/m to allow them to be used as walking surfaces with the ship at large angles of heel.

**8.5.6.9** The escape routes from cabins to stairway enclosures shall be as direct as possible, with a minimum number of direction changes. It shall not be necessary to cross from one side of the ship to the other to reach means of escape. It shall not be necessary to climb more than two decks up or down to reach an assembly station or open deck from any passenger space.

**8.5.6.10** External means of escape to the survival craft embarkation stations shall be provided from all open decks, referred to in [8.5.6.9](#).

## 8.6 GUARD RAILS, BULWARK AND GANGWAYS

**8.6.1** All exposed parts of the freeboard decks, superstructure decks and deckhouse tops shall be provided with efficient guard rails or bulwarks; in case of ships intended for carriage of timber deck cargo collapsible railing or storm rails shall be fitted on this cargo.

**8.6.2** The height of the bulwark or guard rails above the deck shall not be less than 1 m. However, where this height would interfere with the normal operation of the ship, a lesser height may be approved provided the adequate protection of passengers and crew is ensured to the satisfaction of the Register.

**8.6.3** The distance between the stanchions of the guard rails shall be not more than 1,5 m. At least every third stanchion shall be supported by a stay.

Removable and hinged stanchions shall be capable of being locked in the upright position.

It is allowed to use flat steel stanchions with increased breadth at the stanchion weld to the deck. [Fig. 8.6.3](#) shows the installation diagram and the spacing between the stanchions depending on the breadth of the lower edge to be welded to the deck. In places of such stanchions weld to the deck, the deck shall be supported by a minimum 100×12 mm stiffener. For deck plating exceeding 20 mm the support may be omitted.




Fig. 8.6.3:

- Notes: 1. Where  $kb \geq 2,9b$  — at least every third stanchion shall be of increased breadth.  
 2. Where  $2,4b \leq kb \leq 2,9b$  — at least every second stanchion shall be of increased breadth.  
 3. Where  $1,9b \leq kb \leq 2,4b$  — at least every stanchion shall be of increased breadth.

The stanchion breadth  $b$ , shall be chosen according to the design standards

**8.6.4** The gunwale, hand rails and guard rails shall be generally of rigid construction; wire ropes may only be accepted in lieu of guard rails in special circumstances and then only in limited lengths; wire ropes shall be made taut by means of turn-buckles.

Lengths of chains may only be accepted in lieu of rigid guard rails if they are fitted between two fixed stanchions or between the fixed stanchion and bulwark.

**8.6.5** The opening below the lowest course of the guard rails shall not exceed 230 mm. The other courses of rails shall not be more than 380 mm apart.

An exception is made for the guard rails above the timber deck cargo where the height from the base to the lowest course and other course spacings shall not exceed 330 mm. In the case of ships with rounded gunwale, the guard rail supports shall be placed on the flat of the deck.

**8.6.6** Type "A" ships with bulwarks as well as type "B" ships with a freeboard reduced to that required for type "A" ships shall have open rails fitted for at least half the length of the exposed parts of the weather deck, or other effective water freeing arrangements. The upper edge of the sheerstrake shall be kept as low as practicable.

Where superstructures are connected by trunks, open rails shall be fitted for the whole length of the exposed parts of the freeboard deck.

**8.6.7** The bulwark, if arranged, shall comply with the requirements of 2.14 of Part II "Hull".

**8.6.8** Satisfactory means (in the form of life lines, gangways, underdeck passages, etc.) shall be provided for the protection of the crew in getting to and from their accommodation spaces, the machinery space and all other parts used in the necessary work of the ship.

**8.6.9** A fore and aft permanent gangway shall be provided on type "A" ships at the level of the superstructure deck between the poop and the midship superstructure or deckhouse, where fitted, or equivalent means of access shall be provided to carry out the purpose of the gangway, such as underdeck passages. The width of the passages shall be not less than 1 m. The gangways over the entire length of the plating on either side shall be fitted with longitudinal guarding bars. Reliable guard rails, the dimensions of which shall comply with the requirements of [8.6.2](#), [8.6.3](#) and [8.6.5](#) of this Part, and 3.5.5.2 of Part II "Hull" shall be provided.

The gangways shall be constructed of a fire-resisting material, and the plating shall be made, in addition, of a non-slip material.

The plating may be manufactured of fibre reinforced plastic provided it complies with the requirements of 6.9 of Part XIII "Materials".

In ships not having a midship superstructure arrangements to the satisfaction of the Register shall be made to safeguard the crew in reaching all parts of the ship while at sea.

**8.6.10** Safe and convenient ladders from the level of the gangways to the deck shall be provided; they shall not be spaced more than 40 m apart.

Where the length of the deck is more than 70 m, special tripartite shelters (bow — sides) shall be provided along the gangways or other means of access for protection of the crew from bad weather. Such shelters shall be designed for at least one person and shall be spaced not more than 45 m apart. Pipes or other deck equipment shall not impede safe passage.

**8.6.11** Requirements of [8.6.1 — 8.6.10](#) are not applied to the shipborne barges (lighters), barges and other non-self-propelled ships unmanned.

## **8.7 HOISTING GEAR OF SHIPBORNE BARGES**

**8.7.1** The elements of the hoisting gear of the shipborne barges to be lifted by the crane on board the barge carrier (lugs, eye plates, rings, shackles, grips, etc.) shall be designed to withstand the forces resulting from lifting the shipborne barge uniformly loaded with the specification cargo and gripped in two points diagonally positioned. Under these forces the stresses in the elements of the hoisting gear shall not exceed 0,7 times the upper yield stress of material.

## **8.8 PILOT TRANSFER ARRANGEMENTS, MEANS OF EMBARKATION AND DISEMBARKATION**

**8.8.1** The requirements of this Chapter apply to all ships except for ships of less than 500 gross tonnage and fishing vessels.

**8.8.2** Ships engaged on voyages in the course of which pilots are likely to be employed shall be provided with pilot transfer arrangements. Construction and position of pilot transfer arrangements shall comply with the requirements specified in regulation V/23 of SOLAS-74, as amended (hereinafter, SOLAS), and IMO resolutions A.1045(27) and A.1108(29).

Interpretation: sub-paragraphs 1 and 2 of SOLAS regulation V/23.3.3 address two different and distinct arrangements — the former when only a pilot ladder is used; — the latter when a combined arrangement of "an accommodation ladder used in conjunction with the pilot ladder" is used.

The length of climb on a single ladder shall be not more than 9 m regardless of the trim or list of the ship.

Shipside doors used for pilot transfer shall not open outwards.

SOLAS regulation V/23.3.3.2 and Section 3 of IMO resolution A.1045(27) apply to a combined arrangement of "an accommodation ladder used in conjunction with the pilot ladder" for "safe and convenient access to, and egress from, the ship" for which a 15° list requirement does not apply.

**8.8.3** The construction of means of embarkation and disembarkation shall comply with the requirements of IMO circular MSC.1/Circ.1331.

## **9 EMERGENCY OUTFIT**

### **9.1 GENERAL**

**9.1.1** The requirements of this Section are optional. The shipowner, at his discretion, shall determine the necessity and completeness of emergency outfit on board, considering its service area, dimensions as well as national standards of the flag state.

**9.1.2** The items listed in [Tables 9.2.1](#), [9.2.2-1](#), [9.2.2-2](#) and [9.2.3](#) available in the ship, but intended for other purposes may be included into the emergency outfit, provided these items have corresponding markings and their permanent storage places are situated above the bulkhead deck.



## 9.2 EMERGENCY OUTFIT REQUIRED

**9.2.1** All ships except those specified in [9.2.4](#) and [9.2.6](#) shall have emergency outfit in the scope not less than listed in [Table 9.2.1](#).

For the unmanned non-self-propelled ships no emergency outfit is required. The manned non-self-propelled ships shall be supplied with the emergency outfit in accordance with [9.2.10](#) like floating docks with no permanent direct communication with the shore.

Table 9.2.1

Nos.	Item, unit	Size	Quantity for ships of length <i>L</i> , in m				Quantity for tankers <sup>1</sup>
			150 and over	from 150 to 70 incl.	from 70 to 24 incl.	below 24	
1	Armoured collision mat, pc	4,5×4,5 m	1	—	—	—	—
2	Lightened collision mat, pc	3,0×3,0 m	—	1	—	—	1
3	Thrummed collision mat, pc	2,0×2,0 m	—	—	1	—	—
4	Thrummed pad, pc	0,4×0,5 m	4	3	2	1	2
5	Set of rigging tools	as per Table 9.2.3	1	1	1	1	1
6	Set of fitter's tools	as per Table 9.2.3	1	1	1	1	1
7	Pine bar, pc	150×150×4000 mm	8	6	—	—	—
8	Pine bar, pc	80×100×2000 mm	2	2	4	—	4
9	Pine plank, pc	50×200×4000 mm	8	6	2	—	—
10	Pine plank, pc	50×200×2000 mm	4	2	2	—	2
11	Pine wedge, pc	30×200×200 mm	10	6	4	—	4
12	Birch wedge, pc	60×200×400 mm	8	6	4	—	4
13	Pine plugs for ships with side scuttles, pc	side scuttle diameter	6	4	2	2	4
14	Pine plugs, pc	10×30×150 mm	10	6	4	2	4
15	Unbleached canvas, m <sup>2</sup>	—	10	6	4	2	—
16	Coarse felt, m <sup>2</sup>	10 mm in thickness	3	2	1	—	—
17	Rubber plate, m <sup>2</sup>	5 mm in thickness	2	1	0,5	—	0,5
18	Tarred tow, kg	—	50	30	20	10	5
19	Wire (low-carbon steel), pc	3 mm in dia, coils, 50 m each	2	2	1	—	1
20	Construction shackles, pc	12 mm in dia	12	8	4	—	4
21	Hexagon-head bolt, pc	M16×400 mm	10	6	2	—	—
22	Hexagon-head bolt, pc	M16×260 mm	4	2	2	2	—
23	Hexagonal nut, pc	M16	16	10	6	4	—
24	Washer for bolt, pc	M16	32	20	12	8	—
25	Construction nails, kg	70 mm long	4	3	2	1	1
26	Construction nails, kg	150 mm long	6	4	2	1	1
27	Cement (quick setting), kg	—	400	300	100	100	100
28	Sand, natural, kg	—	400	300	100	100	100
29	Accelerator for concrete setting, kg	—	20	15	5	5	5
30	Minium, kg	—	15	10	5	5	5
31	Technical fat, kg	—	15	10	5	—	5
32	Carpenter's axe, pc	—	2	2	1	1	1
33	Saw, cross-cut, pc	1200 mm in length	1	1	1	—	—
34	Hack-saw, pc	600 mm in length	1	1	1	1	1
35	Shovel, pc	—	3	2	1	1	1
36	Bucket, pc	—	3	2	1	1	1
37	Sledge hammer, pc	5 kg	1	1	1	—	—
38	Lantern of explosion-proof type, pc	—	1	1	1	1	1
39	Stop of telescopic type, pc	—	3	2	1	1	1
40	Emergency screw clamp, pc	—	2	1	1	—	—

<sup>1</sup> Whatever the ship length, ice class and navigation area are.

**9.2.2** Additional set of emergency outfit, above that listed in [Table 9.2.1](#), shall be provided:

in accordance with [Table 9.2.2-1](#) for passenger and special purpose ships, of 70 m in length and over, except for fiber-reinforced plastic ships;

in accordance with [Table 9.2.2-2](#) for fiber-reinforced plastic ships.

Table 9.2.2-1

Nos.	Item	Quantity
1	Portable autogenous cutting torch complete with set of fully charged gas cylinders	1
2	Hand jack, hydraulic	1
3	Blacksmith's sledge hammer	1
4	Forge chisel with haft	1
5	Crowbar	2
6	Jack 9,8 kN	1
7	Jack 19,6 kN	1

Table 9.2.2-2

Nos.	Item	Quantity
1	Glass fabric	25 m <sup>2</sup>
2	Glass roving	3 kg
3	Resin binder with hardener	5 kg

**9.2.3** The sets of rigging and fitter's tools specified in [Table 9.2.1](#) shall be completed according to [Table 9.2.3](#).

Table 9.2.3

Nos.	Item	Size	Quantity per set	
			rigging	fitter's
1	Tape measure	2000 mm long	1	–
2	Bench hammer	0,5 kg	1	1
3	Sledge hammer	3,0 kg	–	1
4	Rigger's mallet	–	1	–
5	Puncher (dumb iron)	–	1	–
6	Chisel	20 mm wide, 200 mm long	1	1
7	Marline spike	300 mm long	1	–
8	Carpenter's chisel	20 mm wide	1	–
9	Screw auger	18 mm in dia	1	–
10	Tongs	200 mm long	1	–
11	Hollow punch	18 mm in dia	–	1
12	Hollow punch	25 mm in dia	–	1
13	Triangular file	300 mm long	–	1
14	Half-round file	300 mm long	–	1
15	Multi-purpose tongs	200 mm long	–	1
16	Screw driver	10 mm wide	–	1
17	Adjustable wrench	Jaw width up to 36 mm	–	1
18	Wrench	Jaw width of 24 mm	–	1
19	Rigger's knife	–	1	–
20	Hack-saw frame	–	–	1
21	Hack-saw blade	–	–	6
22	Kit-bag	–	1	1

**9.2.4** For ships of restricted areas of navigation **R1**, **R2-RSN**, **R2-RSN(4,5)** and **R3-RSN** except those specified in [9.2.5](#), equipment with emergency outfit and materials may be laid down as for the nearest lower group of ship's division depending on their length according to [Table 9.2.1](#).

The minimum amount of emergency outfit for ships of restricted area of navigation **R3** shall be determined by the shipowner.

**9.2.5** For **Arc5**, **Arc6**, **Arc7**, **Arc8** and **Arc9** ice class ships, equipment with emergency outfit and materials shall be established as for the nearest higher group of ship's division according to their length as per [Table 9.2.1](#).

**9.2.6** For fiber-reinforced plastic ships provision of emergency outfit listed under [items 6, 9, 17, 21 — 24, 26 — 29, 31, 35, 36, 39, and 40](#) of [Table 9.2.1](#) is not required.

**9.2.7** In ships intended to carry flammable and explosive cargoes tools of emergency outfit shall be made of non-sparking materials wherever practicable.

**9.2.8** The tugs of restricted area of navigation **R3** need not be equipped with emergency outfit, except for the sets of rigging and fitter's tools required in accordance with [Table 9.2.3](#).

**9.2.9** For tugs of unrestricted service and restricted area of navigation **R1** with ice class **Arc5** and higher category equipment with emergency outfit and materials shall be established as for the nearest higher group according to [Table 9.2.1](#).

**9.2.10** The floating docks which are not in permanent direct communication with the shore shall have emergency outfit as indicated under [items 5, 6, 19 — 26, 32 — 34 and 37](#) of [Table 9.2.1](#), length of the floating dock *L* being taken in this case instead of the ship's length *L*.

The floating docks which are in permanent direct communication with the shore need not be provided with emergency outfit.

**9.2.11** For berth-connected ships, the emergency outfit shall be chosen by the owner.

**9.2.12** Ships having distinguishing marks **FF1**, **FF1WS**, **FF2**, **FF2WS**, **FF3** and **FF3WS** in the class notation shall have two searchlights capable of providing an efficient horizontal and vertical range of illumination of a surface not less than 10 m in diameter at a distance up to 250 m at the minimum illumination intensity up to 50 lx at dark time and clear atmosphere.

### **9.3 STORAGE OF EMERGENCY OUTFIT**

**9.3.1** The emergency outfit indicated in [9.2](#) shall be stored at least in two emergency stations, one of which shall be situated in the machinery space. Emergency stations may be special spaces, boxes or places allocated on the deck or in spaces.

In the emergency station of the machinery space the outfit necessary for carrying out the emergency operations inside the space shall be stored; the rest of the emergency outfit shall generally be stored in the emergency stations located above the bulkhead deck; in ships of less than 45 m in length it is allowed to locate the emergency station below the bulkhead deck on condition that free access to this station is provided at all times.

In ships of 31 m in length and below it is allowed to store the emergency outfit only in one emergency station.

**9.3.2** A free passage shall be provided in front of the emergency station; the passage width shall be selected depending on the overall dimensions of the outfit stored in the station but not less than 1,2 m. In ships of less than 70 m in length the passage width is allowed to be reduced to 0,8 m and in ships of 31 m in length and below to 0,6 m.

The passages to the emergency stations shall be as straight and short as practicable.

#### **9.4 MARKING**

**9.4.1** Items of the emergency outfit and cases for their storage (apart from collision mats) shall be painted blue either entirely or in a stripe. The cases for emergency equipment storage shall have the distinct inscription to indicate the name of the material, weight and warranted storage period.

**9.4.2** The emergency stations shall be provided with distinct inscriptions "Emergency Station". Moreover, in the passages and on the decks notices shall be posted showing location of the emergency stations.

## 9.5 COLLISION MATS

**9.5.1** Collision mats shall be made of water-resistant canvas or other equivalent fabric and be provided with either a soft or wire interlayer depending on the type of the collision mat. The collision mats shall be edged by a leech rope with four thimbles fitted into its corners. Moreover, cringles shall be provided according to the number of ropes specified in [Table 9.5.1](#).

Basic data on the collision mats are given in [Table 9.5.1](#) and [Fig. 9.5.1](#).




Fig. 9.5.1

Table 9.5.1

Nos.	Item	Quantity		
		Armoured collision mat, 4,5×4,5 m	Lightened collision mat, 3,0×3,0 cm	Thrummed collision mat, 2,0×2,0 m
1	Canvas layers	4	2	2
2	Interlayer	1 wire net with leech rope	1 felt padding	1 pad
3	Fastening of stiffeners	—	In pockets (pieces of wire rope or pipes)	—
4	Sheets	2	2	2
5	Hogging lines	3	2	2
6	Guys	2	2	—
7	Control lanyard with marking	1	1	1
8	Shackles	12	9	6
9	Tackles (safe working load)	4 (14,7 kN)	2 (9,8 kN)	2 (9,8 kN)
10	Snatch blocks (safe working load)	4 (14,7 kN)	2 (9,8 kN)	2 (9,8 kN)

**9.5.2** The pads shall be made of natural fibre rope strands and be thrummed with natural fibre spun yarn. A canvas shall be sewn on the bottom side of the pad.

**9.5.3** Sheets and guys of armoured collision mats shall be made of flexible steel wire ropes, control lanyards — of natural fibre ropes and hogging lines for all collision mats — of flexible steel wire ropes or chains having suitable diameter.

Wires of steel ropes shall have heavy zinc coating in accordance with the national standards.

The length of the sheets shall be chosen so that a hole may be shut up in any place of the shell plating and the ends of the ropes may be efficiently secured on the deck.

Breaking strength of the whole sheets shall exceed that of the leech ropes by not less than 25 %.

**9.5.4** The blocks of emergency outfit may have hooks as hangers. The permissible load of the shackles joining the ropes shall not be less than 0,25 times the breaking load of the whole ropes referred to above.

## APPENDIX

**CALCULATION OF THE WIDTH OF STAIRWAYS FORMING MEANS OF ESCAPE  
ON PASSENGER SHIPS AND ON SPECIAL PURPOSE SHIPS CARRYING  
MORE THAN 60 PERSONS**

1. The calculation method considers evacuation from enclosed spaces within each main vertical zone individually and takes into account all of the persons using the stairway enclosures in each zone, even if they enter that stairway from another main vertical zone.

2. For each main vertical zone the calculation shall be completed for the night time (case 1) and day time (case 2) and the largest dimension from either case used for determining the stairway width for each deck under consideration.

3. For multi-deck ships, the total stairway width  $W$ , in mm, which allows for the timely flow of persons evacuating from adjacent decks is determined using the following calculation method:

when joining two decks

$$W = (N_1 + N_2) \cdot 10; \quad (3-1)$$

when joining three decks

$$W = (N_1 + N_2 + 0,5N_3) \cdot 10; \quad (3-2)$$

when joining four decks

$$W = (N_1 + N_2 + 0,5N_3 + 0,25N_4) \cdot 10 \quad (3-3)$$

where  $N_1$  = the number of persons to be evacuated from deck with the largest number of persons using the stairway;

$N_2$  = the number of persons to be evacuated from the deck with the next largest number of persons directly entering the stairway etc., i.e.  $N_1 > N_2 > N_3 > N_4$ .

When joining five or more decks, the total stairway width shall be determined by [Formula \(3-3\)](#) with regard for the number of tiers and their capacity ([refer to Fig. 3-1](#)).

The calculated value of  $W$  may be reduced where available landing area is provided in stairways at the deck level ([refer to Fig. 3-2](#)).

The doors to the muster station shall have an aggregate width of at least  $D = 900 + 9355 = 10255$ .






Fig. 3-1

Minimum stairway width calculation example:

Deck 1:  $N_1 = 200$ , $W = 200 \times 10 = 2000$ ;Deck 2:  $N_1 = 200$ ,  $N_2 = 50$ , $W = (200 + 50) \times 10 = 2500$ ;Deck 3:  $N_1 = 200$ ,  $N_2 = 158$ ,  $N_3 = 50$ , $W = (200 + 158 + 0,5 \times 50) \times 10 = 3830$ ;Deck 4:  $N_1 = 425$ ,  $N_2 = 200$ ,  $N_3 = 158$ ,  $N_4 = 50$ , $W = (425 + 200 + 0,5 \times 158 + 0,25 \times 50) \times 10 = 7165$ ;Deck 5:  $N_1 = 425$ ,  $N_2 = 419$ ,  $N_3 = 158$ ,  $N_4 = 50$ , $W = (425 + 419 + 0,5 \times 158 + 0,25 \times 50) \times 10 = 9355$ ;Deck 7:  $N_1 = 200$ , $W = 900$




Fig. 3-2

Landing calculation for stairway width reduction:

1 — handrail on both sides of the stairway;

2 — intermediate landing;

3 — necessary flow area for accessing the flow on the stairs;

4 — door area;

$P = S \times 3 \text{ persons/m}^2$  = the number of persons taking refuge on the landing to a maximum value of  $P = 0,25Z$ ;

$N = Z - P$  = the number of persons directly entering the stairway flow from a given deck;

$Z$  = the number of persons to be evacuated from the deck considered;

$S$  = available landing area, in  $\text{m}^2$ , after subtracting the surface area necessary for movement and subtracting the space taken by the door swing area;

$D$  = width of exit doors to the stairway landing area, in mm

4. The stairway shall not decrease in width in the direction of evacuation to the muster station, except in the case of several muster stations in one main vertical zone the stairway width shall not decrease in the direction of the evacuation to the most distant muster station.

5. Where the passengers and crew are held at a muster station which is not at the survival craft embarkation position the dimensions of stairway width and doors from the muster station to this position shall be based on the number of persons in the controlled groups. The width of these stairways and doors need not exceed 1500 mm unless larger dimensions are required for evacuation from these spaces under normal conditions.

6. The calculations of stairway width shall be based upon the crew and passenger load on each deck. For the purpose of the calculation the maximum capacity of a public space shall be defined by either of the following two values: the number of seats or similar arrangements, or the number obtained by assigning  $2 \text{ m}^2$  of gross deck surface area to each person.

7. The dimensions of the means of escape shall be calculated on the basis of the total number of persons expected to escape by the stairway and through doorways, corridors and landing ([refer to Fig. 7](#)).

Calculations shall be made separately for the two cases of occupancy of the spaces specified below. For each component part of the escape route, the dimension taken shall not be less than the largest dimension determined for each case:

**Case 1:**

passengers in cabins with maximum berthing capacity fully occupied;  
members of the crew in cabins occupied to 2/3 of maximum berthing capacity;  
service spaces occupied by 1/3 of the crew;

**Case 2:**

passengers in public spaces occupied to 3/4 of maximum capacity;  
members of the crew in public spaces occupied to 1/3 of maximum capacity;  
service spaces occupied by 1/3 of the crew;  
crew accommodation occupied by 1/3 of the crew.




Fig. 7

Occupant loading calculation example:

- 1 — public space;
- 2 — landing credit area;
- 3 — door area;

DOWN, UP = stairway flow path  
for upper space:

$$Z_{(pers.)} = \frac{25 \text{ m} \cdot 8 \text{ m}}{2 \text{ m}^2} = 100; N_{(pers.)} = 100 \cdot 0,75 = 75;$$

for lower space:

$$Z_{(pers.)} = \frac{25 \text{ m} \cdot 10 \text{ m}}{2 \text{ m}^2} = 125; N_{(pers.)} = 125 \cdot 0,75 = 93$$

**8.** The maximum number of persons contained in a vertical zone including persons entering stairways from another main vertical zone shall not be assumed to be higher than the maximum number of persons authorized to be carried on board for the calculation of the stairway width only.

## **ADDITIONAL REQUIREMENTS**

1. The aggregate width of stairway exit doors to the muster station shall not be less than the aggregate width of stairways serving this deck.
2. Means of escape plans shall be provided indicating the following:
  - .1 the number of crew and passengers in all normally occupied spaces;
  - .2 the number of crew and passengers expected to escape by the stairway and through doorways, corridors and landing;
  - .3 muster stations and survival craft embarkation positions;
  - .4 primary and secondary means of escape;
  - .5 width of stairways, doors, corridors and landing areas.
3. Means of escape plans shall be accompanied by detailed calculations for determining the width of escape stairways, doors, corridors and landing areas.

Russian Maritime Register of Shipping

**Rules for the Classification and Construction of Sea-Going Ships**  
**Part III**  
**Equipment, Arrangements and Outfit**

FAI "Russian Maritime Register of Shipping"  
8, Dvortsovaya Naberezhnaya,  
191186, St. Petersburg,  
Russian Federation  
[www.rs-class.org/en/](http://www.rs-class.org/en/)